



Robert F. McDonnell
Governor

James S. Cheng
Secretary of Commerce
and Trade

COMMONWEALTH of VIRGINIA

DEPARTMENT OF
HOUSING AND COMMUNITY DEVELOPMENT

William C. Shelton
Director

MEMORANDUM

TO: BHCD Codes and Standards Committee
FSB/BHCD Statewide Fire Prevention Code Development Committee

FROM: Emory Rodgers, Deputy Director *em*
Division of Building and Fire Regulation

DATE: December 6, 2012

SUBJECT: BHCD Codes and Standards Committee and FSB/BHCD Statewide Fire
Prevention Code Development Committee meeting – December 20, 2012

The FSB/BHCD Statewide Fire Prevention Code Development Committee and the BHCD Codes and Standards Committee will meet separately on December 20, 2012 at the Virginia Housing Center starting. The SFPC Development Committee will begin at 10:00 a.m., followed by the Codes and Standards Committee meeting. The purpose for each of the meetings will be to review the SFPC and USBC base documents and to approve 2012 SFPC and USBC/related regulatory code changes that have been submitted for inclusion into the 2012 SFPC and USBC/related regulations.

These include administrative and technical provisions vetted with stakeholders and deemed to be consensus code changes. There will also be discussion for each committee of some potential issues that have been identified and are still being further reviewed with stakeholders in an attempt to gain consensus.

Additional committee meetings will be scheduled for March 25, 2013 and April 22, 2013 for review of these issues as code changes are submitted to approve or deny for the proposed 2012 SFPC and USBC/related regulations. Each committee will have the option of hearing brief public comments at these meetings.

CC: Billy Shelton, VDFP
Bill Shelton, DHCD
Ed Altizer, SFMO
Vernon Hodge, DHCD
Cindy Davis, DHCD
Janice Firestone, DHCD

Partners for Better Communities



www.dhcd.virginia.gov

AGENDA
CODES AND STANDARDS COMMITTEE
BOARD OF HOUSING AND COMMUNITY DEVELOPMENT
Thursday, December 20, 2012
Virginia Housing Center, Glen Allen, VA
(immediately following the 10:00 FSB/BHCD Statewide Fire
Prevention Code Development Committee meeting)

- I. OPENING
Call to Order
Anthony Clatterbuck

- II. REGULATORY CYCLE
a. 2012 Code Change Cycle – Book 2
b. Letter from NVRC (2012 IECC)
Anthony Clatterbuck

- III. NEW BUSINESS
Anthony Clatterbuck

- IV. FUTURE BOARD MEETINGS
Anthony Clatterbuck
a. Monday, January 28, 2013 – BHCD Meeting – (no committee meeting)
b. Monday, March 25th 2013 – BHCD SFPC Development Committee
Codes and Standards Committee
BHCD meeting

- V. ADJOURNMENT
Anthony Clatterbuck

(Note: the committee will break for lunch from 12:00 to 12:30)



Northern Virginia Regional Commission

Chairman

Hon. Martin E. Nohe

Vice Chairman

Hon. Robert W. Lazaro, Jr.

Treasurer

Hon. Redella S. Pepper

Executive Director

G. Mark Gibb

November 1, 2012

County of Arlington

Hon. Jay Fissette

Hon. Libby Garvey

County of Fairfax

Hon. Sharon Bulova

Hon. John C. Cook

Hon. Penelope A. Gross

Hon. Pat Hermy

Hon. Catherine M. Huggins

Hon. Jeffrey C. McKay

Hon. Linda Smyth

County of Loudoun

Hon. Janet Clarke

Hon. Scott K. York

County of Prince William

Hon. Peter Candland

Hon. Martin E. Nohe

Hon. Frank J. Principi

City of Alexandria

Hon. Redella S. Pepper

Hon. Paul C. Smedberg

City of Fairfax

Hon. Scott Silverthorne

City of Falls Church

Hon. Nader Baroukh

City of Manassas

Hon. Harry J. Parrish II

City of Manassas Park

Hon. Suhas Naddoni

Town of Dumfries

Hon. Gerald M. Foreman II

Town of Herndon

Hon. Lisa C. Merkel

Town of Leesburg

Hon. Fernando "Marty" Martinez

Town of Purcellville

Hon. Robert W. Lazaro, Jr.

Town of Vienna

Hon. M. Jane Seeman

(as of July 18, 2012)

Mr. Anthony Clatterbuck

Chairman

Board of Housing and Community Development

600 East Main Street, Suite 300

Richmond, VA 23219

Dear Mr. Clatterbuck:

The Northern Virginia Regional Commission (NVRC) adopted a regional energy strategy that includes actions to increase the efficiency of the built environment. This strategy supports goals adopted by local governments across the region that call for improving the energy efficiency of their communities. Adoption of the 2102 International Energy Conservation Code (IECC) as part of the update to the Uniform Statewide Building Code (USBC) is a critical step to increase the efficiency of buildings consistent with these goals.

NVRC recognizes the value that the USBC offers to Virginia by providing a consistent building code across the Commonwealth. However, when the General Assembly created the requirement for the USBC, superseding local government building codes, it charged you with the responsibility of meeting the needs of local governments and their residents through the statewide code.

Northern Virginia is part of the National Capital Region building market. The state of Maryland has already adopted the 2012 IECC and the District of Columbia is moving towards adopting the 2012 IECC. Due to the lower energy bills and short payback on the increased construction costs related to the 2012 IECC, building owners and occupants in Virginia would be at a disadvantage to those in other parts of the National Capital Region if Virginia does not also adopt the 2012 IECC.

Adopting the 2012 IECC also is consistent with the direction at §36-99 of the *Code of Virginia* that the USBC shall provide that "... buildings and structures should be permitted to be constructed, rehabilitated and maintained at the least possible cost consistent with recognized standards of health, safety, energy conservation and water conservation, ..." and that "... the Board shall have due regard for generally accepted standards as recommended by nationally recognized organizations, including, but not limited to, the standards of the International Code Council..."

Therefore, the Northern Virginia Regional Commission adopted the enclosed resolution "In Support of Adoption of the 2012 International Energy Conservation Code as part of the Uniform Statewide Building Code" at its October 25, 2012, meeting.

Mr. Anthony Clatterbuck
Page two
November 1, 2012

We recognize the Board may need to make some administrative or non-substantive technical changes to the IECC, such as have been proposed by the Virginia Building & Code Officials Association, but urge you to adopt the substantive requirements of the 2012 IECC as the basis of the energy provision of the USBC.

I am respectfully communicating this Resolution to you. Please let me know if you have any questions.

Sincerely,



G. Mark Gibb
Executive Director

GMG/SW/ls
Enclosure

cc: Mr. William Shelton, Director, DHCD
Mr. Emory Rodgers, Deputy Director, DHCD Division of Building and Fire Regulation
Mr. Jim Hyland, District 8 Board representative
Mr. J.P. Carr, District 10 Board representative
Mr. Tito Munoz, District 11 Board representative



Northern Virginia Regional Commission

RESOLUTION

Resolution No. 13-05

PATRON: G. Mark Gibb
Executive Director
DATE: October 25, 2012

IN SUPPORT OF ADOPTION OF THE 2012 INTERNATIONAL ENERGY CONSERVATION CODE AS PART OF THE UNIFORM STATEWIDE BUILDING CODE

WHEREAS, the Virginia Board of Housing and Community Development updates the Uniform Statewide Building Code on a three-year cycle; and

WHEREAS, the Board is developing the 2013 amendments to the Virginia Uniform Statewide Building Code, using the 2012 International Building Code, adopted by the International Code Commission, as the basis for the state code; and

WHEREAS, a critical component of the new International Building Code is the 2012 International Energy Conservation Code; and

WHEREAS, adoption of the 2012 International Energy Conservation Code will result in a 15 percent improvement in energy performance of residential and commercial buildings as compared to the 2009 Code and a 30 percent improvement as compared to the 2006 Code; and

WHEREAS, Northern Virginia Regional Commission member local governments have established goals to substantially reduce energy and resulting emissions; and

WHEREAS, building-based energy use accounts for approximately two-thirds of energy used in Northern Virginia, so improving the energy performance of buildings will be critical to meeting these energy goals; and

WHEREAS, the increased energy efficiency from the 2012 International Energy Efficiency Code would result in homeowners recovering increased construction costs in 20 months (increased construction costs of \$2,179 for an average new home in Virginia would result in an increased down payment of \$440 and an increase of \$8 in monthly mortgage payments, offset by average monthly energy savings of \$31); and

WHEREAS, reducing energy use in the region's buildings not only saves money on energy bills but also reduces the peak demand for energy, lessening the need to increase rates to pay for investments in new electric generation and other energy systems; and

WHEREAS adopting the 2012 International Energy Conservation Code is a critical step to increase the efficiency of the building stock and will create a level minimum standard for construction across the Northern Virginia region, the state, and the National Capital Region; and

THEREFORE BE IT RESOLVED, that the Northern Virginia Regional Commission recommends that the Commonwealth of Virginia adopt the 2012 International Energy Conservation Code as the basis of the energy provisions of the Uniform Statewide Building Code;


Resolution No. 13-05, continued
October 25, 2012

BE IT FURTHER RESOLVED, that the Executive Director communicates this recommendation by letter to the Virginia Board of Housing and Community Development.



CERTIFICATION

The undersigned certifies that the foregoing is a true and correct copy of a resolution adopted at a legally convened meeting of the Northern Virginia Regional Commission on October 25, 2012.


G. Mark Gibb, Certifying Officer

BHCD CODES AND STANDARDS COMMITTEE
2012 CODE CHANGE CYCLE – BOOK 2
December 20, 2012

Opening Statement

TAB 1 – USBC Base document

TAB 2 - Consensus USBC Code Changes and Regulations: Approve individually or as a block

<u>Proposal</u>	<u>Description of Change</u>	<u>Page No.</u>
VCC 108.2 #2	Permit exemptions – accessory structures	1
VCC 108.2 #5	Permit exemptions - fences	2
VCC 108.2 #6	Permit exemptions – retaining walls	4
VCC 108.2 new #11	Permit exemptions - cemeteries	5
VCC 117.1	Temporary use	6
VCC 118	Unsafe buildings and structures	7
VCC118.3	Inspection report and notice of unsafe building or structure	11
VCC 119.1	Appeal board meetings	12
VCC 119.6	Appeal board hearing time period	13
VCC 108.1 and 3411.9.5	Restriping	14
VCC T1106.1	Accessible parking spaces	15
VCC 1106.3	Outpatient clinics and ambulatory health care facilities	16
VCC IECC R402.2.1	Ceilings with attic spaces	17
VCC IECC R402.2.4	Access hatches & doors	18
VCC IECC R402.3.6	Replacement fenestration	20
VCC IECC R402.4.1.2.1	Visual inspection option	21
VCC IECC R402.4.2	Fireplace – tight-fitting flue dampers	22
VCC IECC R404.1	Lighting equipment	23
VCC IRC R602.7	Headers	24
VCC IRC R602.10	Wall bracing	26
VCC IRC R1001.8	Refractory mortar	32
VCC IBC 3109.1	Swimming pools	33
VCC IBC 303.6	A-5 Swimming pools	34
VCC ISPSC 410.2	Showers	35
VCC IBC 907.2.3	Group E	37
VCC IPC Chapter 13	Gray water, rainwater and reclaimed water	39

USBC Non-consensus Issues

- Definitions – Nightclub and main use (TRB interpretation)
- Delete R2 sprinkler exception
- Assisted Living Facilities occupant classification
- Arc fault and GFCI outlets for garage door openers and freezers
- Type I hoods for commercial/residential cooking appliances
- IRC lighting fixtures 75% from 50% required for 2012
- IRC exterior wall R-19 from R-13 insulation
- Marinas bathroom fixtures (unless fixed at December 13th Workgroup 1 meeting)
- Emergency communication voice systems E occupancies
- M occupancies sprinkler threshold reduce from 12,000 to 5,000 s.f.

TAB 3**Virginia Rehabilitation Code (VRC) Change: Approve individually**

<u>Proposal</u>	<u>Description of Change</u>	<u>Page No.</u>
IRC 102.2	Move alterations to VRC	1 - 14

Virginia Maintenance Code (VMC) Change: Approve individually

<u>Proposal</u>	<u>Description of Change</u>	<u>Page No.</u>
VMC 602.2	Heating and cooling dates	15

TAB 4 - Manufactured Home Safety Regulations:

Recommendation – approve as proposed regulations for the April 22, 2013 BHCD meeting

TAB 5 – Industrialized Building Safety Regulations: Recommendation – approve as proposed regulations for the April 22, 2013 BHCD meeting

TAB 6- Virginia Amusement Device Regulations Base Document**TAB 7 – VADR Code Changes: Approve individually or as a block**

<u>Proposal</u>	<u>Description of Change</u>	<u>Page No.</u>
VADR Sections 20 and 75E	Certificate of inspection	1
VADR Section 30	Devices covered and exempt	2
VADR Section 75A	Fees	4
VADR Sections 75D, 200 and 210	Permit duration	5
VADR Section 75J	DGS	7
VADR Section 75J	Violations	8

VADR Non-consensus Issues:

- Generator fees
- Small mechanical rides and inflatables, yearly inspection
- Overall fees
- Clarification of phrase “open to the public”

TAB 8 - Updated Memorandums of Agreement

- Virginia Department of Health

New Business

TAB 1

Virginia Uniform State Building Code (USBC)

Base Document for 2012 Code (Starts with Virginia Code Commission database and adds amendments to use 2012 I-Codes, plus has editorial corrections)

Part I – Construction (VCC)

13VAC5-63-10. Chapter 1 Administration; Section 101 General.

A. Section 101.1 Short title. The Virginia Uniform Statewide Building Code, Part I, Construction, may be cited as the Virginia Construction Code. The term “USBC” shall mean the Virginia Construction Code unless the context in which the term is used clearly indicates it to be an abbreviation for the entire Virginia Uniform Statewide Building Code or for a different part of the Virginia Uniform Statewide Building Code.

Note: This code is also known as the ~~2009~~ 2012 edition of the USBC due to the use of the ~~2009~~ 2012 editions of the model codes.

B. Section 101.2 Incorporation by reference. Chapters 2 - 35 of the ~~2009~~ 2012 International Building Code, published by the International Code Council, Inc., are adopted and incorporated by reference to be an enforceable part of the USBC. The term “IBC” means the ~~2009~~ 2012 International Building Code, published by the International Code Council, Inc. Any codes and standards referenced in the IBC are also considered to be part of the incorporation by reference, except that such codes and standards are used only to the prescribed extent of each such reference. In addition, any provisions of the appendices of the IBC specifically identified to be part of the USBC are also considered to be part of the incorporation by reference.

Note 1: The IBC references ~~the whole family of~~ other International Codes and standards including the following major codes:

~~2009~~ 2012 International Plumbing Code (IPC)
~~2009~~ 2012 International Mechanical Code (IMC)
~~2008~~ 2011 NFPA 70
~~2009~~ 2012 International Fuel Gas Code (IFGC)
~~2009~~ 2012 International Energy Conservation Code (IECC)
~~2009~~ 2012 International Residential Code (IRC)

Note 2: The ~~International Residential Code~~ IRC is applicable to the construction of detached one- and two-family dwellings and townhouses as set out in Section 310.

C. Section 101.3 Numbering system. A dual numbering system is used in the USBC to correlate the numbering system of the Virginia Administrative Code with the numbering system of the IBC. IBC numbering system designations are provided in the catchlines of the Virginia Administrative Code sections. Cross references between sections or chapters of the USBC use only the IBC numbering system designations. The term “chapter” is used in the context of the numbering system of the IBC and may mean a chapter in the USBC, a chapter in the IBC or a chapter in a referenced code or standard, depending on the context of the use

of the term. The term "chapter" is not used to designate a chapter of the Virginia Administrative Code, unless clearly indicated.

D. Section 101.4 Arrangement of code provisions. The USBC is comprised of the combination of (i) the provisions of Chapter 1, Administration, which are established herein, (ii) Chapters 2 - 35 of the IBC, which are incorporated by reference in Section 101.2, and (iii) the changes to the text of the incorporated chapters of the IBC that are specifically identified. The terminology "changes to the text of the incorporated chapters of the IBC that are specifically identified" shall also be referred to as the "state amendments to the IBC." Such state amendments to the IBC are set out using corresponding chapter and section numbers of the IBC numbering system. In addition, since Chapter 1 of the IBC is not incorporated as part of the USBC, any reference to a provision of Chapter 1 of the IBC in the provisions of Chapters 2 - 35 of the IBC is generally invalid. However, where the purpose of such a reference would clearly correspond to a provision of Chapter 1 established herein, then the reference may be construed to be a valid reference to such corresponding Chapter 1 provision.

E. Section 101.5 Use of terminology and notes. The term "this code," or "the code," where used in the provisions of Chapter 1, in Chapters 2 - 35 of the IBC or in the state amendments to the IBC means the USBC, unless the context clearly indicates otherwise. The term "this code" or "the code" where used in a code or standard referenced in the IBC means that code or standard, unless the context clearly indicates otherwise. The use of notes in Chapter 1 is to provide information only and shall not be construed as changing the meaning of any code provision. Notes in the IBC, in the codes and standards referenced in the IBC and in the state amendments to the IBC may modify the content of a related provision and shall be considered to be a valid part of the provision, unless the context clearly indicates otherwise.

F. Section 101.6 Order of precedence. The provisions of Chapter 1 of this code supersede any conflicting provisions of Chapters 2 - 35 of the IBC and any conflicting provisions of the codes and standards referenced in the IBC. In addition, the state amendments to the IBC supersede any conflicting provisions of Chapters 2 - 35 of the IBC and any conflicting provisions of the codes and standards referenced in the IBC. Further, the provisions of Chapters 2 - 35 of the IBC supersede any conflicting provisions of the codes and standards referenced in the IBC.

G. Section 101.7 Administrative provisions. The provisions of Chapter 1 establish administrative requirements, which include but are not limited to provisions relating to the scope of the code, enforcement, fees, permits, inspections and disputes. Any provisions of Chapters 2 - 35 of the IBC or any provisions of the codes and standards referenced in the IBC that address the same subject matter and impose differing requirements are deleted and replaced by the provisions of Chapter 1. Further, any administrative requirements contained in the state amendments to the IBC shall be given the same precedence as the provisions of Chapter 1. Notwithstanding the above, where administrative requirements of Chapters 2 - 35 of the IBC or of the codes and standards referenced in the IBC are specifically identified as valid administrative requirements in Chapter 1 of this code or in the state amendments to the IBC, then such requirements are not deleted and replaced.

Note: The purpose of this provision is to eliminate overlap, conflicts and duplication by providing a single standard for administrative, procedural and enforcement requirements of this code.

H. Section 101.8 Definitions. The definitions of terms used in this code are contained in Chapter 2 along with specific provisions addressing the use of definitions. Terms may be defined in other chapters or provisions of the code and such definitions are also valid.

Note: The order of precedence outlined in Section 101.6 may be determinative in establishing how to apply the definitions in the IBC and in the referenced codes and standards.

13VAC5-63-20. Section 102 Purpose and scope.

A. Section 102.1 Purpose. In accordance with § 36-99 of the Code of Virginia, the purpose of the USBC is to protect the health, safety and welfare of the residents of the Commonwealth of Virginia, provided that buildings and structures should be permitted to be constructed at the least possible cost consistent with recognized standards of health, safety, energy conservation and water conservation, including provisions necessary to prevent overcrowding, rodent or insect infestation, and garbage accumulation; and barrier-free provisions for the physically handicapped and aged.

B. Section 102.2 Scope. This section establishes the scope of the USBC in accordance with § 36-98 of the Code of Virginia. The USBC shall supersede the building codes and regulations of the counties, municipalities and other political subdivisions and state agencies. This code also shall supersede the provisions of local ordinances applicable to single-family residential construction that (i) regulate dwelling foundations or crawl spaces, (ii) require the use of specific building materials or finishes in construction, or (iii) require minimum surface area or numbers of windows; however, this code shall not supersede proffered conditions accepted as a part of a rezoning application, conditions imposed upon the grant of special exceptions, special or conditional use permits or variances, conditions imposed upon a clustering of single-family homes and preservation of open space development through standards, conditions, and criteria established by a locality pursuant to subdivision 8 of § 15.2-2242 of the Code of Virginia or subdivision A 12 of § 15.2-2286 of the Code of Virginia, or land use requirements in airport or highway overlay districts, or historic districts created pursuant to § 15.2-2306 of the Code of Virginia, or local flood plain regulations adopted as a condition of participation in the National Flood Insurance Program.

Note: Requirements relating to functional design are contained in Section 103.11 of this code.

C. Section 102.2.1 Invalidity of provisions. To the extent that any provisions of this code are in conflict with Chapter 6 (§ 36-97 et seq.) of Title 36 of the Code of Virginia or in conflict with the scope of the USBC, those provisions are considered to be invalid to the extent of such conflict.

D. Section 102.3 Exemptions. The following are exempt from this code:

1. Equipment, related wiring, and poles and towers supporting the related wiring installed by a provider of publicly regulated utility service or a franchised cable television operator

and electrical equipment and related wiring used for radio, broadcast or cable television, telecommunications or information service transmission. The exemption shall apply only if under applicable federal and state law the ownership and control of the equipment and wiring is by the service provider or its affiliates. Such exempt equipment and wiring shall be located on either rights-of-way or property for which the service provider has rights of occupancy and entry; however, the structures, including their service equipment, housing or supporting such exempt equipment and wiring shall be subject to the USBC. The installation of equipment and wiring exempted by this section shall not create an unsafe condition prohibited by the USBC.

2. Manufacturing and processing machines that do not produce or process hazardous materials regulated by this code, including all of the following service equipment associated with the manufacturing or processing machines.

2.1. Electrical equipment connected after the last disconnecting means.

2.2. Plumbing piping and equipment connected after the last shutoff valve or backflow device and before the equipment drain trap.

2.3. Gas piping and equipment connected after the outlet shutoff valve.

Manufacturing and processing machines that produce or process hazardous materials regulated by this code are only required to comply with the code provisions regulating the hazardous materials.

3. Parking lots and sidewalks, which are not part of an accessible route.

4. Nonmechanized playground or recreational equipment such as swing sets, sliding boards, climbing bars, jungle gyms, skateboard ramps, and similar equipment where no admission fee is charged for its use or for admittance to areas where the equipment is located.

5. Industrialized buildings subject to the Virginia Industrialized Building Safety Regulations (13VAC5-91) and manufactured homes subject to the Virginia Manufactured Home Safety Regulations (13VAC5-95); except as provided for in Section 424 425.

6. Farm buildings and structures, except for a building or a portion of a building located on a farm that is operated as a restaurant as defined in § 35.1-1 of the Code of Virginia and licensed as such by the Virginia Board of Health pursuant to Chapter 2 (§ 35.1-11 et seq.) of Title 35.1 of the Code of Virginia. However, farm buildings and structures lying within a flood plain or in a mudslide-prone area shall be subject to flood-proofing regulations or mudslide regulations, as applicable.

7. Federally owned buildings and structures unless federal law specifically requires a permit from the locality. Underground storage tank installations, modifications and removals shall comply with this code in accordance with federal law.

13VAC5-63-30. Section 103 Application of code.

A. Section 103.1 General. In accordance with § 36-99 of the Code of Virginia, the USBC shall prescribe building regulations to be complied with in the construction and rehabilitation of buildings and structures, and the equipment therein.

B. Section 103.2 When applicable to new construction. Construction for which a permit application is submitted to the local building department on or after the effective date of the ~~2009~~ 2012 edition of the code shall comply with the provisions of this code, except for permit applications submitted during a one-year period after beginning on the effective date of the ~~2009~~ 2012 edition of the code. The applicant for a permit during such one-year period shall be permitted to choose whether to comply with the provisions of this code or the provisions of the edition of the code in effect immediately prior to the ~~2009~~ 2012 edition. This provision shall also apply to subsequent amendments to this code based on the effective date of such amendments. In addition, when a permit has been properly issued under a previous edition of this code, this code shall not require changes to the approved construction documents, design or construction of such a building or structure, provided the permit has not been suspended or revoked.

C. Section 103.3 Change of occupancy. No change of occupancy shall be made in any structure when the current USBC requires a greater degree of accessibility, structural strength, fire protection, means of egress, ventilation or sanitation. When such a greater degree is required, the owner or the owner's agent shall make written application to the local building department for a new certificate of occupancy and shall obtain the new certificate of occupancy prior to the new use of the structure. When impractical to achieve compliance with this code for the new occupancy classification, the building official shall consider modifications upon application and as provided for in Section 106.3.

Exception: This section shall not be construed to permit noncompliance with any applicable flood load or flood-resistant construction requirements of this code.

D. Section 103.4 Additions. Additions to buildings and structures shall comply with the requirements of this code for new construction and an existing building or structure plus additions shall comply with the height and area provisions of Chapter 5. Further, this code shall not require changes to the design or construction of any portions of the building or structure not altered or affected by an addition, unless the addition has the effect of lowering the current level of safety.

Exception: This section shall not be construed to permit noncompliance with any applicable flood load or flood-resistant construction requirements of this code.

E. Section 103.5 Reconstruction, alteration or repair. The following criteria is applicable to reconstruction, alteration or repair of buildings or structures:

1. Any reconstruction, alteration or repair shall not adversely affect the performance of the building or structure, or cause the building or structure to become unsafe or lower existing levels of health and safety.

2. Parts of the building or structure not being reconstructed, altered or repaired shall not be required to comply with the requirements of this code applicable to newly constructed buildings or structures.

3. The installation of material or equipment, or both, that is neither required nor prohibited shall only be required to comply with the provisions of this code relating to the safe installation of such material or equipment.

4. Material or equipment, or both, may be replaced in the same location with material or equipment of a similar kind or capacity.

Exceptions:

1. This section shall not be construed to permit noncompliance with any applicable flood load or flood-resistant construction requirements of this code.

2. Reconstructed decks, balconies, porches and similar structures located 30 inches (762 mm) or more above grade shall meet the current code provisions for structural loading capacity, connections and structural attachment. This requirement excludes the configuration and height of handrails and guardrails.

F. Section 103.6. Use of rehabilitation code. Compliance with Part II of the Virginia Uniform Statewide Building Code, also known as the "Virginia Rehabilitation Code," shall be an acceptable alternative to compliance with this code for the rehabilitation of such existing buildings and structures within the scope of that code. For the purposes of this section, the term "rehabilitation" shall be as defined in the Virginia Rehabilitation Code.

G. Section 103.7. Retrofit requirements. The local building department shall enforce the provisions of Section 3413, which require certain existing buildings to be retrofitted with fire protection systems and other safety equipment. Retroactive fire protection system requirements contained in the International Fire Code shall not be applicable unless required for compliance with the provisions of Section 3413.

H. Section 103.8 Nonrequired equipment. The following criteria for nonrequired equipment is in accordance with § 36-103 of the Code of Virginia. Building owners may elect to install partial or full fire alarms or other safety equipment that was not required by the edition of the USBC in effect at the time a building was constructed without meeting current requirements of the code, provided the installation does not create a hazardous condition. Permits for installation shall be obtained in accordance with this code. In addition, as a requirement of this code, when such nonrequired equipment is to be installed, the building official shall notify the appropriate fire official or fire chief.

I. Section 103.8.1 Reduction in function or discontinuance of nonrequired fire protection systems. When a nonrequired fire protection system is to be reduced in function or discontinued, it shall be done in such a manner so as not to create a false sense of protection. Generally, in such cases, any features visible from interior areas shall be removed, such as sprinkler heads, smoke detectors or alarm panels or devices, but any wiring or piping hidden

within the construction of the building may remain. Approval of the proposed method of reduction or discontinuance shall be obtained from the building official.

J. Section 103.9 Equipment changes. Upon the replacement or new installation of any fuel-burning appliances or equipment in existing buildings, an inspection or inspections shall be conducted to ensure that the connected vent or chimney systems comply with the following:

1. Vent or chimney systems are sized in accordance with either the ~~International Residential Code~~ IRC, the ~~International Mechanical Code~~ IMC or the ~~International Fuel Gas Code~~ IFGC, depending on which is applicable based on the fuel source and the occupancy classification of the structure.
2. Vent or chimney systems are clean, free of any obstruction or blockages, defects or deterioration and are in operable condition.

Where not inspected by the local building department, persons performing such changes or installations shall certify to the building official that the requirements of Items 1 and 2 of this section are met.

K. Section 103.10 Use of certain provisions of referenced codes. The following provisions of the IBC and of other indicated codes or standards are to be considered valid provisions of this code. Where any such provisions have been modified by the state amendments to the IBC, then the modified provisions apply.

1. Special inspection requirements in Chapters 2 - 35.
2. Chapter 34, Existing Structures, except that Section 3412, Compliance Alternatives, shall not be used to comply with the retrofit requirements identified in Section 103.7 and shall not be construed to permit noncompliance with any applicable flood load or flood-resistant construction requirements of this code.
3. Testing requirements and requirements for the submittal of construction documents in any of the ICC codes referenced in Chapter 35 and in the IRC.
4. Section R301.2 of the ~~International Residential Code~~ IRC authorizing localities to determine climatic and geographic design criteria.
5. Flood load or flood-resistant construction requirements in the IBC or the ~~International Residential Code~~ IRC, including, but not limited to, any such provisions pertaining to flood elevation certificates that are located in Chapter 1 of those codes. Any required flood elevation certificate pursuant to such provisions shall be prepared by a land surveyor licensed in Virginia or an RDP.
6. Section R101.2 of the IRC.

L. Section 103.11 Functional design. The following criteria for functional design is in accordance with § 36-98 of the Code of Virginia. The USBC shall not supersede the regulations of other state agencies that require and govern the functional design and operation

of building related activities not covered by the USBC, including but not limited to (i) public water supply systems, (ii) waste water treatment and disposal systems, (iii) solid waste facilities, nor shall state agencies be prohibited from requiring, pursuant to other state law, that buildings and equipment be maintained in accordance with provisions of this code. In addition, as established by this code, the building official may refuse to issue a permit until the applicant has supplied certificates of functional design approval from the appropriate state agency or agencies. For purposes of coordination, the locality may require reports to the building official by other departments or agencies indicating compliance with their regulations applicable to the functional design of a building or structure as a condition for issuance of a building permit or certificate of occupancy. Such reports shall be based upon review of the plans or inspection of the project as determined by the locality. All enforcement of these conditions shall not be the responsibility of the building official, but rather the agency imposing the condition.

Note: Identified state agencies with functional design approval are listed in the "Related Laws Package," which is available from DHCD.

M. Section 103.12 Amusement devices and inspections. In accordance with § 36-98.3 of the Code of Virginia, to the extent they are not superseded by the provisions of § 36-98.3 of the Code of Virginia and the VADR, the provisions of the USBC shall apply to amusement devices. In addition, as a requirement of this code, inspections for compliance with the VADR shall be conducted either by local building department personnel or private inspectors provided such persons are certified as amusement device inspectors under the VCS.

N. Section 103.13 State buildings and structures. This section establishes the application of the USBC to state-owned buildings and structures in accordance with § 36-98.1 of the Code of Virginia. The USBC shall be applicable to all state-owned buildings and structures, with the exception that §§ 2.2-1159, ~~2.2-1160~~ and through 2.2-1161 of the Code of Virginia shall provide the standards for ready access to and use of state-owned buildings by the physically handicapped.

Any state-owned building or structure for which preliminary plans were prepared or on which construction commenced after the initial effective date of the USBC, shall remain subject to the provisions of the USBC that were in effect at the time such plans were completed or such construction commenced. Subsequent reconstruction, renovation or demolition of such building or structure shall be subject to the pertinent provisions of this code.

Acting through the Division of Engineering and Buildings, the Virginia Department of General Services shall function as the building official for state-owned buildings. The department shall review and approve plans and specifications, grant modifications, and establish such rules and regulations as may be necessary to implement this section. It shall provide for the inspection of state-owned buildings and enforcement of the USBC and standards for access by the physically handicapped by delegating inspection and USBC enforcement duties to the State Fire Marshal's Office, to other appropriate state agencies having needed expertise, and to local building departments, all of which shall provide such assistance within a reasonable time and in the manner requested. State agencies and institutions occupying buildings shall pay to the local building department the same fees as would be paid by a private citizen for the services rendered when such services are requested

by the department. The department may alter or overrule any decision of the local building department after having first considered the local building department's report or other rationale given for its decision. When altering or overruling any decision of a local building department, the department shall provide the local building department with a written summary of its reasons for doing so.

Notwithstanding any provision of this code to the contrary, roadway tunnels and bridges owned by the Virginia Department of Transportation shall be exempt from this code. The Virginia Department of General Services shall not have jurisdiction over such roadway tunnels, bridges and other limited access highways; provided, however, that the Department of General Services shall have jurisdiction over any occupied buildings within any Department of Transportation rights-of-way that are subject to this code.

Except as provided in subdivision D of § 23-38.109 D of the Code of Virginia, and notwithstanding any provision of this code to the contrary, at the request of a public institution of higher education, the Virginia Department of General Services, as further set forth in this provision, shall authorize that institution of higher education to contract with a building official of the locality in which the construction is taking place to perform any inspection and certifications required for the purpose of complying with this code. The department shall publish administrative procedures that shall be followed in contracting with a building official of the locality. The authority granted to a public institution of higher education under this provision to contract with a building official of the locality shall be subject to the institution meeting the conditions prescribed in subdivision B of § 23-38.88 B of the Code of Virginia.

Note: In accordance with § 36-98.1 of the Code of Virginia, roadway tunnels and bridges shall be designed, constructed and operated to comply with fire safety standards based on nationally recognized model codes and standards to be developed by the Virginia Department of Transportation in consultation with the State Fire Marshal and approved by the Virginia Commonwealth Transportation Board. Emergency response planning and activities related to the standards approved by the Commonwealth Transportation Board shall be developed by the Department of Transportation and coordinated with the appropriate local officials and emergency service providers. On an annual basis, the Department of Transportation shall provide a report on the maintenance and operability of installed fire protection and detection systems in roadway tunnels and bridges to the State Fire Marshal.

O. Section 103.13.1 Certification of state enforcement personnel. State enforcement personnel shall comply with the applicable requirements of Section 105 for certification, periodic maintenance training, and continuing education.

13VAC5-63-40. Section 104 Enforcement, generally.

A. Section 104.1 Scope of enforcement. This section establishes the requirements for enforcement of the USBC in accordance with § 36-105 of the Code of Virginia. Enforcement of the provisions of the USBC for construction and rehabilitation shall be the responsibility of the local building department. Whenever a county or municipality does not have such a building department, the local governing body shall enter into an agreement with the local governing body of another county or municipality or with some other agency, or a state

agency approved by DHCD for such enforcement. For the purposes of this section, towns with a population of less than 3,500 may elect to administer and enforce the USBC; however, where the town does not elect to administer and enforce the code, the county in which the town is situated shall administer and enforce the code for the town. In the event such town is situated in two or more counties, those counties shall administer and enforce the USBC for that portion of the town situated within their respective boundaries.

~~Upon~~ However, upon a finding by the local building department, following a complaint by a tenant of a residential ~~rental dwelling~~ dwelling unit that is the subject of such complaint, that there may be a violation of the unsafe structures provisions of Part III of the Virginia Uniform Statewide Building Code, also known as the "Virginia Maintenance Code," the local building department shall enforce such provisions.

If the local building department receives a complaint that a violation of the Virginia Maintenance Code exists that is an immediate and imminent threat to the health or safety of the owner ~~or~~ tenant or occupants of a residential ~~dwelling unit or a nearby residential dwelling unit, and any building or structure, or~~ the owner, occupant or tenant or any nearby building or structure, and the owner, occupant or tenant of the residential dwelling unit building or structure that is the subject of the complaint has refused to allow the local building official or his agent to have access to the subject ~~dwelling building or structure~~, the local building official or his agent may present sworn testimony to a magistrate or a court of competent jurisdiction and request that the magistrate or court grant the local building official or his agent an inspection warrant to enable the building official or his agent to enter the subject ~~dwelling building or structure~~ for the purpose of determining whether violations of the Virginia Maintenance Code exist. The local building official or his agent shall make a reasonable effort to obtain consent from the owner, occupant or tenant of the subject ~~dwelling building or structure~~ prior to seeking the issuance of an inspection warrant under this section.

The local governing body shall, however, inspect and enforce the provisions of the Virginia Maintenance Code for elevators, escalators and related conveyances, except for elevators in single- and two-family homes and townhouses. Such inspection and enforcement shall be carried out by an agency or department designated by the local governing body.

B. Section 104.2 Interagency coordination. When any inspection functions under this code are assigned to a local agency other than the local building department, such agency shall coordinate its reports of inspection with the local building department.

~~C. 104.3 Transfer of ownership. If the local building department has initiated an enforcement action against the owner of a building or structure and such owner subsequently transfers the ownership of the building or structure to an entity in which the owner holds an ownership interest greater than 50%, the pending enforcement action shall continue to be enforced against the owner.~~

13VAC5-63-50. Section 105 Local building department.

A. Section 105.1 Appointment of building official. Every local building department shall have a building official as the executive official in charge of the department. The building official shall be appointed in a manner selected by the local governing body. After permanent

appointment, the building official shall not be removed from office except for cause after having been afforded a full opportunity to be heard on specific and relevant charges by and before the appointing authority. DHCD shall be notified by the appointing authority within 30 days of the appointment or release of a permanent or acting building official.

Note: Building officials are subject to sanctions in accordance with the VCS.

B. Section 105.1.1 Qualifications of building official. The building official shall have at least five years of building experience as a licensed professional engineer or architect, building, fire or trade inspector, contractor, housing inspector or superintendent of building, fire or trade construction or at least five years of building experience after obtaining a degree in architecture or engineering, with at least three years in responsible charge of work. Any combination of education and experience that would confer equivalent knowledge and ability shall be deemed to satisfy this requirement. The building official shall have general knowledge of sound engineering practice in respect to the design and construction of structures, the basic principles of fire prevention, the accepted requirements for means of egress and the installation of elevators and other service equipment necessary for the health, safety and general welfare of the occupants and the public. The local governing body may establish additional qualification requirements.

C. Section 105.1.2 Certification of building official. An acting or permanent building official shall be certified as a building official in accordance with the VCS within one year after being appointed as acting or permanent building official.

Exception: A building official in place prior to April 1, 1983, shall not be required to meet the certification requirements in this section while continuing to serve in the same capacity in the same locality.

D. Section 105.1.3 Noncertified building official. Except for a building official exempt from certification under the exception to Section 105.1.2, any acting or permanent building official who is not certified as a building official in accordance with the VCS shall attend the core module of the Virginia Building Code Academy or an equivalent course in an individual or regional code academy accredited by DHCD within 180 days of appointment. This requirement is in addition to meeting the certification requirement in Section 105.1.2.

E. Section 105.1.4 Requirements for periodic maintenance and continuing education. Building officials shall attend periodic maintenance training as designated by DHCD. In addition to the periodic maintenance training required above, building officials shall attend 16 hours of continuing education every two years as approved by DHCD. If a building official possesses more than one BHCD certificate, the 16 hours shall satisfy the continuing education requirement for all BHCD certificates.

F. Section 105.2 Technical assistants. The building official, subject to any limitations imposed by the locality, shall be permitted to utilize technical assistants to assist the building official in the enforcement of the USBC. DHCD shall be notified by the building official within 60 days of the employment of, contracting with or termination of all technical assistants.

Note: Technical assistants are subject to sanctions in accordance with the VCS.

G. Section 105.2.1 Qualifications of technical assistants. A technical assistant shall have at least three years of experience and general knowledge in at least one of the following areas: building construction; building, fire or housing inspections; plumbing, electrical or mechanical trades; or fire protection, elevator or property maintenance work. Any combination of education and experience that would confer equivalent knowledge and ability shall be deemed to satisfy this requirement. The locality may establish additional qualification requirements.

H. Section 105.2.2 Certification of technical assistants. A technical assistant shall be certified in the appropriate subject area within 18 months after becoming a technical assistant. When required by local policy to have two or more certifications, a technical assistant shall obtain the additional certifications within three years from the date of such requirement.

Exception: A technical assistant in place prior to March 1, 1988, shall not be required to meet the certification requirements in this section while continuing to serve in the same capacity in the same locality.

I. Section 105.2.3 Requirements for periodic maintenance and continuing education. Technical assistants shall attend periodic maintenance training as designated by DHCD. In addition to the periodic maintenance training required above, technical assistants shall attend 16 hours of continuing education every two years as approved by DHCD. If a technical assistant possesses more than one BHCD certificate, the 16 hours shall satisfy the continuing education requirement for all BHCD certificates.

J. Section 105.3 Conflict of interest. The standards of conduct for building officials and technical assistants shall be in accordance with the provisions of the State and Local Government Conflict of Interests Act, Chapter 31 (§ 2.2-3100 et seq.) of Title 2.2 of the Code of Virginia.

K. Section 105.4 Records. The local building department shall retain a record of applications received, permits, certificates, notices and orders issued, fees collected and reports of inspection in accordance with The Library of Virginia's General Schedule Number Six.

13VAC5-63-60. Section 106 Powers and duties of the building official.

A. Section 106.1 Powers and duties, generally. The building official shall enforce this code as set out herein and as interpreted by the State Review Board.

B. Section 106.2 Delegation of authority. The building official may delegate powers and duties except where such authority is limited by the local government. However, such limitations of authority by the local government are not applicable to the third-party inspector policy required by Section 113.7.1 nor shall such limitations of authority by the local government have the effect of altering the provisions of this code or creating building regulations. When such delegations are made, the building official shall be responsible for assuring that they are carried out in accordance with the provisions of this code.

C. Section 106.3 Issuance of modifications. Upon written application by an owner or an owner's agent, the building official may approve a modification of any provision of the USBC provided the spirit and functional intent of the code are observed and public health, welfare and safety are assured. The decision of the building official concerning a modification shall be made in writing and the application for a modification and the decision of the building official concerning such modification shall be retained in the permanent records of the local building department.

Note: The USBC references nationally recognized model codes and standards. Future amendments to such codes and standards are not automatically included in the USBC; however the building official should give them due consideration in deciding whether to approve a modification.

D. Section 106.3.1 Substantiation of modification. The building official may require or may consider a statement from an RDP or other person competent in the subject area of the application as to the equivalency of the proposed modification. In addition, the building official may require the application to include construction documents sealed by an RDP.

E. Section 106.3.2 Use of performance code. Compliance with the provisions of a nationally recognized performance code when approved as a modification shall be considered to constitute compliance with this code. All documents submitted as part of such consideration shall be retained in the permanent records of the local building department.

13VAC5-63-70. Section 107 Fees.

A. Section 107.1 Authority for charging fees. In accordance with § 36-105 of the Code of Virginia, fees may be levied by the local governing body in order to defray the cost of enforcement of the USBC.

B. Section 107.1.1 Fee schedule. The local governing body shall establish a fee schedule incorporating unit rates, which may be based on square footage, cubic footage, estimated cost of construction or other appropriate criteria. A permit or any amendments to an existing permit shall not be issued until the designated fees have been paid, except that the building official may authorize the delayed payment of fees.

C. Section 107.1.2 Refunds. When requested in writing by a permit holder, the locality shall provide a fee refund in the case of the revocation of a permit or the abandonment or discontinuance of a building project. The refund shall not be required to exceed an amount which correlates to work not completed.

D. Section 107.2 Code academy fee levy. In accordance with subdivision 7 of § 36-137 of the Code of Virginia, the local building department shall collect a 2.0% levy of fees charged for permits issued under this code and transmit it quarterly to DHCD to support training programs of the Virginia Building Code Academy. Localities that maintain individual or regional training academies accredited by DHCD shall retain such levy.

13VAC5-63-80. Section 108 Application for permit.

A. Section 108.1 When applications are required. Application for a permit shall be made to the building official and a permit shall be obtained prior to the commencement of any of the following activities, except that applications for emergency construction, alterations or equipment replacement shall be submitted by the end of the first working day that follows the day such work commences. In addition, the building official may authorize work to commence pending the receipt of an application or the issuance of a permit.

1. Construction or demolition of a building or structure. Installations or alterations involving (i) the removal or addition of any wall, partition or portion thereof, (ii) any structural component, (iii) the repair or replacement of any required component of a fire or smoke rated assembly, (iv) the alteration of any required means of egress system, (v) water supply and distribution system, sanitary drainage system or vent system, (vi) electric wiring, (vii) fire protection system, mechanical systems, or fuel supply systems, or (viii) any equipment regulated by the USBC.

2. For change of occupancy, application for a permit shall be made when a new certificate of occupancy is required under Section 103.3.

3. Movement of a lot line that increases the hazard to or decreases the level of safety of an existing building or structure in comparison to the building code under which such building or structure was constructed.

4. Removal or disturbing of any asbestos containing materials during the construction or demolition of a building or structure, including additions.

B. Section 108.2 Exemptions from application for permit. Notwithstanding the requirements of Section 108.1, application for a permit and any related inspections shall not be required for the following; however, this section shall not be construed to exempt such activities from other applicable requirements of this code. In addition, when an owner or an owner's agent requests that a permit be issued for any of the following, then a permit shall be issued and any related inspections shall be required.

1. Installation of wiring and equipment that (i) operates at less than 50 volts, (ii) is for network powered broadband communications systems, or (iii) is exempt under Section 102.3(1), except when any such installations are located in a plenum, penetrate fire rated or smoke protected construction or are a component of any of the following:

- 1.1. Fire alarm system.

- 1.2. Fire detection system.

- 1.3. Fire suppression system.

- 1.4. Smoke control system.

- 1.5. Fire protection supervisory system.

- 1.6. Elevator fire safety control system.

- 1.7. Access or egress control system or delayed egress locking or latching system.
- 1.8. Fire damper.
- 1.9. Door control system.
2. One story detached accessory structures used as tool and storage sheds, playhouses or similar uses, provided the floor area does not exceed 200 square feet (18 m²) and the structures are not classified as a Group F-1 or H occupancy.
3. Detached prefabricated buildings housing the equipment of a publicly regulated utility service, provided the floor area does not exceed 150 square feet (14 m²).
4. Tents or air-supported structures, or both, that cover an area of 900 square feet (84 m²) or less, including within that area all connecting areas or spaces with a common means of egress or entrance, provided such tents or structures have an occupant load of 50 or less persons.
5. Fences and privacy walls not part of a building, structure or of the barrier for a swimming pool, provided such fences and privacy walls do not exceed six feet in height above the finished grade. Ornamental post caps shall not be considered to contribute to the height of the fence or privacy wall and shall be permitted to extend above the six feet height measurement.
6. Retaining walls supporting less than two feet of unbalanced fill. This exemption shall not apply to any wall impounding Class I, II or III-A liquids or supporting a surcharge other than ordinary unbalanced fill.
7. Swimming pools that have a surface area not greater than 150 square feet (13.95 m²); or ~~that do not exceed 5,000 gallons (19 000 L) and are less than 24 inches (610 mm) deep.~~
8. Signs under the conditions in Section H101.2 of Appendix H.
9. Replacement of above-ground existing LP-gas containers of the same capacity in the same location and associated regulators when installed by the serving gas supplier.
10. Ordinary repairs that include the following:
 - 10.1. Replacement of windows and doors with windows and doors of similar operation and opening dimensions that do not require changes to the existing framed opening and that are not required to be fire rated in Group R-2 where serving a single dwelling unit and in Groups R-3, R-4 and R-5.
 - 10.2. Replacement of plumbing fixtures in all groups without alteration of the water supply and distribution systems, sanitary drainage systems or vent systems.

10.3. Replacement of general use snap switches, dimmer and control switches, 125 volt-15 or 20 ampere receptacles, luminaries (lighting fixtures) and ceiling (paddle) fans in Group R-2 where serving a single dwelling unit and in Groups R-3, R-4 and R-5.

10.4. Replacement of mechanical appliances provided such equipment is not fueled by gas or oil in Group R-2 where serving a single family dwelling and in Groups R-3, R-4 and R-5.

10.5. Replacement of an unlimited amount of roof covering or siding in Groups R-3, R-4 or R-5 provided the building or structure is not in an area where the design (3 second gust) wind speed is greater than 100 miles per hour (160 km/hr) and replacement of 100 square feet (9.29 m²) or less of roof covering in all groups and all wind zones.

10.6. Replacement of 100 square feet (9.29 m²) or less of roof decking in Groups R-3, R-4 or R-5 unless the decking to be replaced was required at the time of original construction to be fire-retardant-treated or protected in some other way to form a fire-rated wall termination.

10.7. Installation or replacement of floor finishes in all occupancies.

10.8. Replacement of Class C interior wall or ceiling finishes installed in Groups A, E and I and replacement of all classes of interior wall or ceiling finishes in other groups.

10.9. Installation ~~of~~ or replacement of cabinetry or trim.

10.10. Application of paint or wallpaper.

10.11. Other repair work deemed by the building official to be minor and ordinary which does not adversely affect public health or general safety.

Exception: Application for a permit may be required by the building official for the installation of replacement siding, roofing and windows in buildings within a historic district designated by a locality pursuant to § 15.2-2306 of the Code of Virginia.

C. Section 108.3 Applicant information, processing by mail. Application for a permit shall be made by the owner or lessee of the relevant property or the agent of either or by the RDP, contractor or subcontractor associated with the work or any of their agents. The full name and address of the owner, lessee and applicant shall be provided in the application. If the owner or lessee is a corporate body, when and to the extent determined necessary by the building official, the full name and address of the responsible officers shall also be provided.

A permit application may be submitted by mail and such permit applications shall be processed by mail, unless the permit applicant voluntarily chooses otherwise. In no case shall an applicant be required to appear in person.

The building official may accept applications for a permit through electronic submissions provided the information required by this section is obtained.

D. Section 108.4 Prerequisites to obtaining permit. In accordance with § 54.1-1111 of the Code of Virginia, any person applying to the building department for the construction, removal or improvement of any structure shall furnish prior to the issuance of the permit either (i) satisfactory proof to the building official that he is duly licensed or certified under the terms of Chapter 11 (§ 54.1-1000 et seq.) of Title 54.1 of the Code of Virginia to carry out or superintend the same or (ii) file a written statement, supported by an affidavit, that he is not subject to licensure or certification as a contractor or subcontractor pursuant to Chapter 11 of Title 54.1 of the Code of Virginia. The applicant shall also furnish satisfactory proof that the taxes or license fees required by any county, city, or town have been paid so as to be qualified to bid upon or contract for the work for which the permit has been applied.

E. Section 108.5 Mechanics' lien agent designation. In accordance with § 36-98.01 of the Code of Virginia, a building permit issued for any one- or two-family residential dwelling shall at the time of issuance contain, at the request of the applicant, the name, mailing address, and telephone number of the mechanics' lien agent as defined in § 43-1 of the Code of Virginia. If the designation of a mechanics' lien agent is not so requested by the applicant, the building permit shall at the time of issuance state that none has been designated with the words "None Designated."

Note: In accordance with § 43-4.01A of the Code of Virginia, a permit may be amended after it has been initially issued to name a mechanics' lien agent or a new mechanics' lien agent.

F. Section 108.6 Application form, description of work. The application for a permit shall be submitted on a form or forms supplied by the local building department. The application shall contain a general description and location of the proposed work and such other information as determined necessary by the building official.

G. Section 108.7 Amendments to application. An application for a permit may be amended at any time prior to the completion of the work governed by the permit. Additional construction documents or other records may also be submitted in a like manner. All such submittals shall have the same effect as if filed with the original application for a permit and shall be retained in a like manner as the original filings.

H. Section 108.8 Time limitation of application. An application for a permit for any proposed work shall be deemed to have been abandoned six months after the date of filing unless such application has been pursued in good faith or a permit has been issued, except that the building official is authorized to grant one or more extensions of time if a justifiable cause is demonstrated.

13VAC5-63-90. Section 109 Construction documents.

A. Section 109.1 Submittal of documents. Construction documents shall be submitted with the application for a permit. The number of sets of such documents to be submitted shall be determined by the locality. Construction documents for one- and two-family dwellings may have floor plans reversed provided an accompanying site plan is approved.

Exception: Construction documents do not need to be submitted when the building official determines the proposed work is of a minor nature.

Note: Information on the types of construction required to be designed by an RDP is included in the "Related Laws Package" available from DHCD.

B. Section 109.2 Site plan. When determined necessary by the building official, a site plan shall be submitted with the application for a permit. The site plan shall show to scale the size and location of all proposed construction, including any associated wells, septic tanks or drain fields. The site plan shall also show to scale the size and location of all existing structures on the site, the distances from lot lines to all proposed construction, the established street grades and the proposed finished grades. When determined necessary by the building official, the site plan shall contain the elevation of the lowest floor of any proposed buildings. The site plan shall also be drawn in accordance with an accurate boundary line survey. When the application for a permit is for demolition, the site plan shall show all construction to be demolished and the location and size of all existing structures that are to remain on the site.

Note: Site plans are generally not necessary for alterations, renovations, repairs or the installation of equipment.

C. Section 109.3 Engineering details. When determined necessary by the building official, construction documents shall include adequate detail of the structural, mechanical, plumbing or electrical components. Adequate detail may include computations, stress diagrams or other essential technical data and when proposed buildings are more than two stories in height, adequate detail may specifically be required to include where floor penetrations will be made for pipes, wires, conduits, and other components of the electrical, mechanical and plumbing systems and how such floor penetrations will be protected to maintain the required structural integrity or fire-resistance rating, or both. All engineered documents, including relevant computations, shall be sealed by the RDP responsible for the design.

D. Section 109.4 Examination of documents. The building official shall examine or cause to be examined all construction documents or site plans, or both, within a reasonable time after filing. If such documents or plans do not comply with the provisions of this code, the permit applicant shall be notified in writing of the reasons, which shall include any adverse construction document review comments or determinations that additional information or engineering details need to be submitted. The review of construction documents for new one- and two-family dwellings for determining compliance with the technical provisions of this code not relating to the site, location or soil conditions associated with the dwellings shall not be required when identical construction documents for identical dwellings have been previously approved in the same locality under the same edition of the code and such construction documents are on file with the local building department.

E. Section 109.4.1 Expedited construction document review. The building official may accept reports from an approved person or agency that the construction documents have been examined and conform to the requirements of the USBC and may establish requirements for the person or agency submitting such reports. In addition, where such reports have been submitted, the building official may expedite the issuance of the permit.

F. Section 109.5 Approval of construction documents. The approval of construction documents shall be limited to only those items within the scope of the USBC. Either the word "Approved" shall be stamped on all required sets of approved construction documents or an equivalent endorsement in writing shall be provided. One set of the approved construction documents shall be retained for the records of the local building department and one set shall be kept at the building site and shall be available to the building official at all reasonable times.

G. Section 109.6 Phased approval. The building official is authorized to issue a permit for the construction of foundations or any other part of a building or structure before the construction documents for the whole building or structure have been submitted, provided that adequate information and detailed statements have been filed complying with pertinent requirements of this code. The holder of such permit for the foundation or other parts of a building or structure shall proceed at the holder's own risk with the building operation and without assurance that a permit for the entire structure will be granted.

13VAC5-63-100. Section 110 Permits.

A. Section 110.1 Approval and issuance of permits. The building official shall examine or cause to be examined all applications for permits or amendments to such applications within a reasonable time after filing. If the applications or amendments do not comply with the provisions of this code or all pertinent laws and ordinances, the permit shall not be issued and the permit applicant shall be notified in writing of the reasons for not issuing the permit. If the application complies with the applicable requirements of this code, a permit shall be issued as soon as practicable. The issuance of permits shall not be delayed in an effort to control the pace of construction of new detached one- or two-family dwellings.

B. Section 110.2 Types of permits. Separate or combined permits may be required for different areas of construction such as building construction, plumbing, electrical, and mechanical work, or for special construction as determined appropriate by the locality. In addition, permits for two or more buildings or structures on the same lot may be combined. Annual permits may also be issued for any construction regulated by this code. The annual permit holder shall maintain a detailed record of all alterations made under the annual permit. Such record shall be available to the building official and shall be submitted to the local building department if requested by the building official.

C. Section 110.3 Asbestos inspection in buildings to be renovated or demolished; exceptions. In accordance with § 36-99.7 of the Code of Virginia, the local building department shall not issue a building permit allowing a building for which an initial building permit was issued before January 1, 1985, to be renovated or demolished until the local building department receives certification from the owner or his agent that the affected portions of the building have been inspected for the presence of asbestos by an individual licensed to perform such inspections pursuant to § 54.1-503 of the Code of Virginia and that no asbestos-containing materials were found or that appropriate response actions will be undertaken in accordance with the requirements of the Clean Air Act National Emission Standard for the Hazardous Air Pollutant (NESHAPS) (40 CFR Part 61, Subpart M), and the asbestos worker protection requirements established by the U.S. Occupational Safety and Health Administration for

construction workers (29 CFR 1926.1101). Local educational agencies that are subject to the requirements established by the Environmental Protection Agency under the Asbestos Hazard Emergency Response Act (AHERA) shall also certify compliance with 40 CFR Part 763 and subsequent amendments thereto.

To meet the inspection requirements above, except with respect to schools, asbestos inspection of renovation projects consisting only of repair or replacement of roofing, floorcovering, or siding materials may be satisfied by a statement that the materials to be repaired or replaced are assumed to contain friable asbestos and that asbestos installation, removal, or encapsulation will be accomplished by a licensed asbestos contractor.

The provisions of this section shall not apply to single-family dwellings or residential housing with four or fewer units unless the renovation or demolition of such buildings is for commercial or public development purposes. The provisions of this section shall not apply if the combined amount of regulated asbestos-containing material involved in the renovation or demolition is less than 260 linear feet on pipes or less than 160 square feet on other facility components or less than 35 cubic feet off facility components where the length or area could not be measured previously.

An abatement area shall not be reoccupied until the building official receives certification from the owner that the response actions have been completed and final clearances have been measured. The final clearance levels for reoccupancy of the abatement area shall be 0.01 or fewer asbestos fibers per cubic centimeter if determined by Phase Contrast Microscopy analysis (PCM) or 70 or fewer structures per square millimeter if determined by Transmission Electron Microscopy analysis (TEM).

D. Section 110.4 Fire apparatus access road requirements. The permit applicant shall be informed of any requirements for providing or maintaining fire apparatus access roads prior to the issuance of a building permit.

E. Section 110.5 Signature on and posting of permits; limitation of approval. The signature of the building official or authorized representative shall be on or affixed to every permit. A copy of the permit shall be posted on the construction site for public inspection until the work is completed. Such posting shall include the street or lot number, if one has been assigned, to be readable from a public way. In addition, each building or structure to which a street number has been assigned shall, upon completion, have the number displayed so as to be readable from the public way.

A permit shall be considered authority to proceed with construction in accordance with this code, the approved construction documents, the permit application and any approved amendments or modifications. The permit shall not be construed to otherwise authorize the omission or amendment of any provision of this code.

F. Section 110.6 Abandonment of work. A building official shall be permitted to revoke a permit if work on the site authorized by the permit is not commenced within six months after issuance of the permit, or if the authorized work on the site is suspended or abandoned for a period of six months after the permit is issued; however, permits issued for plumbing, electrical and mechanical work shall not be revoked if the building permit is still in effect. It

shall be the responsibility of the permit applicant to prove to the building official that authorized work includes substantive progress, characterized by approved inspections as specified in Section 113.3 of at least one inspection within a period of six months or other evidence that would indicate substantial work has been performed. Upon written request, the building official may grant one or more extensions of time, not to exceed one year per extension.

G. Section 110.7 Single-family dwelling permits. The building official shall be permitted to require a three year time limit to complete construction of new detached single-family dwellings, additions to detached single-family dwellings and residential accessory structures. The time limit shall begin from the issuance date of the permit. The building official may grant extensions of time if the applicant can demonstrate substantive progress, characterized by approved inspections as specified in Section 113.3 of at least one inspection within a period of six months or other evidence that would indicate substantial work has been performed.

H. Section 110.8 Revocation of a permit. The building official may revoke a permit or approval issued under this code in the case of any false statement, misrepresentation of fact, abandonment of work, failure to complete construction as required by Section 110.7 or incorrect information supplied by the applicant in the application or construction documents on which the permit or approval was based.

13VAC5-63-110. Section 111 RDP services.

A. Section 111.1 When required. In accordance with § 54.1-410 of the Code of Virginia and under the general authority of this code, the local building department shall establish a procedure to ensure that construction documents under Section 109 are prepared by an RDP in any case in which the exemptions contained in § 54.1-401, 54.1-402 or 54.1-402.1 of the Code of Virginia are not applicable or in any case where the building official determines it necessary. When required under § 54.1-402 of the Code of Virginia or when required by the building official, or both, construction documents shall bear the name and address of the author and his occupation.

Note: Information on the types of construction required to be designed by an RDP is included in the "Related Laws Package" available from DHCD.

B. Section 111.2 Special inspection requirements. Special inspections shall be conducted when required by Section 1704. Individuals or agencies, or both, conducting special inspections shall meet the qualification requirements of Sections 1703 and ~~1704.1~~ 1704.2.1. The permit applicant shall submit a completed statement of special inspections with the permit application. The building official shall review, and if satisfied that the requirements have been met, approve the statement of special inspections as required in Sections ~~1704.1-1~~ 1704.2.3 and 1705 as a requisite to the issuance of a building permit. The building official may require interim inspection reports. The building official shall receive, and if satisfied that the requirements have been met, approve a final report of special inspections as specified in Section ~~1704.1-2~~ 1704.2.4. All fees and costs related to the special inspections shall be the responsibility of the building owner.

13VAC5-63-120. Section 112 Workmanship, materials and equipment.

A. Section 112.1 General. It shall be the duty of any person performing work covered by this code to comply with all applicable provisions of this code and to perform and complete such work so as to secure the results intended by the USBC.

B. Section 112.2 Alternative methods or materials. In accordance with § 36-99 of the Code of Virginia, where practical, the provisions of this code are stated in terms of required level of performance so as to facilitate the prompt acceptance of new building materials and methods. When generally recognized standards of performance are not available, this section and other applicable requirements of this code provide for acceptance of materials and methods whose performance is substantially equal in safety to those specified on the basis of reliable test and evaluation data presented by the proponent. In addition, as a requirement of this code, the building official shall require that sufficient technical data be submitted to substantiate the proposed use of any material, equipment, device, assembly or method of construction.

C. Section 112.3 Documentation and approval. In determining whether any material, equipment, device, assembly or method of construction complies with this code, the building official shall approve items listed by nationally recognized testing laboratories (NRTL), when such items are listed for the intended use and application, and in addition, may consider the recommendations of RDPs. Approval shall be issued when the building official finds that the proposed design is satisfactory and complies with the intent of the provisions of this code and that the material, equipment, device, assembly or method of construction offered is, for the purpose intended, at least the equivalent of that prescribed by the code. Such approval is subject to all applicable requirements of this code and the material, equipment, device, assembly or method of construction shall be installed in accordance with the conditions of the approval and their listings. In addition, the building official may revoke such approval whenever it is discovered that such approval was issued in error or on the basis of incorrect information, or where there are repeated violations of the USBC.

D. Section 112.3.1 Conditions of listings. Where conflicts between this code and conditions of the listing or the manufacturer's installation instructions occur, the provisions of this code shall apply.

Exception: Where a code provision is less restrictive than the conditions of the listing of the equipment or appliance or the manufacturer's installation instructions, the conditions of the listing and the manufacturer's installation instructions shall apply.

E. Section 112.4 Used material and equipment. Used materials, equipment and devices may be approved provided they have been reconditioned, tested or examined and found to be in good and proper working condition and acceptable for use by the building official.

F. Section 112.5 Defective materials. Notwithstanding any provision of this code to the contrary, where action has been taken and completed by the BHCD under § 36-99 D of the Code of Virginia establishing new performance standards for identified defective materials, this section sets forth the new performance standards addressing the prospective use of such materials and establishes remediation standards for the removal of any defective materials already installed, which, when complied with, enables the building official to certify that the building is deemed to comply with the edition of the USBC under which the building was

originally constructed with respect to the remediation of the defective materials. Subsections F through X of this section expire on August 29, 2013.

G. Section 112.5.1 Drywall, performance standard. All newly installed gypsum wallboard shall not be defective drywall as defined in Section 112.5.1.1.1.

H. Section 112.5.1.1 Remediation standards. The following provisions establish remediation standards where defective drywall was installed in buildings.

I. Section 112.5.1.1.1 Definition. For the purposes of this section the term "defective drywall" shall mean gypsum wallboard that (i) contains elemental sulfur exceeding 10 parts per million that when exposed to heat or humidity, or both, emits volatile sulfur compounds in quantities that cause observable corrosion on electrical wiring, plumbing pipes, fuel gas lines, or HVAC equipment, or any components of the foregoing or (ii) has been designated by the U.S. Consumer Product Safety Commission as a product with a product defect that constitutes a substantial product hazard within the meaning of § 15(a)(2) of the Consumer Product Safety Act (15 USC § 2064(a)(2)).

J. Section 112.5.1.1.2 Permit. Application for a permit shall be made to the building official and a permit shall be obtained prior to the commencement of remediation work undertaken to remove defective drywall from a building and for the removal, replacement, or repair of corroded electrical, plumbing, mechanical, or fuel gas equipment and components.

K. Section 112.5.1.1.3 Protocol. Where remediation of defective drywall is undertaken, the following standards shall be met. The building official shall be permitted to consider and approve modifications to these standards in accordance with Section 106.3.

L. Section 112.5.1.1.3.1 Drywall. Drywall in the building, whether defective or nondefective, shall be removed and discarded, including fasteners that held any defective drywall to prevent small pieces of drywall from remaining under fasteners.

Exceptions:

1. Nondefective drywall not subject to the corrosive effects of any defective drywall shall be permitted to be left in place in buildings where the defective drywall is limited to a defined room or space or isolated from the rest of the building and the defective drywall can be positively identified. If the room or space containing the defective drywall also contains any nondefective drywall, the nondefective drywall in that room or space shall also be removed.

2. In multi-family buildings where defective drywall was not used in the firewalls between units and there are no affected building systems behind the firewalls, the firewalls shall be permitted to be left in place.

M. Section 112.5.1.1.3.2 Insulation and other building components. Insulation in walls and ceilings shall be removed and discarded. Carpet and vinyl flooring shall be removed and discarded. Woodwork, trim, cabinets, and tile or wood floors may be left in place or may be reused.

Exceptions:

1. Closed-cell foam insulation is permitted to be left in place if testing for off-gassing from defective drywall is negative, unless its removal is required to gain access.
2. Insulation, carpet, or vinyl flooring in areas not exposed to defective drywall or to the effects of defective drywall, may be left in place or reused.

N. Section 112.5.1.1.3.3 Electrical wiring, equipment, devices, and components. All electrical wiring regulated by this code shall be permitted to be left in place, but removal or cleaning of exposed ends of the wiring to reveal clean or uncorroded surfaces is required. All electrical equipment, devices, and components of the electrical system of the building regulated by this code shall be removed and discarded. This shall include all smoke detectors.

Exceptions:

1. Electrical equipment, devices, or components in areas not exposed to the corrosive effects of defective drywall shall be permitted to be left in place or reused. Electrical equipment, devices, or components in areas exposed to the corrosive effects of defective drywall shall be cleaned, repaired, or replaced.
2. Cord and plug connected appliances are not subject to this code and, therefore, cannot be required to be removed or replaced.

Note: All low voltage wiring associated with security systems, door bells, elevator controls, and other such components shall be removed and replaced or repaired.

O. Section 112.5.1.1.3.4 Plumbing and fuel gas piping, fittings, fixtures, and equipment. All copper fuel gas piping and all equipment utilizing fuel gas with copper, silver, or aluminum components shall be removed and discarded. All copper plumbing pipes and fittings shall be removed and discarded. Plumbing fixtures with copper, silver, or aluminum components shall be removed and discarded.

Exception: Plumbing or fuel gas piping, fittings, fixtures, equipment, or components in areas not exposed to the corrosive effects of defective drywall shall be permitted to be left in place or reused.

P. Section 112.5.1.1.3.5 Mechanical systems. All heating, air-conditioning, and ventilation system components, including, but not limited to, ductwork, air-handling units, furnaces, heat pumps, refrigerant lines, and thermostats and associated wiring, shall be removed and discarded.

Exception: Mechanical system components in areas not exposed to the corrosive effects of defective drywall shall be permitted to be left in place or reused.

Q. Section 112.5.1.1.3.6 Cleaning. Following the removal of all materials and components in accordance with Sections 112.5.1.1.3.1 through 112.5.1.1.3.5, the building shall be thoroughly cleaned to remove any particulate matter and dust.

R. Section 112.5.1.1.3.7 Airing out. Following cleaning in accordance with Section 112.5.1.1.3.6, the building shall be thoroughly aired out with the use of open windows and doors and fans.

S. Section 112.5.1.1.3.8 Pre-rebuilding clearance testing. Following the steps outlined above for removal of all materials and components, cleaning and airing out, a pre-rebuilding clearance test shall be conducted with the use of copper or silver coupons and the methodology outlined in the April 2, 2010, joint report by the Consumer Products Safety Commission and the Department of Housing and Urban Development entitled "Interim Remediation Guidance for Homes with Corrosion from Problem Drywall" or with the use of a copper probe and dosimeter. The clearance testing shall confirm that all airborne compounds associated with the defective drywall are at usual environmental background levels. The clearance testing report, certifying compliance, shall be submitted to the building official.

Notes:

1. Where the building is served by a well and prior to conducting clearance tests, all outlets in piping served by the well should be capped or otherwise plugged to prevent contamination of the air sample.

2. To prevent siphoning and evaporation of the trap seals, fixtures should be capped or otherwise plugged to prevent sewer gases from contaminating the air sample.

T. Section 112.5.1.1.3.9 Testing agencies and personnel. Agencies and personnel performing pre-rebuilding or post-rebuilding clearance testing shall be independent of those responsible for all other remediation work and the agencies and personnel shall be appropriately certified or accredited by the Council of Engineering and Scientific Specialty Boards, the American Indoor Air Quality Council, or the World Safety Organization.

Exception: Testing agencies and personnel shall be accepted if certified by an RDP or if the agency employs an RDP to be in responsible charge of the work.

U. Section 112.5.1.1.3.10 Rebuilding standards. The rebuilding of the building shall comply with the edition of the USBC that was in effect when the building was originally built.

V. Section 112.5.1.1.3.11 Post-rebuilding clearance testing. A post-rebuilding clearance test prior to reoccupancy of the building or structure shall be conducted with the use of copper or silver coupons and the methodology outlined in the April 2, 2010, joint report by the Consumer Products Safety Commission and by the Department of Housing and Urban Development entitled "Interim Remediation Guidance for Homes with Corrosion from Problem Drywall" or with the use of a copper probe and dosimeter. The clearance testing shall confirm that all airborne compounds associated with the defective drywall are at usual environmental background levels. The clearance testing report certifying compliance shall be submitted to the building official.

Notes:

1. Where the building is served by a well and prior to conducting clearance tests, all outlets in piping served by the well should be capped or otherwise plugged to prevent contamination of the air sample.

2. To prevent siphoning and evaporation of the trap seals, fixtures should be capped or otherwise plugged to prevent sewer gases from contaminating the air sample.

W. Section 112.5.1.1.4 Final approval by the building official. Once remediation has been completed in accordance with this section, a certificate or letter of approval shall be issued by the building official. The certificate or letter shall state that the remediation and rebuilding is deemed to comply with this code.

X. Section 112.5.1.1.4.1 Approval of remediation occurring prior to these standards. The building official shall issue a certificate or letter of approval for remediation of defective drywall that occurred prior to the effective date of these standards provided post-rebuilding clearance testing has been performed in accordance with Section 112.5.1.1.3.11, by agencies and personnel complying with Section 112.5.1.1.3.9, and the clearance testing confirms that all airborne compounds associated with the defective drywall are at usual environmental background levels. The clearance testing report certifying compliance shall be submitted to the building official.

13VAC5-63-130. Section 113 Inspections.

A. Section 113.1 General. In accordance with § 36-105 of the Code of Virginia, any building or structure may be inspected at any time before completion, and shall not be deemed in compliance until approved by the inspecting authority. Where the construction cost is less than \$2,500, however, the inspection may, in the discretion of the inspecting authority, be waived. The building official shall coordinate all reports of inspections for compliance with the USBC, with inspections of fire and health officials delegated such authority, prior to the issuance of an occupancy permit.

B. Section 113.1.1 Equipment required. Any ladder, scaffolding or test equipment necessary to conduct or witness a requested inspection shall be provided by the permit holder.

C. Section 113.1.2 Duty to notify. When construction reaches a stage of completion that requires an inspection, the permit holder shall notify the building official.

D. Section 113.1.3 Duty to inspect. Except as provided for in Section 113.7, the building official shall perform the requested inspection in accordance with Section 113.6 when notified in accordance with Section 113.1.2.

E. Section 113.2 Prerequisites. The building official may conduct a site inspection prior to issuing a permit. When conducting inspections pursuant to this code, all personnel shall carry proper credentials.

F. Section 113.3 Minimum inspections. The following minimum inspections shall be conducted by the building official when applicable to the construction or permit:

1. Inspection of footing excavations and reinforcement material for concrete footings prior to the placement of concrete.
2. Inspection of foundation systems during phases of construction necessary to assure compliance with this code.
3. Inspection of preparatory work prior to the placement of concrete.
4. Inspection of structural members and fasteners prior to concealment.
5. Inspection of electrical, mechanical and plumbing materials, equipment and systems prior to concealment.
6. Inspection of energy conservation material prior to concealment.
7. Final inspection.

G. Section 113.4 Additional inspections. The building official may designate additional inspections and tests to be conducted during the construction of a building or structure and shall so notify the permit holder.

H. Section 113.5 In-plant and factory inspections. When required by the provisions of this code, materials, equipment or assemblies shall be inspected at the point of manufacture or fabrication. The building official shall require the submittal of an evaluation report of such materials, equipment or assemblies. The evaluation report shall indicate the complete details of the assembly including a description of the assembly and its components, and describe the basis upon which the assembly is being evaluated. In addition, test results and other data as necessary for the building official to determine conformance with the USBC shall be submitted. For factory inspections, an identifying label or stamp permanently affixed to materials, equipment or assemblies indicating that a factory inspection has been made shall be acceptable instead of a written inspection report, provided the intent or meaning of such identifying label or stamp is properly substantiated.

I. Section 113.6 Approval or notice of defective work. The building official shall either approve the work in writing or give written notice of defective work to the permit holder. Upon request of the permit holder, the notice shall reference the USBC section that serves as the basis for the defects and such defects shall be corrected and reinspected before any work proceeds that would conceal such defects. A record of all reports of inspections, tests, examinations, discrepancies and approvals issued shall be maintained by the building official and shall be communicated promptly in writing to the permit holder. Approval issued under this section may be revoked whenever it is discovered that such approval was issued in error or on the basis of incorrect information, or where there are repeated violations of the USBC.

J. Section 113.7 Approved inspection agencies. The building official may accept reports of inspections and tests from individuals or inspection agencies approved in accordance with the building official's written policy required by Section 113.7.1. The individual or inspection agency shall meet the qualifications and reliability requirements established by the written policy. Under circumstances where the building official is unable to make the inspection or

test required by Section 113.3 or 113.4 within two working days of a request or an agreed upon date or if authorized for other circumstances in the building official's written policy, the building official shall accept reports for review. The building official shall approve the report from such approved individuals or agencies unless there is cause to reject it. Failure to approve a report shall be in writing within two working days of receiving it stating the reason for the rejection. Reports of inspections conducted by approved third-party inspectors or agencies shall be in writing, shall indicate if compliance with the applicable provisions of the USBC have been met and shall be certified by the individual inspector or by the responsible officer when the report is from an agency.

Note: Photographs, videotapes or other sources of pertinent data or information may be considered as constituting such reports and tests.

K. Section 113.7.1 Third-party inspectors. Each building official charged with the enforcement of the USBC shall have a written policy establishing the minimum acceptable qualifications for third-party inspectors. The policy shall include the format and time frame required for submission of reports, any prequalification or preapproval requirements before conducting a third-party inspection and any other requirements and procedures established by the building official.

L. Section 113.7.2 Qualifications. In determining third-party inspector qualifications, the building official may consider such items as DHCD inspector certification, other state or national certifications, state professional registrations, related experience, education and any other factors that would demonstrate competency and reliability to conduct inspections.

M. Section 113.8 Final inspection. Upon completion of a building or structure and before the issuance of a certificate of occupancy, a final inspection shall be conducted to ensure that any defective work has been corrected and that all work complies with the USBC and has been approved, including any work associated with modifications under Section 106.3. The approval of a final inspection shall be permitted to serve as the new certificate of occupancy required by Section 116.1 in the case of additions or alterations to existing buildings or structures that already have a certificate of occupancy.

13VAC5-63-140. Section 114 Stop work orders.

A. Section 114.1 Issuance of order. When the building official finds that work on any building or structure is being executed contrary to the provisions of this code or any pertinent laws or ordinances, or in a manner endangering the general public, a written stop work order may be issued. The order shall identify the nature of the work to be stopped and be given either to the owner of the property involved, to the owner's agent or to the person performing the work. Following the issuance of such an order, the affected work shall cease immediately. The order shall state the conditions under which such work may be resumed.

B. Section 114.2 Limitation of order. A stop work order shall apply only to the work identified in the order, provided that other work on the building or structure may be continued if not concealing the work covered by the order.

13VAC5-63-150. Section 115 Violations.

A. Section 115.1 Violation a misdemeanor; civil penalty. In accordance with § 36-106 of the Code of Virginia, it shall be unlawful for any owner or any other person, firm or corporation, on or after the effective date of any code provisions, to violate any such provisions. Any locality may adopt an ordinance that establishes a uniform schedule of civil penalties for violations of specified provisions of the code that are not abated or remedied promptly after receipt of a notice of violation from the local enforcement officer.

Note: See the full text of § 36-106 of the Code of Virginia for additional requirements and criteria pertaining to legal action relative to violations of the code.

B. Section 115.2 Notice of violation. The building official shall issue a written notice of violation to the responsible party if any violations of this code or any directives or orders of the building official have not been corrected or complied with in a reasonable time. The notice shall reference the code section upon which the notice is based and direct the discontinuance and abatement of the violation or the compliance with such directive or order. The notice shall be issued by either delivering a copy to the responsible party by mail to the last known address or delivering the notice in person or by leaving it in the possession of any person in charge of the premises, or by posting the notice in a conspicuous place if the person in charge of the premises cannot be found. The notice of violation shall indicate the right of appeal by referencing the appeals section. When the owner of the building or structure, or the permit holder for the construction in question, or the tenants of such building or structure, are not the responsible party to whom the notice of violation is issued, then a copy of the notice shall also be delivered to the such owner, permit holder or tenants.

C. Section 115.2.1 Notice not to be issued under certain circumstances. When violations are discovered more than two years after the certificate of occupancy is issued or the date of initial occupancy, whichever occurred later, or more than two years after the approved final inspection for an alteration or renovation, a notice of violation shall only be issued upon advice from the legal counsel of the locality that action may be taken to compel correction of the violation. When compliance can no longer be compelled by prosecution under § 36-106 of the Code of Virginia, the building official, when requested by the building owner, shall document in writing the existence of the violation noting the edition of the USBC the violation is under.

D. Section 115.3 Further action when violation not corrected. If the responsible party has not complied with the notice of violation, the building official shall submit a written request to the legal counsel of the locality to institute the appropriate legal proceedings to restrain, correct or abate the violation or to require the removal or termination of the use of the building or structure involved. In cases where the locality so authorizes, the building official may issue or obtain a summons or warrant. Compliance with a notice of violation notwithstanding, the building official may request legal proceedings be instituted for prosecution when a person, firm or corporation is served with three or more notices of violation within one calendar year for failure to obtain a required construction permit prior to commencement of work subject to this code.

Note: See § 19.2-8 of the Code of Virginia concerning the statute of limitations for building code prosecutions.

E. Section 115.4 Penalties and abatement. Penalties for violations of the USBC shall be as set out in § 36-106 of the Code of Virginia. The successful prosecution of a violation of the USBC shall not preclude the institution of appropriate legal action to require correction or abatement of a violation.

F. Section 115.5 Transfer of ownership. In accordance with § 36-105 of the Code of Virginia, if the local building department has initiated an enforcement action against the owner of a building or structure and such owner subsequently transfers the ownership of the building or structure to an entity in which the owner holds an ownership interest greater than 50%, the pending enforcement action shall continue to be enforced against the owner.

13VAC5-63-160. Section 116 Certificates of occupancy.

A. Section 116.1 General; when to be issued. A certificate of occupancy indicating completion of the work for which a permit was issued shall be obtained prior to the occupancy of any building or structure, except as provided for in this section generally and as specifically provided for in Section 113.8 for additions or alterations. The certificate shall be issued after completion of the final inspection and when the building or structure is in compliance with this code and any pertinent laws or ordinances, or when otherwise entitled. The building official shall, however, issue a certificate of occupancy within five working days after being requested to do so, provided the building or structure meets all of the requirements for a certificate.

Exception: A certificate of occupancy is not required for an accessory structure as defined in the International Residential Code.

B. Section 116.1.1 Temporary certificate of occupancy. Upon the request of a permit holder, a temporary certificate of occupancy may be issued before the completion of the work covered by a permit, provided that such portion or portions of a building or structure may be occupied safely prior to full completion of the building or structure without endangering life or public safety.

C. Section 116.2 Contents of certificate. A certificate of occupancy shall specify the following:

1. The edition of the USBC under which the permit is issued.
2. The group classification and occupancy in accordance with the provisions of Chapter 3.
3. The type of construction as defined in Chapter 6.
4. If an automatic sprinkler system is provided and whether or not such system was required.
5. Any special stipulations and conditions of the building permit and if any modifications were issued under the permit, there shall be a notation on the certificate that modifications were issued.

D. Section 116.3 Suspension or revocation of certificate. A certificate of occupancy may be revoked or suspended whenever the building official discovers that such certificate was issued in error or on the basis of incorrect information, or where there are repeated violations of the USBC after the certificate has been issued or when requested by the code official under Section 105.7 of the Virginia Maintenance Code. The revocation or suspension shall be in writing and shall state the necessary corrections or conditions for the certificate to be reissued or reinstated in accordance with Section 116.3.1.

E. Section 116.3.1 Reissuance of reinstatement of certificate of occupancy. When a certificate of occupancy has been revoked or suspended, it shall be reissued or reinstated upon correction of the specific condition or conditions cited as the cause of the revocation or suspension and the revocation or suspension of a certificate of occupancy shall not be used as justification for requiring a building or structure to be subject to a later edition of the code than that under which such building or structure was initially constructed.

F. Section 116.4 Issuance of certificate for pre-USBC buildings or structures. When a building or structure was constructed prior to being subject to the initial edition of the USBC and the local building department does not have a certificate of occupancy for the building or structure, the owner or owner's agent may submit a written request for a certificate to be created. The building official, after receipt of the request, shall issue a certificate provided a determination is made that there are no current violations of the Virginia Maintenance Code or the Virginia Statewide Fire Prevention Code (13VAC5-51) and the occupancy classification of the building or structure has not changed. Such buildings and structures shall not be prevented from continued use.

Exception: When no certificate exists, but the local building department has records indicating that a certificate did exist, then the building official may either verify in writing that a certificate did exist or issue a certificate based upon the records.

13VAC5-63-170. Section 117 Temporary and moved buildings and structures; demolition.

A. Section 117.1 Temporary building and structures. The building official is authorized to issue a permit for temporary buildings or structures. Such permits shall be limited as to time of service, but shall not be permitted for more than one year, except that upon the permit holder's written request, the building official may grant one or more extensions of time, not to exceed one year per extension. The building official is authorized to terminate the approval and order the demolition or removal of temporary buildings or structures during the period authorized by the permit when determined necessary.

B. Section 117.2 Moved buildings and structures. Any building or structure moved into a locality or moved to a new location within a locality shall not be occupied or used until a certification of occupancy is issued for the new location. Such moved buildings or structures shall be required to comply with the requirements of this code for a newly constructed building or structure unless meeting all of the following requirements relative to the new location:

1. There is no change in the occupancy classification from its previous location.

2. The building or structure was in compliance with all state and local requirements applicable to it in its previous location and is in compliance with all state and local requirements applicable if originally constructed in the new location.

3. The building or structure did not become unsafe during the moving process due to structural damage or for other reasons.

4. Any alterations, reconstruction, renovations or repairs made pursuant to the move are in compliance with applicable requirements of this code.

C. Section 117.3 Demolition of buildings and structures. Prior to the issuance of a permit for the demolition of any building or structure, the owner or the owner's agent shall provide certification to the building official that all service connections of utilities have been removed, sealed or plugged satisfactorily and a release has been obtained from the associated utility company. The certification shall further provide that written notice has been given to the owners of adjoining lots and any other lots that may be affected by the temporary removal of utility wires or the temporary disconnection or termination of other services or facilities relative to the demolition. In addition, the requirements of Chapter 33 of the IBC for any necessary retaining walls or fences during demolition shall be applicable and when a building or structure is demolished or removed, the established grades shall be restored.

13VAC5-63-180. Section 118 Buildings and structures becoming unsafe during construction.

A. Section 118.1 Applicability. This section applies to buildings and structures for which a construction permit has been issued under this code and construction has not been completed or a certificate of occupancy has not been issued, or both. In addition, this section applies to any building or structure that is under construction or that was constructed without obtaining the required permits under this edition or any edition of the USBC.

Note: Existing buildings and structures other than those under construction or subject to this section are subject to the Virginia Maintenance Code that also has requirements for unsafe conditions.

B. Section 118.2 Repair or removal of unsafe buildings or structures. Any building or structure subject to this section that is either deteriorated, improperly maintained, of faulty construction, deficient in adequate exit facilities, a fire hazard or dangerous to life or the public welfare, or both, or any combination of the foregoing, is an unsafe building or structure and shall be made safe through compliance with this code or shall be taken down and removed if determined necessary by the building official.

C. Section 118.3 Inspection report and notice of unsafe building or structure. The building official shall inspect any building or structure reported to be unsafe and shall prepare a report to be filed in the records of the local building department. In addition to a description of any unsafe conditions found, the report shall include the occupancy classification of the building or structure and the nature and extent of any damages caused by collapse or failure of any building components. If the building or structure is determined by the building official to be unsafe, a notice of unsafe building or structure shall be issued in person to the owner and any

permit holder. The notice shall describe any unsafe conditions and specify any repairs or improvements necessary to make the building or structure safe, or alternatively, when determined necessary by the building official, require the unsafe building or structure, or any portion of it, to be taken down and removed. The notice shall stipulate a time period for the repair or demolition of the unsafe building or structure and contain a statement requiring the person receiving the notice to determine whether to accept or reject the terms of the notice. If any persons to which the notice of unsafe building or structure is to be issued cannot be found after diligent search, as equivalent service, the notice shall be sent by registered or certified mail to the last known address of such persons and a copy of the notice posted in a conspicuous place on the premises.

D. Section 118.4 Vacating the unsafe building or structure. If any portion of an unsafe building or structure has collapsed or fallen, or if the building official determines there is actual and immediate danger of any portion collapsing or falling, and when life is endangered by the occupancy of the unsafe building or structure, the building official shall be authorized to order the occupants to immediately vacate the unsafe building or structure. When an unsafe building or structure is ordered to be vacated, the building official shall post a notice at each entrance that reads as follows:

“This Building (or Structure) is Unsafe and its Occupancy (or Use) is Prohibited by the Building Official.”

After posting, occupancy or use of the unsafe structure shall be prohibited except when authorized to enter to conduct inspections, make required repairs or as necessary to demolish the building or structure.

E. Section 118.5 Emergency repairs and demolition. To the extent permitted by the locality, the building official may authorize emergency repairs to unsafe buildings or structures when it is determined that there is an immediate danger of any portion of the unsafe building or structure collapsing or falling and when life is endangered. Emergency repairs may also be authorized when there is a code violation resulting in the immediate, serious and imminent threat to the life and safety of the occupants. The building official shall be permitted to authorize the necessary work to make the building or structure temporarily safe whether or not legal action to compel compliance has been instituted.

In addition, whenever an owner of an unsafe building or structure fails to comply with a notice to demolish issued under Section 118.3 in the time period stipulated, the building official shall be permitted to cause the unsafe building or structure to be demolished. In accordance with §§ 15.2-906 and 15.2-1115 of the Code of Virginia, the legal counsel of the locality may be requested to institute appropriate action against the property owner to recover the costs associated with any such emergency repairs or demolition and every such charge that remains unpaid shall constitute a lien against the property on which the emergency repairs or demolition were made and shall be enforceable in the same manner as provided in Articles 3 (§ 58.1-3940 et seq.) and 4 (§ 58.1-3965 et seq.) of Chapter 39 of Title 58.1 of the Code of Virginia.

Note: Building officials and local governing bodies should be aware that other statutes and court decisions may impact on matters relating to demolition, in particular whether newspaper

publication is required if the owner cannot be located and whether the demolition order must be delayed until the owner has been given the opportunity for a hearing.

13VAC5-63-190. Section 119 Appeals.

A. Section 119.1 Establishment of appeals board. In accordance with § 36-105 of the Code of Virginia, there shall be established within each local building department a LBBCA. Whenever a county or a municipality does not have such a LBBCA, the local governing body shall enter into an agreement with the local governing body of another county or municipality or with some other agency, or a state agency approved by DHCD for such appeals resulting therefrom. Fees may be levied by the local governing body in order to defray the cost of such appeals. In addition, as an authorization in this code, separate LBBCAs may be established to hear appeals of different enforcement areas such as electrical, plumbing or mechanical requirements. Each such LBBCA shall comply with the requirements of this section.

B. Section 119.2 Membership of board. The LBBCA shall consist of at least five members appointed by the locality for a specific term of office established by written policy. Alternate members may be appointed to serve in the absence of any regular members and as such, shall have the full power and authority of the regular members. Regular and alternate members may be reappointed. Written records of current membership, including a record of the current chairman and secretary shall be maintained in the office of the locality. In order to provide continuity, the terms of the members may be of different length so that less than half will expire in any one-year period. The LBBCA shall meet at least once annually to assure a duly constituted board, appoint officers as necessary, and receive such training on the code as may be appropriate or necessary from staff of the locality.

C. Section 119.3 Officers and qualifications of members. The LBBCA shall annually select one of its regular members to serve as chairman. When the chairman is not present at an appeal hearing, the members present shall select an acting chairman. The locality or the chief executive officer of the locality shall appoint a secretary to the LBBCA to maintain a detailed record of all proceedings. Members of the LBBCA shall be selected by the locality on the basis of their ability to render fair and competent decisions regarding application of the USBC and shall to the extent possible, represent different occupational or professional fields relating to the construction industry. At least one member should be an experienced builder; at least one member should be an RDP, and at least one member should be an experienced property manager. Employees or officials of the locality shall not serve as members of the LBBCA.

D. Section 119.4 Conduct of members. No member shall hear an appeal in which that member has a conflict of interest in accordance with the State and Local Government Conflict of Interests Act (§ 2.2-3100 et seq. of the Code of Virginia). Members shall not discuss the substance of an appeal with any other party or their representatives prior to any hearings.

E. Section 119.5 Right of appeal; filing of appeal application. Any person aggrieved by the local building department's application of the USBC or the refusal to grant a modification to the provisions of the USBC may appeal to the LBBCA. The applicant shall submit a written request for appeal to the LBBCA within 30 calendar days of the receipt of the decision being appealed. The application shall contain the name and address of the owner of the building or structure and in addition, the name and address of the person appealing, when the applicant is

not the owner. A copy of the building official's decision shall be submitted along with the application for appeal and maintained as part of the record. The application shall be marked by the LBBCA to indicate the date received. Failure to submit an application for appeal within the time limit established by this section shall constitute acceptance of a building official's decision.

Note: To the extent that a decision of a building official pertains to amusement devices there may be a right of appeal under the VADR.

F. Section 119.6 Meetings and postponements. The LBBCA shall meet within 30 calendar days after the date of receipt of the application for appeal, except that a longer time period shall be permitted if agreed to by all the parties involved in the appeal. A notice indicating the time and place of the hearing shall be sent to the parties in writing to the addresses listed on the application at least 14 calendar days prior to the date of the hearing, except that a lesser time period shall be permitted if agreed to by all the parties involved in the appeal. When a quorum of the LBBCA is not present at a hearing to hear an appeal, any party involved in the appeal shall have the right to request a postponement of the hearing. The LBBCA shall reschedule the appeal within 30 calendar days of the postponement, except that a longer time period shall be permitted if agreed to by all the parties involved in the appeal.

G. Section 119.7 Hearings and decision. All hearings before the LBBCA shall be open meetings and the appellant, the appellant's representative, the locality's representative and any person whose interests are affected by the building official's decision in question shall be given an opportunity to be heard. The chairman shall have the power and duty to direct the hearing, rule upon the acceptance of evidence and oversee the record of all proceedings. The LBBCA shall have the power to uphold, reverse or modify the decision of the official by a concurring vote of a majority of those present. Decisions of the LBBCA shall be final if no further appeal is made. The decision of the LBBCA shall be by resolution signed by the chairman and retained as part of the record of the appeal. Copies of the resolution shall be sent to all parties by certified mail. In addition, the resolution shall contain the following wording:

"Any person who was a party to the appeal may appeal to the State Review Board by submitting an application to such Board within 21 calendar days upon receipt by certified mail of this resolution. Application forms are available from the Office of the State Review Board, 600 East Main Street, Richmond, Virginia 23219, (804) 371-7150."

H. Section 119.8 Appeals to the State Review Board. After final determination by the LBBCA in an appeal, any person who was a party to the appeal may further appeal to the State Review Board. In accordance with § 36-98.2 of the Code of Virginia for state-owned buildings and structures, appeals by an involved state agency from the decision of the building official for state-owned buildings or structures shall be made directly to the State Review Board. The application for appeal shall be made to the State Review Board within 21 calendar days of the receipt of the decision to be appealed. Failure to submit an application within that time limit shall constitute an acceptance of the building official's decision. For appeals from a LBBCA, a copy of the building official's decision and the resolution of the LBBCA shall be submitted with the application for appeal to the State Review Board. Upon request by the office of the State Review Board, the LBBCA shall submit a copy of all pertinent information from the

record of the appeal. In the case of appeals involving state-owned buildings or structures, the involved state agency shall submit a copy of the building official's decision and other relevant information with the application for appeal to the State Review Board. Procedures of the State Review Board are in accordance with Article 2 (§ 36-108 et seq.) of Chapter 6 of Title 36 of the Code of Virginia. Decisions of the State Review Board shall be final if no further appeal is made.

13VAC5-63-200. Chapter 2 Definitions: ~~Section 202 Definitions.~~

A. Add the following definitions to Section 202 of the IBC to read:

Aboveground liquid fertilizer storage tank (ALFST). A device that contains an accumulation of liquid fertilizer (i) constructed of nonearthen materials, such as concrete, steel or plastic, that provide structural support; (ii) having a capacity of 100,000 gallons (378 500 L) or greater; and (iii) the volume of which is more than 90% above the surface of the ground. The term does not include any wastewater treatment or wastewater storage tank, utility or industry pollution control equipment.

Building regulations. Any law, rule, resolution, regulation, ordinance or code, general or special, or compilation thereof, heretofore or hereafter enacted or adopted by the Commonwealth or any county or municipality, including departments, boards, bureaus, commissions, or other agencies thereof, relating to construction, reconstruction, alteration, conversion, repair, maintenance, or use of structures and buildings and installation of equipment therein. The term does not include zoning ordinances or other land use controls that do not affect the manner of construction or materials to be used in the erection, alteration or repair of a building or structure.

Change of occupancy. A change in the use or occupancy of any building or structure which would place the building or structure in a different division of the same group of occupancies or in a different group of occupancies; or a change in the purpose or level of activity within a building or structure that involves a change in application of the requirements of this code.

Construction. The construction, reconstruction, alteration, repair, or conversion of buildings and structures.

Day-night average sound level (Ldn). ~~See Section 1202.1~~ A 24-hour energy average sound level expressed in dBA, with a 10 decibel penalty applied to noise occurring between 10 p.m. and 7 a.m.

DHCD. The Virginia Department of Housing and Community Development.

Emergency communication equipment. ~~See Section 902.1~~ Emergency communication equipment, includes but is not limited to, two-way radio communications, signal booster, bi-directional amplifiers, radiating cable systems or internal multiple antenna, or a combination of the foregoing.

Emergency public safety personnel. ~~See Section 902.1~~ Emergency public safety personnel includes firefighters, emergency medical personnel, law-enforcement officers and other

emergency public safety personnel routinely called upon to provide emergency assistance to members of the public in a wide variety of emergency situations, including, but not limited to, fires, medical emergencies, violent crimes and terrorist attacks.

Equipment. Plumbing, heating, electrical, ventilating, air-conditioning and refrigeration equipment, elevators, dumbwaiters, escalators, and other mechanical additions or installations.

Farm building or structure. A building or structure not used for residential purposes, located on property where farming operations take place, and used primarily for any of the following uses or combination thereof:

1. Storage, handling, production, display, sampling or sale of agricultural, horticultural, floricultural or silvicultural products produced in the farm.
2. Sheltering, raising, handling, processing or sale of agricultural animals or agricultural animal products.
3. Business or office uses relating to the farm operations.
4. Use of farm machinery or equipment or maintenance or storage of vehicles, machinery or equipment on the farm.
5. Storage or use of supplies and materials used on the farm.
6. Implementation of best management practices associated with farm operations.

Industrialized building. A combination of one or more sections or modules, subject to state regulations and including the necessary electrical, plumbing, heating, ventilating and other service systems, manufactured off-site and transported to the point of use for installation or erection, with or without other specified components, to comprise a finished building. Manufactured homes shall not be considered industrialized buildings for the purpose of this code.

Hospice facility. See Section 308.3.1 An institution, place, or building owned or operated by a hospice provider and licensed by the Virginia Department of Health as a hospice facility to provide room, board, and palliative and supportive medical and other health services to terminally ill patients and their families, including respite and symptom management, on a 24-hour basis to individuals requiring such care pursuant to the orders of a physician.

LBBCA. Local board of building code appeals.

Liquid fertilizer. A fluid in which a fertilizer is in true solution. This term does not include anhydrous ammonia or a solution used in pollution control.

Local building department. The agency or agencies of any local governing body charged with the administration, supervision, or enforcement of this code, approval of construction

documents, inspection of buildings or structures, or issuance of permits, licenses, certificates or similar documents.

Local governing body. The governing body of any city, county or town in this Commonwealth.

Locality. A city, county or town in this Commonwealth.

Manufactured home. A structure subject to federal regulation, which is transportable in one or more sections; is eight body feet or more in width and 40 body feet or more in length in the traveling mode, or is 320 or more square feet when erected on site; is built on a permanent chassis; is designed to be used as a single-family dwelling, with or without a permanent foundation, when connected to the required utilities; and includes the plumbing, heating, air-conditioning, and electrical systems contained in the structure.

Night club. Any building in which the main use is a place of public assembly that provides exhibition, performance or other forms of entertainment; serves alcoholic beverages; and provides music and space for dancing.

Skirting. A weather-resistant material used to enclose the space from the bottom of the manufactured home to grade.

Sound transmission class (STC) rating. ~~See Section 1202.1~~ A single number characterizing the sound reduction performance of a material tested in accordance with ASTM E90-90, "Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions."

State regulated care facility (SRCF). A building with an occupancy in Group R-2, R-3, R-4 or R-5 occupied by persons in the care of others where program oversight is provided by the Virginia Department of Social Services, the Virginia Department of Behavioral Health and Developmental Services, the Virginia Department of Education or the Virginia Department of Juvenile Justice.

State Review Board. The Virginia State Building Code Technical Review Board as established under § 36-108 of the Code of Virginia.

Technical assistant. Any person employed by or under an extended contract to a local building department or local enforcing agency for enforcing the USBC, including but not limited to inspectors and plans reviewers. For the purpose of this definition, an extended contract shall be a contract with an aggregate term of 18 months or longer.

~~Technical production area. See Section 410.2.~~

VADR. The Virginia Amusement Device Regulations (13VAC5-31).

VCS. The Virginia Certification Standards (13VAC5-21).

Working day. A day other than Saturday, Sunday or a legal local, state or national holiday.

B. Change the following definitions in Section 202 of the IBC to read:

Ambulatory health care facility. Buildings or portions thereof that are licensed by the Virginia Department of Health as outpatient surgical hospitals.

Automatic fire-extinguishing system. An approved system of devices and equipment which automatically detects a fire and discharges an approved fire-extinguishing agent onto or in the area of a fire and shall include among other systems an automatic sprinkler system, unless otherwise expressly stated.

Building. A combination of materials, whether portable or fixed, having a roof to form a structure for the use or occupancy by persons, or property. The word "building" shall be construed as though followed by the words "or part or parts thereof" unless the context clearly requires a different meaning. "Building" shall not include roadway tunnels and bridges owned by the Virginia Department of Transportation, which shall be governed by construction and design standards approved by the Virginia Commonwealth Transportation Board.

For application of this code, each portion of a building that is completely separated from other portions by fire walls complying with Section 706 shall be considered as a separate building (see Section 503.1).

Owner. The owner or owners of the freehold of the premises or lesser estate therein, a mortgagee or vendee in possession, assignee of rents, receiver, executor, trustee or lessee in control of a building or structure.

Registered Design Professional (RDP). An architect or professional engineer, licensed to practice architecture or engineering, as defined under § 54.1-400 of the Code of Virginia.

Structure. An assembly of materials forming a construction for occupancy or use including stadiums, gospel and circus tents, reviewing stands, platforms, stagings, observation towers, radio towers, water tanks, storage tanks (underground and aboveground), trestles, piers, wharves, swimming pools, amusement devices, storage bins, and other structures of this general nature but excluding water wells. The word "structure" shall be construed as though followed by the words "or part or parts thereof" unless the context clearly requires a different meaning. "Structure" shall not include roadway tunnels and bridges owned by the Virginia Department of Transportation, which shall be governed by construction and design standards approved by the Virginia Commonwealth Transportation Board.

C. Delete the following definitions from Section 202 of the IBC:

Agricultural; building.

Existing structure (For Chapter 34).

Fly gallery.

Gridiron.

13VAC5-63-210. Chapter 3 Use and occupancy classification.

A. Change exception 13 of Section 307.1 of the IBC to read:

13. The storage of black powder, smokeless propellant and small arms primers in Groups M, R-3 and R-5 and special industrial explosive devices in Groups B, F, M and S, provided such storage conforms to the quantity limits and requirements prescribed in the International Fire Code, as amended in Section 307.9.

B. Add Section 307.9 to the IBC to read:

307.9 Amendments. The following changes shall be made to the International Fire Code for the use of Exception 13 in Section 307.1:

1. Change the following definition in Section 202 of the International Fire Code to read:

Smokeless Propellants. Solid propellants, commonly referred to as smokeless powders, or any propellants classified by DOTn as smokeless propellants in accordance with NA3178 (Smokeless Powder for Small Arms), used in small arms ammunition, firearms, cannons, rockets, propellant-actuated devices and similar articles.

2. Change Section 314.1 of the IFC International Fire Code to read as follows:

314.1 General. Indoor displays constructed within any building or structure shall comply with Sections 314.2 through 314.5.

2. 3. Add new Section 314.5 to the IFC International Fire Code to read as follows:

314.5 Smokeless powder and small arms primers. Vendors shall not store, display or sell smokeless powder or small arms primers during trade shows inside exhibition halls except as follows:

1. The amount of smokeless powder each vender may store is limited to the storage arrangements and storage amounts established in Section ~~3306.5.2.1~~ 5506.5.2.1.

2. Smokeless powder shall remain in the manufacturer's original sealed container and the container shall remain sealed while inside the building. The repackaging of smokeless powder shall not be performed inside the building. Damaged containers shall not be repackaged inside the building and shall be immediately removed from the building in such manner to avoid spilling any powder.

3. There shall be at least 50 feet separation between vendors and 20 feet from any exit.

4. Small arms primers shall be displayed and stored in the manufacturer's original packaging and in accordance with the requirements of Section ~~3306.5.2.3~~ 5506.5.2.3.

3. ~~4.~~ Change Exception 4 and add Exceptions 10 and 11 to Section ~~3301.1~~ 5501.1 of the IFC International Fire Code as follows:

4. The possession, storage and use of not more than 15 pounds (6.75 kg) of commercially manufactured sporting black powder, 20 pounds (9 kg) of smokeless powder and any amount of small arms primers for hand loading of small arms ammunition for personal consumption.

10. The display of small arms primers in Group M when in the original manufacturer's packaging.

11. The possession, storage and use of not more than 50 pounds (23 kg) of commercially manufactured sporting black powder, 100 pounds (45 kg) of smokeless powder, and small arms primers for hand loading of small arms ammunition for personal consumption in Group R-3 or R-5, or 200 pounds (91 kg) of smokeless powder when stored in the manufacturer's original containers in detached Group U structures at least 10 feet (3048 mm) from inhabited buildings and are accessory to Group R-3 or R-5.

4. ~~Change the definition of Smokeless Propellants in Section 3302.1 of the IFC as follows:~~

~~SMOKELESS PROPELLANTS. Solid propellants, commonly referred to as smokeless powders, or any propellants classified by DOT as smokeless propellants in accordance with NA3178 (Smokeless Powder for Small Arms), used in small arms ammunition, firearms, cannons, rockets, propellant-actuated devices and similar articles.~~

5. Change Section ~~3306.4~~ 5606.4 of the IFC International Fire Code to read as follows:

~~3306.4~~ 5506.4 Storage in residences. Propellants for personal use in quantities not exceeding 50 pounds (23 kg) of black powder or 100 pounds (45 kg) of smokeless powder shall be stored in original containers in occupancies limited to Group R-3 and R-5 or 200 pounds (91 kg) of smokeless powder when stored in the manufacturer's original containers in detached Group U structures at least 10 feet (3048 mm) from inhabited buildings and are accessory to Group R-3 or R-5. In other than Group R-3 or R-5, smokeless powder in quantities exceeding 20 pounds (9 kg) but not exceeding 50 pounds (23 kg) shall be kept in a wooden box or cabinet having walls of at least one inch (25 mm) nominal thickness or equivalent.

6. Delete Sections ~~3306.4.1~~ 5506.4.1 and ~~3306.4.2~~ 5506.4.2 of the IFC International Fire Code.

7. Change Section ~~3306.5.1.1~~ 5506.5.1.1 of the IFC International Fire Code to read as follows:

~~3306.5.1.1~~ 5506.5.1.1 Smokeless propellant. No more than 100 pounds (45 kg) of smokeless propellants in containers of eight pounds (3.6 kg) or less capacity shall be displayed in Group M occupancies.

8. Delete Section ~~3306.5.1.3~~ 5506.5.1.3 of the ~~IFC~~ International Fire Code.

9. Change Section ~~3306.5.2.1~~ 5506.5.2.1 of the ~~IFC~~ International Fire Code as follows:

~~3306.5.2.1~~ 5506.5.2.1 Smokeless propellant. Commercial stocks of smokeless propellants shall be stored as follows:

1. Quantities exceeding 20 pounds (9 kg), but not exceeding 100 pounds (45 kg) shall be stored in portable wooden boxes having walls of at least one inch (25 mm) nominal thickness or equivalent.

2. Quantities exceeding 100 pounds (45 kg), but not exceeding 800 pounds (363 kg), shall be stored in storage cabinets having walls at least one inch (25 mm) nominal thickness or equivalent. Not more than 400 pounds (182 kg) shall be stored in any one cabinet, and cabinets shall be separated by a distance of at least 25 feet (7620 mm) or by a fire partition having a fire-resistance rating of at least one hour.

3. Storage of quantities exceeding 800 pounds (363 kg), but not exceeding 5,000 pounds (2270 kg) in a building shall comply with all of the following:

3.1. The storage is inaccessible to unauthorized personnel.

3.2. Smokeless propellant shall be stored in nonportable storage cabinets having wood walls at least one inch (25 mm) nominal thickness or equivalent and having shelves with no more than 3 feet (914 mm) of vertical separation between shelves.

3.3. No more than 400 pounds (182 kg) is stored in any one cabinet.

3.4. Cabinets shall be located against walls with at least 40 feet (12 192 mm) between cabinets. The minimum required separation between cabinets may be reduced to 20 feet (6096 mm) provided that barricades twice the height of the cabinets are attached to the wall, midway between each cabinet. The barricades must extend a minimum of 10 feet (3048 mm) outward, be firmly attached to the wall, and be constructed of steel not less than 0.25 inch thick (6.4 mm), 2-inch (51 mm) nominal thickness wood, brick, or concrete block.

3.5. Smokeless propellant shall be separated from materials classified as combustible liquids, flammable liquids, flammable solids, or oxidizing materials by a distance of 25 feet (7620 mm) or by a fire partition having a fire-resistance rating of 1 hour.

3.6. The building shall be equipped throughout with an automatic sprinkler system installed in accordance with Section 903.3.1.1.

4. Smokeless propellants not stored according to Item 1, 2, or 3 above shall be stored in a Type 2 or 4 magazine in accordance with Section 3304 and NFPA 495.

C. ~~Change~~ Add the following to the list of terms in Section 308.2 of the IBC ~~to read:~~

Hospice facility.

D. Change Section 308.3 of the IBC to read:

~~308.2~~ 308.3 Institutional Group I-1. This occupancy shall include buildings, structures or ~~parts~~ portions thereof ~~housing for more than 16 persons, who reside on a 24-hour basis, who because of age, mental disability or other reasons, live in a supervised residential environment that provides personal and receive custodial care services.~~ The occupants persons receiving care are capable of responding to an emergency situation without physical assistance from staff self preservation. This group shall include, but not be limited to, the following:

Alcohol and drug centers

Assisted living facilities

Congregate care facilities

Group homes

Halfway houses

Residential board and custodial care facilities

Social rehabilitation facilities

Exception: In Group I-1 occupancies, not more than five of the residents may require physical assistance from staff to respond to an emergency situation when all residents that may require the physical assistance reside on a single level of exit discharge.

~~A facility such as the above with five or fewer persons shall be classified as a Group R-3 or shall comply with the International Residential Code in accordance with Section 101.2. A facility such as above, housing at least six and not more than 16 persons, shall be classified as Group R-4.~~

D. E. ~~Change~~ Section 308.3 308.4 of the IBC to read:

~~308.3~~ 308.4 Group I-2. This occupancy shall include buildings and structures used for ~~medical, surgical, psychiatric, nursing or custodial care~~ on a 24-hour basis for more than five persons who are not capable incapable of self-preservation. This group shall include, but not be limited to, the following:

Child-care facilities

Convalescent facilities

Foster care facilities

Detoxification facilities

Hospice facilities

Hospitals

Mental hospitals

Nursing homes

Psychiatric hospitals

Exception: Hospice facilities occupied by 16 or less occupants, excluding staff, are permitted to be classified as Group R-4.

E. ~~Add the following definition to Section 308.3.1 of the IBC:~~

~~Hospice facility. An institution, place, or building owned or operated by a hospice provider and licensed by the Virginia Department of Health as a hospice facility to provide room, board, and palliative and supportive medical and other health services to terminally ill patients and their families, including respite and symptom management, on a 24-hour basis to individuals requiring such care pursuant to the orders of a physician.~~

F. Change Add an exception to Section 308.5.2 308.6 of the IBC to read:

~~308.5.2 Child care facility. A facility other than family day homes under Section 310.4 that provides supervision and personal care on less than a 24-hour basis for more than five children 2 1/2 years of age or less shall be classified as Group I-4.~~

~~Exception: A child day care facility that provides care for more than five but no more than 100 children 2 1/2 years or less of age, where the rooms in which the children are cared for are located on a level of exit discharge serving such rooms and each of these child care rooms has an exit door directly to the exterior, shall be classified as Group E Family days homes under Section 310.9.~~

G. Change occupancy classifications "R-1" and "R-4" and add new occupancy classification "R-5" to Section 310 Section 310.3 of the IBC to read:

310.3 Residential Group R-1. Residential occupancies containing sleeping units where the occupants are primarily transient in nature, including:

Boarding houses (transient) with more than 10 occupants

Congregate living facilities (transient) with more than 10 occupants

Hotels (transient)

Motels (transient)

~~Congregate living facilities (transient) with 10 or fewer occupants are permitted to comply with the construction requirements for Group R-3.~~

Exceptions:

1. Nonproprietor occupied bed and breakfast and other transient boarding facilities not more than three stories above grade plane in height with a maximum of 10 occupants total are permitted to be classified as either Group R-3 or Group R-5 provided that smoke alarms are installed in compliance with Section ~~907.2.10.1.2~~ 907.2.11.2 for Group R-3 or Section ~~313.1~~ R314 of the International Residential Code for Group R-5.
2. Proprietor occupied bed and breakfast and other transient boarding facilities not more than three stories above grade plane in height, that are also occupied as the residence of the proprietor, with a maximum of five guest room sleeping units provided for the transient occupants are permitted to be classified as either Group R-3 or R-5 provided that smoke alarms are installed in compliance with Section ~~907.2.10.1.2~~ 907.2.11.2 for Group R-3 or Section ~~313.1~~ R314 of the International Residential Code for Group R-5.

H. Change Section 310.6 of the IBC to read:

310.6 Residential Group R-4. Residential occupancies This occupancy shall include buildings arranged for occupancy as residential care/assisted living facilities including structures or portions thereof for more than five but not more than 16 occupants persons, excluding staff and buildings arranged for occupancy as, who reside on a 24-hour basis in a supervised environment and receive custodial care. The persons receiving care are capable of self-preservation. This group shall include, but not be limited to, the following:

Alcohol and drug centers

Assisted living facilities

Congregate care facilities

Group homes

Halfway houses

Residential board and custodial care facilities

Social rehabilitation facilities

This occupancy shall also include hospice facilities with not more than 16 occupants, excluding staff.

Group R-4 occupancies shall meet the requirements for construction as defined for Group R-3, except as otherwise provided for in this code, or shall comply with the IRC provided the building is protected by an automatic sprinkler system installed in accordance with Section 903.2.7 903.2.8.

Exceptions:

1. Group homes licensed by the Virginia Department of Behavioral Health and Developmental Services that house no more than eight persons with one or more resident counselors shall be classified as Group R-2, R-3, R-4 or R-5. Not more than five of the persons may require physical assistance from staff to respond to an emergency situation.
2. In Group R-4 occupancies, not more than five of the residents may require physical assistance from staff to respond to an emergency situation when all residents who may require the physical assistance from staff reside on a single level of exit discharge and other than using a ramp, a change of elevation using steps or stairs is not within the path of egress to an exit door.
3. Assisted living facilities licensed by the Virginia Department of Social Services that house no more than eight persons, with one or more resident counselors, and all of the residents are capable of responding to an emergency situation without physical assistance from staff, may be classified as Group R-2, R-3 or R-5.
4. Assisted living facilities licensed by the Virginia Department of Social Services that house no more than eight persons, with one or more resident counselors, may be classified as Group R-5 when in compliance with all of the following:
 - 4.1. The building is protected by an automatic sprinkler system installed in accordance with Section 903.3 or Section P2904 of the IRC.
 - 4.2. Not more than five of the residents may require physical assistance from staff to respond to an emergency situation.
 - 4.3. All residents who may require physical assistance from staff to respond to an emergency situation reside on a single level of exit discharge and other than using a ramp, a change in elevation using steps or stairs is not within the path of egress to an exit door.
5. Hospice facilities with five or fewer occupants are permitted to comply with the IRC provided the building is protected by an automatic sprinkler system in accordance with IRC Section P2904 or IBC Section 903.3.

I. Add Section 310.7 to the IBC to read:

310.7 Residential Group R-5. Residential occupancies in detached one- and two-family dwellings, townhouses and accessory structures within the scope of the International Residential Code, also referred to as the “IRC.” IRC.

~~H.~~ H. Change the definition of “Residential care/assisted living facilities” in Section 310.2 of the IBC to read:

~~Residential care/assisted living facilities. Any congregate residential setting that provides or coordinates personal and health care services, 24-hour supervision and assistance for the maintenance or care of four or more adults who are aged, infirm or disabled and who are cared for in a primarily residential setting, and provides for the protection, general supervision and oversight of the physical and mental well being of aged, infirmed or disabled individuals. Residents are capable of self-evacuation.~~

~~I.~~ J. Add Section ~~310.3~~ 310.8 to the IBC to read:

~~310.3~~ 310.8 Group R-5. The construction of Group R-5 structures shall comply with the IRC. The amendments to the IRC set out in Section ~~310.6~~ 310.11 shall be made to the IRC for its use as part of this code. ~~In addition, all references to Section 101.2 in the IBC relating to the construction of such structures subject to the IRC shall be considered to be references to this section.~~

~~J.~~ K. Add Section ~~310.3.1~~ 310.8.1 to the IBC to read:

~~310.3.1~~ 310.8.1 Additional requirements. Methods of construction, materials, systems, equipment or components for Group R-5 structures not addressed by prescriptive or performance provisions of the IRC shall comply with applicable IBC requirements.

~~K.~~ L. Add Section ~~310.4~~ 310.9 to the IBC to read:

~~310.4~~ 310.9 Family day homes. Family day homes where program oversight is provided by the Virginia Department of Social Services shall be classified as Group R-2, R-3 or R-5.

Note: Family day homes may generally care for up to 12 children. See the DHCD Related Laws Package for additional information.

~~L.~~ M. Add Section ~~310.5~~ 310.10 to the IBC to read:

~~310.5~~ 310.10 Radon-resistant construction in Group R-3 and R-4 structures. Group R-3 and R-4 structures shall be subject to the radon-resistant construction requirements in Appendix F of the IRC in localities enforcing such requirements pursuant to Section ~~R325~~ R324 of the IRC.

~~M.~~ N. Add Section ~~310.6~~ 310.11 to the IBC to read:

~~310.6~~ 310.11 Amendments to the IRC. The following changes shall be made to the IRC for its use as part of this code:

1. Change Section R301.2.1 to read:

~~R301.2.1 Wind limitations design criteria. Buildings and portions thereof shall be limited by constructed in accordance with the wind provisions of this code using the basic wind speed, as defined in Table R301.2(1), and construction methods in accordance with this code. Basic wind speeds shall be determined from Figure R301.2(4). Where different construction methods and structural materials are used for various portions of a building, the applicable requirements of this section for each portion shall apply. Where loads for wall coverings, curtain walls, roof coverings, exterior windows, skylights, garage doors and exterior doors are not otherwise specified, the loads listed in Table R301.2(2) adjusted for height and exposure using Table R301.2(3) shall be used to determine design load performance requirements for wall coverings, curtain walls, roof coverings, exterior windows, skylights, garage doors and exterior doors. Asphalt shingles shall be designed for wind speeds in accordance with Section R905.2.6 as determined from Figure R301.2(4)A. The structural provisions of this code for wind loads are not permitted where wind design is required as specified in Section R301.2.1.1. Where different construction methods and structural materials are used for various portions of a building, the applicable requirements of this section for each portion shall apply. Where not otherwise specified, the wind loads listed in Table R301.2(2) adjusted for height and exposure using Table R301.2(3) shall be used to determine design load performance requirements for wall coverings, curtain walls, roof coverings, exterior windows, skylights, garage doors and exterior doors. Asphalt shingles shall be designed for wind speeds in accordance with Section R905.2.4. A continuous load path shall be provided to transmit the applicable uplift forces in Section R802.11.1 from the roof assembly to the foundation. Wind speeds for localities in special wind regions, near mountainous terrain, and near gorges shall be based on elevation. Areas at 4,000 feet in elevation or higher shall use 110 V mph (48.4 m/s) and areas under 4,000 feet in elevation shall use 90 V mph (39.6 m/s). Gorge areas shall be based on the highest recorded speed per locality or in accordance with local jurisdiction requirements determined in accordance with Section 6.5.4 26.5.1 of ASCE 7.~~

2. Change Section R301.2.1.1 to read:

~~R301.2.1.1 Design criteria. Construction in regions where the basic wind speeds from Figure R301.2(4) equal or exceed 110 miles per hour (49 m/s) shall be designed in accordance with one of the following methods. The elements of design not addressed by these documents in items 1 through 4 shall be in accordance with this code.~~

~~1. American Forest and Paper Association (AF&PA) Wood Frame Construction Manual for One and Two Family Dwellings (WFCM); or~~

~~2. International Code Council (ICC) Standard for Residential Construction in High Wind Regions (ICC-600); or~~

~~3. Minimum Design Loads for Buildings and Other Structures (ASCE 7); or~~

~~4. American Iron and Steel Institute (AISI), Standard for Cold Formed Steel Framing Prescriptive Method for One and Two Family Dwellings (AISI S230).~~

~~5. Concrete construction shall be designed in accordance with the provisions of this code.~~

~~6. Structural insulated panel (SIP) walls shall be designed in accordance with the provisions of this code.~~

3. Change Section R301.2.2.1.1 to read:

~~R301.2.2.1.1 Alternate determination of seismic design category. The Seismic Design Categories and corresponding Short Period Design Spectral Response Accelerations, S_{DS} shown in Figure R301.2(2) are based on soil Site Class D, as defined in Section 1613.5.2 of the International Building Code. If soil conditions are other than Site Class D, the Short Period Design Spectral Response Accelerations, S_{DS} , for a site can be determined according to Section 1613.5 of the International Building Code. The value of S_{DS} determined according to Section 1613.5 of the International Building Code is permitted to be used to set the seismic design category according to Table R301.2.2.1.1, and to interpolate between values in Tables R602.10.3(3), R603.7 and other seismic design requirements of this code.~~

4. ~~Delete Section R301.2.2.3 and all subsections.~~

5. ~~Delete Section R301.2.2.4.~~

6. Change the exception to Item 1 of Section R301.3 to read:

~~Exception: For wood framed wall buildings with bracing in accordance with Section R602.10, the wall stud clear height used to determine the maximum permitted story height may be increased to 12 feet (3658 mm) without requiring an engineered design for the building wind and seismic force resisting systems.~~

7. Add Exception 6 to Section R302.1 to read:

6. Decks and open porches.

8. Change the last column and add footnote "a" to Table R302.1 as shown:

Minimum Fire Separation Distance
<5 feet ^a
≥5 feet ^a
≥2 feet to 5 feet ^a

-	5 feet ^a
-	<3 feet
-	3 feet
-	5 feet ^a
-	<5 feet ^a
-	5 feet ^a

~~^aThe minimum fire separation distance shall be reduced to three feet in developments which are fully sprinklered as provided for in Sections R313.1 or R313.2.~~

9. 3. Change the exception in Section R302.2 to require a common two-hour fire-resistance-rated wall instead of a one-hour fire-resistance-rated wall, unless the townhouse development is fully sprinklered as provided for in Section R313.1, in which case a common one-hour fire-resistive-rated wall shall be permitted between townhouses.

10. 4. Add the following sentence to the end of Section R302.3 to read:

Dwelling unit separation wall assemblies that are constructed on a lot line shall be constructed as required in Section R302.2 for townhouses.

11. 5. Add an exception to Section ~~R303.8~~ R303.9 to read:

Exception: Seasonal structures not used as a primary residence for more than 90 days per year, unless rented, leased or let on terms expressed or implied to furnish heat, shall not be required to comply with this section.

12. 6. Add Section ~~R303.8.1~~ R303.9.1 to read:

~~R303.8.1~~ R303.9.1 Nonowner occupied required heating. Every dwelling unit or portion thereof which is to be rented, leased or let on terms either expressed or implied to furnish heat to the occupants thereof shall be provided with facilities in accordance with Section ~~R303.8~~ R303.9 during the period from October 15 to May 1.

13. 7. Add Section ~~R303.9~~ R303.10 to read:

~~R303.9~~ R303.10 Insect screens. Every door, window and other outside opening required for ventilation purposes shall be supplied with approved tightly fitted screens of not less than 16 mesh per inch (16 mesh per 25 mm) and every screen door used for insect control shall have a self-closing device.

14. 8. Add Section R306.5 to read:

R306.5 Water supply sources and sewage disposal systems. The water and drainage system of any building or premises where plumbing fixtures are installed shall be connected to a public or private water supply and a public or private sewer

system. As provided for in Section 103.11 of Part I of the Virginia Uniform Statewide Building Code (13 VAC 5-63), for functional design, water supply sources and sewage disposal systems are regulated and approved by the Virginia Department of Health and the Virginia Department of Environmental Quality.

Note: See also the Memorandums of Agreement in the "Related Laws Package," which is available from the Virginia Department of Housing and Community Development.

~~15-~~ 9. Change Section R310.1 to read:

R310.1 Emergency escape and rescue required. Basements, habitable attics and each ~~every~~ sleeping room designated on the construction documents shall have at least one ~~openable~~ operable emergency escape and rescue opening. ~~Such opening shall be directly to the exterior of the building or to a deck, screen porch or egress court, all of which shall provide access to a public street, public alley or yard.~~ Where basements contain one or more sleeping rooms, emergency egress and rescue openings shall be required in each sleeping room. Where emergency escape and rescue openings are provided, they shall have a sill height of not more than 44 inches (1118 mm) above measured from the finished floor to the bottom of the clear opening. Where a door opening having a threshold below the adjacent ground elevation serves as an emergency escape and rescue opening and is provided with a bulkhead enclosure, the bulkhead enclosure shall comply with Section R310.3. The net clear opening dimensions required by this section shall be obtained by the normal operation of the emergency escape and rescue opening from the inside, except that tilt-out or removable sash designed windows shall be permitted to be used. Emergency escape and rescue openings with a finished height below the adjacent ground elevation shall be provided with a window well in accordance with Section R310.2. Emergency escape and rescue openings shall open directly into a public way, or to a yard or court that opens to a public way.

Exceptions:

1. Dwelling units equipped throughout with an approved automatic sprinkler system installed in accordance with NFPA 13, 13R, 13D or Section P2904.
2. Basements used only to house mechanical equipment and not exceeding total floor area of 200 square feet (18.58 m²).

~~16-~~ 10. Change Section R310.1.1 to read:

R310.1.1 Minimum opening area. All emergency escape and rescue openings shall have a minimum net clear opening of 5.7 square feet (0.530 m²), including the tilting or removal of the sash as the normal operation to comply with sections R310.1.2 and R310.1.3.

Exception: Grade floor openings shall have a minimum net clear opening of 5 square feet (0.465 m²).

47. 11. Change Section R311.7.4.1 R311.7.5.1 to read:

~~R311.7.4.1 Riser height~~ R311.7.5.1 Risers. The maximum riser height shall be 8-1/4 inches (210 mm). The riser shall be measured vertically between the leading edges of the adjacent treads. The greatest riser height within any flight of stairs shall not exceed the smallest by more than 3/8 inch (9.5 mm). Risers shall be vertical or sloped from the underside of the nosing of the tread above at an angle not more than 30 degrees (0.51 rad) from the vertical. Open risers are permitted provided that the opening between treads does not permit the passage of a 4-inch-diameter (102 mm) sphere.

Exception: The opening between adjacent treads is not limited on stairs with a total rise of 30 inches (762 mm) or less.

48. 12. Change Section R311.7.4.2 R311.7.5.2 to read:

~~R311.7.4.2 Tread depth~~ R311.7.5.2 Treads. The minimum tread depth shall be 9 inches (229 mm). The tread depth shall be measured horizontally between the vertical planes of the foremost projection of adjacent treads and at a right angle to the tread's leading edge. The greatest tread depth within any flight of stairs shall not exceed the smallest by more than 3/8 inch (9.5 mm). ~~Consistently shaped winders at the walkline shall be allowed within the same flight of stairs as rectangular treads and do not have to be within 3/8 inch (9.5 mm) of the rectangular tread depth. Winder treads shall have a minimum tread depth of 10 inches (254 mm) measured between the vertical planes of the foremost projection of adjacent treads at the intersection with the walkline. Winder treads shall have a minimum tread depth of 6 inches (152 mm) at any point within the clear width of the stair. Within any flight of stairs, the largest winder tread depth at the walkline shall not exceed the smallest winder tread by more than 3/8 inch (9.5 mm).~~

49. 13. Change Section R311.7.6 R311.7.7 to read:

~~R311.7.6~~ R311.7.7 Stairway walking surface. The walking surface of treads and landings of stairways shall be level or sloped no steeper than one unit vertical in 48 inches horizontal (two-percent slope).

14. Change Section R312.2.1 to read:

R312.2.1 Window sills. In dwelling units, where the opening of an operable window is located more than 72 inches (1829 mm) above the finished grade or surface below, the lowest part of the clear opening of the window shall be a minimum of 18 inches (457 mm) above the finished floor of the room in which the window is located. Operable sections of windows shall not permit openings that allow passage of a 4-inch-diameter (102 mm) sphere where such openings are located within 18 inches (457 mm) of the finished floor.

Exceptions:

1. Windows whose openings will not allow a 4-inch-diameter (102 mm) sphere to pass through the opening when the opening is in its largest opened position.
2. Openings that are provided with window fall prevention devices that comply with ASTM F 2090.
3. Windows that are provided with window opening control devices that comply with Section R312.2.2.

~~20.~~ 15. Replace Section R313 with the following:

Section R313.

Automatic Fire Sprinkler Systems.

R313.1 Townhouse automatic fire sprinkler systems. Notwithstanding the requirements of Section 103.8, where installed, an automatic residential fire sprinkler system for townhouses shall be designed and installed in accordance with NFPA 13D or Section P2904.

Exception: An automatic residential fire sprinkler system shall not be required when additions or alterations are made to existing townhouses that do not have an automatic residential fire sprinkler system installed.

R313.2 One- and two-family dwellings automatic fire sprinkler systems. Notwithstanding the requirements of Section 103.8, where installed, an automatic residential fire sprinkler system shall be designed and installed in accordance with NFPA 13D or Section P2904.

Exception: An automatic residential fire sprinkler system shall not be required for additions or alterations to existing buildings that are not already provided with an automatic residential fire sprinkler system.

~~21.~~ 16. Change Section R314.2 to read:

R314.2 Smoke detection systems. Household fire alarm systems installed in accordance with NFPA 72 that include smoke alarms, or a combination of smoke detector and audible notification device installed as required by this section for smoke alarms, shall be permitted. The household fire alarm system shall provide the same level of smoke detection and alarm as required by this section for smoke alarms. Where a household fire warning system is installed using a combination of smoke detector and audible notification device(s), the system shall become a permanent fixture of the dwelling unit.

Exception: Where smoke alarms are provided meeting the requirements of Section R314.4.

~~22.~~ 17. Delete Section R314.3.1.

~~23.~~ 18. Delete Section ~~R315.2~~ R315.3.

~~24.~~ 19. Change Section ~~R315.2~~ R315.4 to read:

~~R315.3~~ R315.4 Alarm requirements. Single station carbon monoxide alarms shall be hard wired, plug-in or battery type; listed as complying with UL 2034; and installed in accordance with this code and the manufacturer's installation instructions.

~~25.~~ 20. Add Section R324 Radon-Resistant Construction.

~~26.~~ 21. Add Section R324.1 to read:

R324.1 Local enforcement of radon requirements. Following official action under Article 7 (§ 15.2-2280 et seq.) of Chapter 22 of Title 15.2 of the Code of Virginia by a locality in areas of high radon potential, as indicated by Zone 1 on the U.S. EPA Map of Radon Zones (IRC Figure AF101), such locality shall enforce the provisions contained in Appendix F.

Exception: Buildings or portions thereof with crawl space foundations which are ventilated to the exterior, shall not be required to provide radon-resistant construction.

~~27.~~ 22. Add Section R325 Swimming Pools, Spas and Hot Tubs.

~~28.~~ 23. Add Section R325.1 to read:

R325.1 Use of Appendix G for swimming pools, spas and hot tubs. In addition to other applicable provisions of this code, swimming pools, spas and hot tubs shall comply with the provisions in Appendix G.

~~29.~~ 24. Add Section R326 Patio Covers.

~~30.~~ 25. Add Section R326.1 to read:

R326.1 Use of Appendix H for patio covers. Patio covers shall comply with the provisions in Appendix H.

~~31.~~ 26. Add Section R327 Sound Transmission.

~~32.~~ 27. Add Section R327.1 to read:

R327.1 Sound transmission between dwelling units. Construction assemblies separating dwelling units shall provide airborne sound insulation as required in Appendix K.

~~33.~~ 28. Add Section R327.2 to read:

R327.2 Airport noise attenuation. This section applies to the construction of the exterior envelope of detached one- and two-family dwellings and multiple single-family dwellings (townhouses) not more than three stories high with separate means of egress within airport noise zones when enforced by a locality pursuant to § 15.2-2295 of the Code of Virginia. The exterior envelope of such structures shall comply with Section 1207.4 ~~of the state amendments to the IBC of Part 1 of the Virginia Uniform Statewide Building Code (13 VAC 5-63).~~

~~34.~~ Add Section R328 ~~Gray Water and Rain Water Recycling Systems.~~

~~35.~~ Add Section R328.1 to read:

~~R328.1 Use of Appendix O for gray water and rain water recycling systems. In addition to other applicable provisions of this code, gray water recycling systems and rain water recycling systems shall comply with the provisions in Appendix O. In the use of Appendix O for rain water recycling systems, the term "rain water" shall be substituted for the term "gray water." Gray water recycling systems and rain water recycling systems shall be separate systems and shall not be interconnected.~~

~~36.~~ 29. Add Section R329 Fire Extinguishers.

~~37.~~ 30. Add Section R329.1 to read:

R329.1 Kitchen areas. Other than where the dwelling is equipped with an approved sprinkler system in accordance with Section R313, a fire extinguisher having a rating of 2-A:10-B:C or an approved equivalent type of fire extinguisher shall be installed in the kitchen area.

~~38.~~ 31. Change Section R401.3 to read:

R401.3 Drainage. Surface drainage shall be diverted to a storm sewer conveyance or other approved point of collection that does not create a hazard to the dwelling unit. Lots shall be graded to drain surface water away from foundation walls. The grade shall fall a minimum of six inches (152 mm) within the first 10 feet (3048 mm).

Exception: Where lot lines, walls, slopes or other physical barriers prohibit six inches (152 mm) of fall within 10 feet (3048 mm), drains or swales shall be constructed to ensure drainage away from the structure. Impervious surfaces within 10 feet (3048 mm) of the building foundation shall be sloped a minimum of 2.0% away from the building.

39. 32. Change Section R403.1 to read:

R403.1 General. All exterior walls shall be supported on continuous solid or fully grouted masonry or concrete footings, wood foundations, or other approved structural systems which shall be of sufficient design to accommodate all loads according to Section R301 and to transmit the resulting loads to the soil within the limitations as determined from the character of the soil. Footings shall be supported on undisturbed natural soils or engineered fill.

Exception: One-story detached accessory structures used as tool and storage sheds, playhouses and similar uses, not exceeding 256 square feet (23.7824 m²) of building area, provided all of the following conditions are met:

1. The building eave height is 10 feet or less.
2. The maximum height from the finished floor level to grade does not exceed 18 inches.
3. The supporting structural elements in direct contact with the ground shall be placed level on firm soil and when such elements are wood they shall be approved pressure preservative treated suitable for ground contact use.
4. The structure is anchored to withstand wind loads as required by this code.
5. The structure shall be of light-frame construction whose vertical and horizontal structural elements are primarily formed by a system of repetitive wood or light gauge steel framing members, with walls and roof of light weight material, not slate, tile, brick or masonry.

40. ~~Change Exceptions 2 and 3 in Section R403.1.6 to read:~~

~~2. Walls 24 inches (610 mm) total length or shorter connecting offset braced wall panels shall be anchored to the foundation with a minimum of one anchor bolt located in the center third of the plate section.~~

~~3. Connection of walls 12 inches (305 mm) total length or shorter connecting offset braced wall panels to the foundation without anchor bolts shall be permitted.~~

41. ~~Delete Item 5 of Section R403.1.6.1.~~

42. 33. Add Section R408.3.1 to read:

R408.3.1 Termite inspection. Where an unvented crawl space is installed and meets the criteria in Section R408, the vertical face of the sill plate shall be clear and unobstructed and an inspection gap shall be provided below the sill plate along the top of any interior foundation wall covering. The gap shall be a minimum of one inch (25.4 mm) and a maximum of two inches (50.8 mm) in width and shall

extend throughout all parts of any foundation that is enclosed. Joints between the sill plate and the top of any interior wall covering may be sealed.

Exceptions:

1. In areas not subject to damage by termites as indicated by Table R301.2(1).
2. Where other approved means are provided to inspect for potential damage.

Where pier and curtain foundations are installed as depicted in Figure R404.1.5(1), the inside face of the rim joist and sill plate shall be clear and unobstructed except for construction joints which may be sealed.

Exception: Fiberglass or similar insulation may be installed if easily removable.

~~43. Change Section R502.2.1 to read:~~

~~R502.2.1 Framing at braced wall panels. A load path for lateral forces shall be provided between floor framing and braced wall panels located above or below a floor, as specified in Sections R602.3.5 and R602.10.8.~~

~~44. 34. Change Section R506.2.1 to read:~~

R506.2.1 Fill. Fill material shall be free of vegetation and foreign material and shall be natural nonorganic material that is not susceptible to swelling when exposed to moisture. The fill shall be compacted to assure uniform support of the slab, and except where approved, the fill depth shall not exceed 24 inches (610 mm) for clean sand or gravel and 8 inches (203 mm) for earth.

Exception: Material other than natural material may be used as fill material when accompanied by a certification from an RDP and approved by the building official.

~~45. 35. Change Section R506.2.2 to read:~~

R506.2.2 Base. A 4-inch-thick (102 mm) base course consisting of clean graded sand, gravel or crushed stone passing a 2-inch (51 mm) sieve shall be placed on the prepared subgrade when the slab is below grade.

Exception: A base course is not required when the concrete slab is installed on well drained or sand-gravel mixture soils classified as Group I according to the United Soil Classification System in accordance with Table R405.1. Material other than natural material may be used as base course material when accompanied by a certification from an RDP and approved by the building official.

~~46. Modify Table R602.3(1) to change and add items as shown:~~

7	Built-up studs, face nail	10d (3"x0.128")	24" o.c.
7a	Abutting studs at intersecting wall	16d (3 1/2"x0.135")	12" o.c.

	corners, face nail		
26a	Rim joist or blocking to sill plate, toe nail	8d (2½"x0.113")	6" o.c.

47. Add Section R602.3.5 to read:

~~R602.3.5 Braced wall panel uplift load path. Braced wall panels located at exterior walls that support roof rafters or trusses (including stories below top story) shall have the framing members connected in accordance with one of the following:~~

~~1. Fastening in accordance with Table R602.3(1) where:~~

~~1.1. The basic wind speed does not exceed 90 mph (40 m/s), the wind exposure category is B, the roof pitch is 5:12 or greater, and the roof span is 32 feet (9754 mm) or less, or~~

~~1.2. The net uplift value at the top of a wall does not exceed 100 plf (146 N/mm). The net uplift value shall be determined in accordance with Section R802.11 and shall be permitted to be reduced by 60 plf (57 N/mm) for each full wall above.~~

~~2. Where the net uplift value at the top of a wall exceeds 100 plf (146 N/mm), installing approved uplift framing connectors to provide a continuous load path from the top of the wall to the foundation or to a point where the uplift force is 100 plf (146 N/mm) or less. The net uplift value shall be as determined in Item 1.2 above.~~

~~3. Wall sheathing and fasteners designed in accordance with accepted engineering practice to resist combined uplift and shear forces.~~

48. Change Section R602.9 to read:

~~R602.9 Cripple walls. Foundation cripple walls shall be framed of studs not smaller than the studding above. When exceeding four feet (1219 mm) in height, such walls shall be framed of studs having the size required for an additional story.~~

~~Cripple walls with a stud height less than 14 inches (356 mm) shall be continuously sheathed on one side with wood structural panels fastened to both the top and bottom plates in accordance with Table R602.3(1), or the cripple walls shall be constructed of solid blocking. Cripple walls shall be supported on continuous foundations.~~

(Items 49-52 (the main braced wall panel provisions) are deleted but not shown)

53. Change Section R612.2 to read:

~~R612.2 Window sills. In dwelling units, where the opening of an operable window is located more than 72 inches (1829 mm) above the finished grade or surface~~

~~below, the lowest part of the clear opening of the window shall be a minimum of 18 inches (457 mm) above the finished floor of the room in which the window is located. Operable sections of windows shall not permit openings that allow passage of a 4-inch diameter (102 mm) sphere where such openings are located within 18 inches (457 mm) of the finished floor.~~

~~Exceptions:~~

- ~~1. Windows whose openings will not allow a 4-inch diameter (102 mm) sphere to pass through the opening when the opening is in its largest opened position.~~
- ~~2. Openings that are provided with window fall prevention devices that comply with Section R612.3.~~
- ~~3. Openings that are provided with fall protection devices that comply with ASTM F 2090.~~
- ~~4. Windows that are provided with opening limiting devices that comply with Section R612.4.~~

~~54. Change Section R703.7 to read:~~

~~R703.7 Stone and masonry veneer, general. Stone and masonry veneer shall be installed in accordance with this chapter, Table R703.4 and Figure R703.7. These veneers installed over a backing of wood or cold-formed steel shall be limited to the first story above grade and shall not exceed five inches (127 mm) in thickness. See Tables R602.10.3(3) and R602.10.3(4) for wall bracing requirements for masonry veneer for wood framed construction and Section R603.9.5 for wall bracing requirements for masonry veneer for cold-formed steel construction.~~

~~Exceptions:~~

- ~~1. For all buildings in Seismic Design Categories A, B and C, exterior stone or masonry veneer, as specified in Table R703.7(1), with a backing of wood or steel framing shall be permitted to the height specified in Table R703.7(1) above a noncombustible foundation.~~
- ~~2. For detached one family or two family dwellings in Seismic Design Categories D₀, D₁ and D₂, exterior stone or masonry veneer, as specified in Table R703.7(2), with a backing of wood framing shall be permitted to the height specified in Table R703.7(2) above a noncombustible foundation.~~

~~55. Delete the reference to footnote "P" and the footnote itself in Figure R802.11.~~

~~56. Delete Section N1101.9.~~

~~57. 36. Change Section N1103.2.2 to read:~~

N1103.2.2 (R403.2.2) Sealing (Mandatory). ~~All ducts~~ Ducts, air handlers, and filter boxes and building cavities used as ducts shall be sealed. Joints and seams shall comply with Section M1601.4.1 of the ~~International Residential Code~~ this code. Verification of compliance with this section shall be in accordance with either Section N1103.2.2.1 or Section N1103.2.2.2.

Exceptions:

1. Air-impermeable spray foam products shall be permitted to be applied without additional joint seals.
2. Where a duct connection is made that is partially inaccessible, three screws or rivets shall be equally spaced on the exposed portion of the joint so as to prevent a hinge effect.
3. Continuously welded and locking-type longitudinal joints and seams in ducts operating at static pressures less than 2 inches of water column (500 Pa) pressure classification shall not require additional closure systems.

58: 37. Add Change Section N1103.2.2.1 to read:

N1103.2.2.1 Testing option. Duct tightness shall be verified by either of the following:

1. Post-construction test: ~~Leakage to outdoors~~ Total leakage shall be less than or equal to ~~eight 4 cfm (3.78 L/s 113.3 L/min)~~ 4 cfm (2.83 L/s 113.3 L/min) per 100 ~~ft² square feet (9.29 m²)~~ ft² square feet (9.29 m²) of conditioned floor area or a total leakage less than or equal to ~~12 cfm (5.66 L/s) per 100 ft² (9.29 m²)~~ 12 cfm (5.66 L/s) per 100 ft² (9.29 m²) of conditioned floor area when tested at a pressure differential of 0.1 inch w.g. (25 Pa) across the entire system, including the manufacturer's air handler ~~and closure~~ enclosure. All register boots shall be taped or otherwise sealed during the test.
2. Rough-in test: Total leakage shall be less than or equal to ~~six 4 cfm (2.83 L/s 113.3 L/min)~~ 4 cfm (2.83 L/s 113.3 L/min) per 100 ~~ft² square feet (9.29 m²)~~ ft² square feet (9.29 m²) of conditioned floor area when tested at a pressure differential of 0.1 inch w.g. (25 Pa) across the ~~roughed-in~~ rough-in system, including the manufacturer's air handler enclosure. All register boots shall be taped or otherwise sealed during the test. If the air handler is not installed at the time of the test, total leakage shall be less than or equal to ~~4 3 cfm (1.89 L/s 85 L/min)~~ 3 cfm (1.25 L/s 85 L/min) per 100 ~~ft² square feet (9.29 m²)~~ ft² square feet (9.29 m²) of conditioned floor area.

Exception: Duct tightness ~~The total leakage test is not required if the for ducts and air handler and all ducts are~~ The total leakage test is not required if the for ducts and air handlers located entirely within conditioned space the building thermal envelope.

When this option is chosen, testing shall be performed by approved qualified individuals, testing agencies or contractors. Testing and results shall be as prescribed in Section N1103.2.2 and approved recognized industry standards.

~~59-~~ 38. Add Section N1103.2.2.2 to read:

N1103.2.2.2 Visual inspection option. In addition to the inspection of ducts otherwise required by this code, when the air handler and all ducts are not within conditioned space and this option is chosen to verify duct tightness, duct tightness shall be considered acceptable when the requirements of Section N1103.2.2 are field verified.

39. Add Section N1103.2.2.3 to read:

N1103.2.2.3 (R403.2.2.1) Sealed air handler. Air handlers shall have a manufacturer's designation for an air leakage of no more than 2 percent of the design air flow rate when tested in accordance with ASHRAE 193.

~~60-~~ Change Section M1502.4.4.1 to read:

~~M1502.4.4.1 Specified length. The maximum length of the exhaust duct shall be 35 feet (10 668 mm) from the connection to the transition duct from the dryer to the outlet terminal. Where fittings are used the maximum length of the exhaust duct shall be reduced in accordance with Table M1502.4.4.1.~~

~~61-~~ 40. Add Section M1801.1.1 to read:

M1801.1.1 Equipment changes. Upon the replacement or new installation of any fuel-burning appliances or equipment in existing buildings, an inspection or inspections shall be conducted to ensure that the connected vent or chimney systems comply with the following:

1. Vent or chimney systems are sized in accordance with this code.
2. Vent or chimney systems are clean, free of any obstruction or blockages, defects or deterioration and are in operable condition.

Where not inspected by the local building department, persons performing such changes or installations shall certify to the building official that the requirements of Items 1 and 2 of this section are met.

~~62-~~ 41. Add Section G2425.1.1 to read:

G2425.1.1 Equipment changes. Upon the replacement or new installation of any fuel-burning appliances or equipment in existing buildings, an inspection or inspections shall be conducted to ensure that the connected vent or chimney systems comply with the following:

1. Vent or chimney systems are sized in accordance with this code.

2. Vent or chimney systems are clean, free of any obstruction or blockages, defects, or deterioration and are in operable condition.

Where not inspected by the local building department, persons performing such changes or installations shall certify to the building official that the requirements of Items 1 and 2 of this section are met.

63. 42. Change Section P2601.2 to read:

P2601.2 Connections. Plumbing fixtures, drains and appliances used to receive or discharge liquid wastes or sewage shall be directly connected to the sanitary drainage system of the building or premises, in accordance with the requirements of this code. This section shall not be construed to prevent indirect waste systems.

Exception: Bathtubs, showers, lavatories, clothes washers and laundry trays are shall not be required to discharge to the sanitary drainage system where these such fixtures discharge to an approved gray water or rain water recycling system for flushing of water closets and urinals or for subsurface landscape irrigation.

64. 43. Change Section P2602.1 to read:

P2602.1 General. The water and drainage system of any building or premises where plumbing fixtures are installed shall be connected to a public or private water supply and a public or private sewer system. As provided for in Section 103.11 of Part I of the Virginia Uniform Statewide Building Code (13VAC5-63) for functional design, water supply sources and sewage disposal systems are regulated and approved by the Virginia Department of Health and the Virginia Department of Environmental Quality.

Note: See also the Memorandums of Agreement in the "Related Laws Package," which is available from the Virginia Department of Housing and Community Development.

65. 44. Change Section P2903.5 to read:

P2903.5 Water hammer. The flow velocity of the water distribution system shall be controlled to reduce the possibility of water hammer. A water-hammer arrestor shall be installed where quick-closing valves are utilized, unless otherwise approved. Water hammer arrestors shall be installed in accordance with manufacturer's specifications. Water hammer arrestors shall conform to ASSE 1010.

66. 45. Add Section P3002.2.1 to read:

P3002.2.1 Tracer wire. Nonmetallic sanitary sewer piping that discharges to public systems shall be locatable. An insulated copper tracer wire, 18 AWG minimum in size and suitable for direct burial or an equivalent product, shall be utilized. The wire shall be installed in the same trench as the sewer within 12 inches (305 mm)

of the pipe and shall be installed from within five feet of the building wall to the point where the building sewer intersects with the public system. At a minimum, one end of the wire shall terminate above grade in an accessible location that is resistant to physical damage, such as with a cleanout or at the building wall.

46. Change the title of Section P3009 to "Gray Water and Rain Water Recycling Systems."

47. Change Section P3009.1 to read:

P3009.1 Scope. The provisions of Section P3009 shall govern the materials, design, construction and installation of gray water and rain water systems for flushing of water closets and urinals and for subsurface landscape irrigation. See Figures P3009.1(1) and P3009.1(2). In the use of Section P3009 for rain water systems, the term "rain water" shall be substituted for the term "gray water." Gray water systems and rain water systems shall be separate systems and shall not be interconnected.

~~67.~~ 48. Add Section E3601.8 to read:

E3601.8 Energizing service equipment. The building official shall give permission to energize the electrical service equipment of a one- or two-family dwelling unit when all of the following requirements have been approved:

1. The service wiring and equipment, including the meter socket enclosure, shall be installed and the service wiring terminated.
2. The grounding electrode system shall be installed and terminated.
3. At least one receptacle outlet on a ground fault protected circuit shall be installed and the circuit wiring terminated.
4. Service equipment covers shall be installed.
5. The building roof covering shall be installed.
6. Temporary electrical service equipment shall be suitable for wet locations unless the interior is dry and protected from the weather.

~~68.~~ 49. Change Section E3802.4 to read:

E3802.4 In unfinished basements. Where type SE or NM cable is run at angles with joists in unfinished basements, cable assemblies containing two or more conductors of sizes 6 AWG and larger and assemblies containing three or more conductors of sizes 8 AWG and larger shall not require additional protection where attached directly to the bottom of the joists. Smaller cables shall be run either through bored holes in joists or on running boards. Type NM or SE cable installed on the wall of an unfinished basement shall be permitted to be installed in

a listed conduit or tubing or shall be protected in accordance with Table E3802.1. Conduit or tubing shall be provided with a suitable insulating bushing or adapter at the point the where cable enters the raceway. The sheath of the Type NM or SE cable sheath shall extend through the conduit or tubing and into the outlet or device box not less than 1/4 inch (6.4 mm). The cable shall be secured within 12 inches (305 mm) of the point where the cable enters the conduit or tubing. Metal conduit, tubing, and metal outlet boxes shall be connected to an equipment grounding conductor complying with Section E3908.13.

69. 50. Change Section ~~E3902.11~~ E3902.12 to read:

~~E3902.11~~ E3902.12 Arc-fault protection of bedroom outlets. All branch circuits that supply 120-volt, single phase, 15-ampere and 20-ampere outlets installed in bedrooms shall be protected by a combination type arc-fault circuit interrupter installed to provide protection of the branch circuit.

Exceptions:

1. Where ~~a combination~~ an outlet branch-circuit type AFCI is installed at the first outlet to provide protection for the remaining portion of the branch circuit, the portion of the branch circuit between the branch-circuit overcurrent device and ~~such the first~~ the first outlet shall be ~~wired~~ installed with metal outlet and junction boxes and RMC, IMC, EMT, Type MC or steel armored eable, Type AC cables meeting the requirements of Section E3908.8.

2. Where an outlet branch-circuit type AFCI is installed at the first outlet to provide protection for the remaining portion of the branch circuit, the portion of the branch circuit between the branch-circuit overcurrent device and the first outlet shall be installed with metal or nonmetallic conduit or tubing that is encased in not less than 2 inches (51 mm) of concrete.

3. AFCI protection is not required for a an individual branch circuit supplying only a fire alarm system where the branch circuit is wired with metal outlet and junction boxes and RMC, IMC, EMT or steel-sheathed armored cable Type AC, or Type MC meeting the requirements of Section E3908.8.

51. Add the following referenced standard to Chapter 44:

<u>Standard reference number</u>	<u>Title</u>	<u>Referenced in code section number</u>
<u>NFPA 13R-10</u>	<u>Installation of Sprinkler Systems in Residential Occupancies Up to and Including Four Stories in Height</u>	<u>R310.1</u>

13VAC5-63-220. Chapter 4 Special detailed requirements based on use and occupancy.

A. Delete Section 403.4.4 of the IBC.

B. ~~Add~~ Change Section 407.10 407.4.1.1 to the IBC to read:

~~407.10~~ 407.4.1.1 Special locking arrangement. Means of egress doors shall be permitted to contain locking devices restricting the means of egress in areas in which the clinical needs of the patients require restraint of movement, where all of the following conditions are met:

1. The locks release upon activation of the fire alarm system or the loss of power.
2. The building is equipped with an approved automatic sprinkler system in accordance with Section 903.3.1.1.
3. A manual release device is provided at a nursing station responsible for the area.
4. A key-operated switch or other manual device is provided adjacent to each door equipped with the locking device. Such switch or other device, when operated, shall result in direct interruption of power to the lock -- independent of the control system electronics.
5. All staff shall have keys or other means to unlock the switch or other device or each door provided with the locking device.

C. Add Section 407.11 to the IBC to read:

407.11 Emergency power systems. Emergency power shall be provided for medical life support equipment, operating, recovery, intensive care, emergency rooms, fire detection and alarm systems in any Group I-2 occupancy licensed by the Virginia Department of Health as a hospital, nursing home or hospice facility.

D. ~~Change the title of IBC Section 410 to read:~~

~~Stages, Platforms and Technical Production Areas.~~

E. ~~Delete the following definitions in IBC Section 410.2:~~

~~Fly gallery.~~

~~Gridiron.~~

F. ~~Add the following definition to IBC Section 410.2 to read:~~

~~Technical production area. Open elevated areas or spaces intended for entertainment technicians to walk on and occupy for servicing and operating entertainment technology systems and equipment. Galleries, including fly and lighting galleries, gridirons, catwalks and similar areas are designed for these purposes.~~

G. ~~Delete Section 410.5.3 of the IBC, add new Section 410.6 to the IBC and renumber Sections 410.6 and 410.7 of the IBC to Sections 410.7 and 410.8 respectively.~~

~~410.6 Means of egress. Except as modified or as provided for in this section, the provisions of Chapter 10 shall apply.~~

~~410.6.1 Arrangement. Where two or more exits or exit access doorways are required per Section 1015.1 from the stage, at least one exit or exit access doorway shall be provided on each side of the stage.~~

~~410.6.2 Stairway and ramp enclosure. Stairways and ramps provided from stages, platforms and technical production areas are not required to be enclosed.~~

~~410.6.3 Technical production areas. Technical production areas shall be provided with means of egress and means of escape in accordance with Section 410.6.3.1 through 410.6.3.5.~~

~~410.6.3.1 Means of egress. At least one means of egress shall be provided from technical production areas.~~

~~410.6.3.2 Travel distance. The maximum length of exit access travel shall not exceed 300 feet (91 440 mm) for buildings without a sprinkler system and 400 feet (121 920 mm) for buildings equipped throughout with an automatic sprinkler system in accordance with Section 903.3.1.1.~~

~~410.6.3.3 Two means of egress. Where two means of egress are required, the common path of travel shall not exceed 100 feet (30 480 mm).~~

~~Exception: A means of egress to a roof in place of a second means of egress is permitted.~~

~~410.6.3.4 Path of egress travel. The following exit access components are permitted when serving technical production areas:~~

- ~~1. Stairways.~~
- ~~2. Ramps.~~
- ~~3. Spiral stairways.~~
- ~~4. Catwalks.~~
- ~~5. Alternating tread devices.~~
- ~~6. Permanent ladders.~~

~~410.6.3.5 Width. The path of egress travel within and from technical production areas shall be a minimum of 22 inches (559 mm).~~

H. Add Section 415.1.1 to the IBC to read:

415.1.1 Flammable and combustible liquids. ~~Notwithstanding the provisions of this chapter,~~ Construction associated with the storage, handling, processing, and transporting of flammable and combustible liquids shall be in accordance with the mechanical code and the fire code listed in Chapter 35 of this code. ~~Regulations and regulations~~ governing the installation, repair, upgrade, and closure of underground and aboveground storage tanks under the Virginia State Water Control Board regulations 9VAC25-91 and 9VAC25-580, which are hereby adopted and incorporated by reference to be an enforceable part of this code. Where differences occur between the provisions of this code and the ~~incorporated~~ provisions of the such State Water Control Board regulations, the provisions of the State Water Control Board regulations shall apply.

I. ~~E.~~ Add IBC Section 424 425 Manufactured Homes and Industrialized Buildings.

J. ~~F.~~ Add Section 424.1 425.1 to the IBC to read:

424.1 425.1 General. The provisions of this section shall apply to the installation or erection of manufactured homes subject to the Virginia Manufactured Home Safety Regulations (13VAC5-95) and industrialized buildings subject to the Virginia Industrialized Building Safety Regulations (13VAC5-91).

Note: Local building departments are also responsible for the enforcement of certain provisions of the Virginia Manufactured Home Safety Regulations (13VAC5-95) and the Virginia Industrialized Building Safety Regulations (13VAC5-91) as set out in those regulations.

K. ~~G.~~ Add Section 424.2 425.2 to the IBC to read:

424.2 425.2 Site work for manufactured homes. The aspects for the installation and set up of a new manufactured home covered by this code rather than the Virginia Manufactured Home Safety Regulations (13VAC5-95) include, but are not limited to, footings, foundations systems, anchoring of the home, exterior, interior close-up, and additions and alterations done during initial installation. Such aspects shall be subject to and shall comply with the manufacturer's installation instructions provided by the manufacturer of the home. To the extent that the manufacturer's installation instructions do not address any aspect enumerated above or when the manufacturer's installation instructions are not available, such aspects shall be subject to and comply with 24 CFR Part 3285 – Model Manufactured Home Installation Standards. To the extent that the manufacturer's installation instructions and 24 CFR Part 3285 do not address any aspect enumerated above, the installer must first attempt to obtain Design Approval Primary Inspection Agency (DAPIA) as defined in 24 CFR Part 3285.5, approved designs and instructions prepared by the manufacturer; or if designs and instructions are not available from the manufacturer, obtain an alternate design prepared and certified by an RDP that is consistent with the manufactured home design, conforms to the requirements of the Manufactured Housing Consensus Committee (MHCSS) as defined in 24 CFR Part 3285.5, and has been approved by the manufacturer and the DAPIA. Stoops, decks, porches and used manufactured homes shall comply with the provisions of this code, which shall include the option of using the IRC for the technical requirements for the installation and set up of the home and the use of Appendix E of the IRC for additions,

alterations and repairs to the home. Additionally, all applicable provisions of Chapter 1 of this code, including but not limited to requirements for permits, inspections, certificates of occupancy and requiring compliance, are applicable to the installation and set up of a manufactured home. Where the installation or erection of a manufactured home utilizes components that are to be concealed, the installer shall notify the building official that an inspection is necessary and assure that an inspection is performed and approved prior to concealment of such components, unless the building official has agreed to an alternative method of verification.

~~L.~~ H. Add Section ~~424.3~~ 425.3 to the IBC to read:

~~424.3~~ 425.3 Wind load requirements for manufactured homes. Manufactured homes shall be anchored to withstand the wind loads established by the federal regulation for the area in which the manufactured home is installed. For the purpose of this code, Wind Zone II of the federal regulation shall include the cities of Chesapeake, Norfolk, Portsmouth, and Virginia Beach.

~~M.~~ I. Add Section ~~424.4~~ 425.4 to the IBC to read:

~~424.4~~ 425.4 Skirting requirements for manufactured homes. As used in this section, "skirting" means a weather-resistant material used to enclose the space from the bottom of the manufactured home to grade. In accordance with § 36-99.8 of the Code of Virginia, manufactured homes installed or relocated shall have skirting installed within 60 days of occupancy of the home. Skirting materials shall be durable, suitable for exterior exposures and installed in accordance with the manufacturer's installation instructions. Skirting shall be secured as necessary to ensure stability, to minimize vibrations, to minimize susceptibility to wind damage and to compensate for possible frost heave. Each manufactured home shall have a minimum of one opening in the skirting providing access to any water supply or sewer drain connections under the home. Such openings shall be a minimum of 18 inches (457 mm) in any dimension and not less than three square feet (.28 m²) in area. The access panel or door shall not be fastened in a manner requiring the use of a special tool to open or remove the panel or door. On-site fabrication of the skirting by the owner or installer of the home shall be acceptable, provided that the material meets the requirements of this code. In addition, as a requirement of this code, skirting for the installation and set-up of a new manufactured home shall also comply with the requirements of 24 CFR Part 3285 – Model Manufactured Home Installation Standards.

~~N.~~ J. Add Section ~~424.5~~ 425.5 to the IBC to read:

~~424.5~~ 425.5 Site work for industrialized buildings. Site work for the erection and installation of an industrialized building shall comply with the manufacturer's installation instructions. To the extent that any aspect of the erection or installation of an industrialized building is not covered by the manufacturer's installation instructions, this code shall be applicable, including the use of the IRC for any construction work where the industrialized building would be classified as a Group R-5 building. In addition, all administrative requirements of this code for permits, inspections, and certificates of occupancy are also applicable. Further, the building official may require the submission of plans and specifications for details of items needed to comprise the finished building that

are not included or specified in the manufacturer's instructions, including, but not limited to, footings, foundations, supporting structures, proper anchorage, and the completion of the plumbing, mechanical, and electrical systems. Where the installation or erection of an industrialized building utilizes components that are to be concealed, the installer shall notify the building official that an inspection is necessary and assure that an inspection is performed and approved prior to concealment of such components, unless the building official has agreed to an alternative method of verification.

Exception: Temporary family health care structures installed pursuant to § 15.2-2292.1 of the Code of Virginia shall not be required or permitted to be placed on a permanent foundation, but shall otherwise remain subject to all pertinent provisions of this section.

Ø. K. Add Section 424.6 425.6 to the IBC to read:

424.6 425.6 Relocated industrialized buildings; alterations and additions. Industrialized buildings constructed prior to January 1, 1972, shall be subject to Section 117 when relocated. Alterations and additions to any existing industrialized buildings shall be subject to pertinent provisions of this code. Building officials shall be permitted to require the submission of plans and specifications for the model to aid in the evaluation of the proposed alteration or addition. Such plans and specifications shall be permitted to be submitted in electronic or other available format acceptable to the building official.

P. L. Add IBC Section 425 426 Aboveground Liquid Fertilizer Tanks.

Q. M. Add Sections 425.1 426.1 through 425.6 426.6 to the IBC to read:

425.1 426.1 General. This section shall apply to the construction of ALFSTs and shall supersede any conflicting requirements in other provisions of this code. ALFSTs shall also comply with any applicable non-conflicting requirements of this code.

425.1.1 426.1.1 When change of occupancy rules apply. A change of occupancy to use a tank as an ALFST occurs when there is a change in the use of a tank from storing liquids other than liquid fertilizers to a use of storing liquid fertilizer and when the type of liquid fertilizer being stored has a difference of at least 20% of the specific gravity or operating temperature, or both, or a significant change in the material's compatibility.

425.2 426.2 Standards. Newly constructed welded steel ALFSTs shall comply with API 650 and TFI RMIP, as applicable. Newly constructed ALFSTs constructed of materials other than welded steel shall be constructed in accordance with accepted engineering practice to prevent the discharge of liquid fertilizer and shall be constructed of materials that are resistant to corrosion, puncture or cracking. In addition, newly constructed ALFSTs constructed of materials other than welded steel shall comply with TFI RMIP, as applicable. For the purposes of this code, the use of TFI RMIP shall be construed as mandatory and any language in TFI RMIP, such as, but not limited to, the terms "should" or "may" which indicate that a provision is only a recommendation or a guideline shall be taken as a requirement. ALFSTs shall be placarded in accordance with NFPA 704.

Exception: Sections 4.1.4, 4.2.5, 5.1.2, 5.2.8, 5.3 and 8.1(d)(i) of TFI RMIP shall not be construed as mandatory.

~~425.3~~ 426.3 Secondary containment. When ALFSTs are newly constructed and when there is a change of occupancy to use a tank as an ALFST, a secondary containment system designed and constructed to prevent any liquid fertilizer from reaching the surface water, groundwater or adjacent land before cleanup occurs shall be provided. The secondary containment system may include dikes, berms or retaining walls, curbing, diversion ponds, holding tanks, sumps, vaults, double-walled tanks, liners external to the tank, or other approved means and shall be capable of holding up to 110% of the capacity of the ALFST as certified by an RDP.

~~425.4~~ 426.4 Repair, alteration and reconstruction of ALFSTs. Repair, alteration and reconstruction of ALFSTs shall comply with applicable provisions of API 653 and TFI RMIP.

~~425.5~~ 426.5 Inspection. Applicable inspections as required by and in accordance with API 653 and TFI RMIP shall be performed for repairs and alterations to ALFSTs, the reconstruction of ALFSTs and when there is a change of occupancy to use a tank as an ALFST. When required by API 653 or TFI RMIP, such inspections shall occur prior to the use of the ALFST.

~~425.6~~ 426.6 Abandoned ALFSTs. Abandoned ALFSTs shall comply with applicable provisions of Section 3404.2.13.2 of the IFC.

13VAC5-63-230. Chapter 7 ~~Fire-resistant-rated construction~~ Fire and smoke protection features.

A. Change Section ~~703.6~~ 703.7 of the IBC to read:

~~703.6~~ 703.7 Fire-resistance assembly marking. Concealed fire walls, vertical fire separation assemblies, fire barriers, fire partitions and smoke barriers shall be designated above ceilings and on the inside of all ceiling access doors which provide access to such fire rated assemblies by signage having letters no smaller than one inch (25.4 mm) in height. Such signage shall indicate the fire-resistance rating of the assembly and the type of assembly and be provided at horizontal intervals of no more than eight feet (2438 mm).

Note: An example of suggested formatting for the signage would be "ONE HOUR FIRE PARTITION."

B. Change the existing exception in Section 705.2 of the IBC to Exception 1 and add the following Exception 2 to read:

~~705.2 Projections. Except for decks~~ 2. Decks and open porches of buildings in Groups R-3 and R-4, ~~cornices, eave overhangs, exterior balconies and similar projections extending beyond the exterior wall shall conform to the requirements of this section and Section 1406. Exterior egress balconies and exterior exit stairways shall also comply with Sections~~

~~1019 and 1026, respectively. Projections shall not extend beyond the distance determined by the following three methods, whichever results in the lesser projection:~~

~~1. A point one third the distance from the exterior face of the wall to the lot line where protected openings or a combination of protected and unprotected openings are required in the exterior wall.~~

~~2. A point one half the distance from the exterior face of the wall to the lot line where all openings in the exterior wall are permitted to be unprotected or the building is equipped throughout with an automatic sprinkler system installed under the provisions of Section 705.8.2.~~

~~3. More than 12 inches (305 mm) into areas where openings are prohibited.~~

~~Buildings on the same lot and considered as portions of one building in accordance with Section 705.3 are not required to comply with this section.~~

C. Add Exception 4 to Section 706.5.2 of the IBC to read:

4. Decks and open porches of buildings in Groups R-3 and R-4.

D. Delete Sections ~~708.14.1 through 708.14.2.11~~ 713.14.1 and 713.14.1.1.

E. Change Section 716.5.3 of the IBC to read:

~~716.5.3 Penetrations of shaft enclosures. Shaft enclosures that are permitted to be penetrated by ducts and air transfer openings shall be protected with approved fire and smoke dampers installed in accordance with their listing.~~

Exceptions:

~~1. Fire and smoke dampers are not required where steel exhaust subducts extend at least 22 inches (559 mm) vertically in exhaust shafts provided there is a continuous airflow upward to the outside.~~

~~2. Fire dampers are not required where penetrations are tested in accordance with ASTM E 119 as part of the fire resistance rated assembly.~~

~~3. Fire and smoke dampers are not required where ducts are used as part of an approved smoke control system in accordance with Section 909.~~

~~4. Fire and smoke dampers are not required where the penetrations are in parking garage exhaust or supply shafts that are separated from other building shafts by not less than two-hour fire resistance-rated construction.~~

~~5. Smoke dampers are not required where the building is equipped throughout with an automatic sprinkler system in accordance with Section 903.3.1.1.~~

13VAC5-63-240. Chapter 9 Fire protection systems.

A. Add the following definitions to the list of terms in Section 902 902.1 of the IBC ~~to read:~~

~~Emergency communication equipment. Emergency communication equipment, includes but is not limited to, two-way radio communications, signal booster, bi-directional amplifiers, radiating cable systems or internal multiple antenna, or a combination of the foregoing.~~

~~Emergency public safety personnel. Emergency public safety personnel includes firefighters, emergency medical personnel, law enforcement officers and other emergency public safety personnel routinely called upon to provide emergency assistance to members of the public in a wide variety of emergency situations, including, but not limited to, fires, medical emergencies, violent crimes and terrorist attacks.~~

B. ~~Change the following definition in Section 902 of the IBC to read:~~

~~Automatic fire extinguishing system. An approved system of devices and equipment which automatically detects a fire and discharges an approved fire extinguishing agent onto or in the area of a fire and shall include among other systems an automatic sprinkler system, unless otherwise expressly stated.~~

C. ~~Change~~ Section 903.2.1.2 of the IBC to read:

903.2.1.2 Group A-2. An automatic sprinkler system shall be provided for Group A-2 occupancies where one of the following conditions exists:

1. The fire area exceeds 5,000 square feet (464.5m²);
2. The fire area has an occupant load of 100 or more in night clubs or 300 or more in other Group A-2 occupancies; or
3. The fire area is located on a floor other than a level of exit discharge serving such occupancies.

~~D. C.~~ Change Item 2 of Section 903.2.1.3 of the IBC to read:

2. In Group A-3 occupancies other than churches, the fire area has an occupant load of 300 or more; or

~~E. D.~~ Change Section 903.2.3 of the IBC to read:

903.2.3 Group E. An automatic sprinkler system shall be provided for Group E occupancies as follows:

1. Throughout all Group E fire areas greater than 20,000 square feet (1858 m²) in area.

2. Throughout every portion of educational buildings below the lowest level of exit discharge serving that portion of the building.

Exception: An automatic sprinkler system is not required in any area below the lowest level of exit discharge serving that area where every classroom throughout the building has at least one exterior exit door at ground level.

F. E. Change Section 903.2.7 of the IBC to read:

903.2.7 Group M. An automatic sprinkler system shall be provided throughout buildings containing a Group M occupancy where one of the following conditions exists:

1. A Group M fire area exceeds 12,000 square feet (1115 m²).
2. A Group M fire area is located more than three stories above grade plane.
3. The combined area of all Group M fire areas on all floors, including any mezzanines, exceeds 24,000 square feet (2230 m²).

G. F. Change Section 903.2.8 of the IBC to read:

~~903.2.7~~ 903.2.8 Group R. An automatic sprinkler system installed in accordance with Section 903.3 shall be provided throughout all buildings with a Group R fire area, except in the following for Group R-2 occupancies listed in the exceptions to this section when the necessary water pressure or volume, or both, for the system is not available:

Exceptions:

1. Buildings Group R-2 occupancies which do not exceed two stories, including basements which are not considered as a story above grade, and with a maximum of 16 dwelling units per fire area. Each dwelling unit shall have at least one door opening to an exterior exit access that leads directly to the exits required to serve that dwelling unit.
2. Buildings Group R-2 occupancies where all dwelling units are not more than two stories above the lowest level of exit discharge and not more than one story below the highest level of exit discharge of exits serving the dwelling unit and a two-hour fire barrier is provided between each pair of dwelling units. Each bedroom of a dormitory or boarding house shall be considered a dwelling unit under this exception.

H. ~~Add Item 6 to Section 903.3.1.1.1 of the IBC to read:~~

~~6. Elevator machine rooms and elevator machine spaces for occupant evacuation elevators.~~

I. G. Add Section 903.3.1.2.2 to the IBC to read:

903.3.1.2.2 Attics. Sprinkler protection shall be provided for attics in buildings of Type III, IV or V construction in Group R-2 occupancies that are designed or developed and marketed to senior citizens 55 years of age or older and in Group I-1 occupancies in accordance with Section ~~6.7.2~~ 7.2 of NFPA 13R.

~~J.~~ H. Change Section 903.4.2 of the IBC to read:

903.4.2 Alarms. Approved audible devices shall be connected to every automatic sprinkler system. Such sprinkler water-flow alarm devices shall be activated by water flow equivalent to the flow of a single sprinkler of the smallest orifice size installed in the system. Alarm devices shall be provided on the exterior of the building in an approved location. Where a fire alarm system is installed, actuation of the automatic sprinkler system shall actuate the building fire alarm system. Group R-2 occupancies that contain 16 or more dwelling units or sleeping units, any dwelling unit or sleeping unit two or more stories above the lowest level of exit discharge, or any dwelling unit or sleeping unit more than one story below the highest level of exit discharge of exits serving the dwelling unit or sleeping unit shall provide a manual fire alarm box at an approved location to activate the suppression system alarm.

~~K.~~ I. Add an exception to Section 905.2 of the IBC to read:

Exception: The residual pressure of 100 psi for 2-1/2 inch hose connection and 65 psi for 1-1/2 inch hose connection is not required in buildings equipped throughout with an automatic sprinkler system in accordance with Section 903.3.1.1 or 903.3.1.2 and where the highest floor level is not more than 150 feet above the lowest level of fire department vehicle access.

~~L.~~ J. Change Item 1 of Section 906.1 of the IBC to read:

1. In Group A, B, E, F, H, I, M, R-1, R-4, and S occupancies.

Exceptions:

1. In Group A, B, and E occupancies equipped throughout with quick response sprinklers, portable fire extinguishers shall be required only in locations specified in Items 2 through 6.

2. In Group I-3 occupancies, portable fire extinguishers shall be permitted to be located at staff locations and the access to such extinguishers shall be permitted to be locked.

~~M.~~ K. Change Section 907.2.1.1 of the IBC to read:

907.2.1.1 System initiation in Group A occupancies with a occupant load of 1,000 or more and in certain night clubs. Activation of the fire alarm in Group A occupancies with an occupant load of 1,000 or more and in night clubs with an occupant load of 300 or more shall initiate a signal using an emergency voice and alarm communications system in accordance with Section 907.5.2.2.

Exception: Where approved, the prerecorded announcement is allowed to be manually deactivated for a period of time, not to exceed three minutes, for the sole purpose of allowing a live voice announcement from an approved, constantly attended location.

~~N.~~ L. Add an exception to Section 907.5.2.1.1 of the IBC to read:

Exception: Sound pressure levels in Group I-3 occupancies shall be permitted to be limited to only the notification of occupants in the affected smoke compartment.

~~O.~~ M. ~~Add~~ Change Sections 908.7, and 908.7.1 and add Section 908.7.2 to the IBC to read:

908.7 Carbon monoxide alarms. Carbon monoxide alarms shall be provided in new buildings and structures in accordance with this section.

908.7.1 Alarm requirements. Carbon monoxide alarms shall be single station, hard wired, plug-in or battery type, listed as complying with UL 2034, and shall be installed in accordance with this code and the manufacturer's installation instructions.

908.7.2 Where required. Carbon monoxide alarms shall be installed outside of each separate sleeping area in the immediate vicinity of the bedrooms in dwelling units and outside of, but in the immediate vicinity of, each sleeping unit in all Group R occupancies located within buildings containing fuel-fired appliances or where a dwelling unit or sleeping unit in a Group R occupancy is attached to a Group U private garage.

~~P.~~ N. Change Section 909.6 of the IBC to read:

909.6 Pressurization method. When approved by the building official, the means of controlling smoke shall be permitted by pressure differences across smoke barriers. Maintenance of a tenable environment is not required in the smoke-control zone of fire origin.

~~Q.~~ O. Change Section 911.1.3 of the IBC to read:

911.1.3 Size. The fire command center shall be a minimum of 96 square feet (9 m²) in area with a minimum dimension of eight feet (2438 mm).

Exception: Where it is determined by the building official, after consultation with the fire chief, that specific building characteristics require a larger fire command center, the building official may increase the minimum required size of the fire command center up to 200 square feet (19 m²) in area with a minimum dimension of up to 10 feet (3048 mm).

~~R.~~ P. Change the title of IBC Section 915 to read:

In-Building Emergency Communications Coverage.

~~S.~~ Q. Change Section 915.1 of the IBC to read:

915.1 General. For localities utilizing public safety wireless communications, dedicated infrastructure to accommodate and perpetuate continuous in-building emergency communication equipment to allow emergency public safety personnel to send and receive emergency communications shall be provided in new buildings and structures in accordance with this section.

Exceptions:

1. Buildings of Use Groups A-5, I-4, within dwelling units of R-2, R-3, R-4, R-5, and U.
2. Buildings of Type IV and V construction without basements, that are not considered unlimited area buildings in accordance with Section 507.
3. Above grade single story buildings of less than 20,000 square feet.
4. Buildings or leased spaces occupied by federal, state, or local governments, or the contractors thereof, with security requirements where the building official has approved an alternative method to provide emergency communication equipment for emergency public safety personnel.
5. Where the owner provides technological documentation from a qualified individual that the structure or portion thereof does not impede emergency communication signals.

~~T. R.~~ Add Sections 915.1.1, 915.1.2 and 915.1.3 to the IBC to read:

915.1.1 Installation. The building owner shall install radiating cable, such as coaxial cable or equivalent. The radiating cable shall be installed in dedicated conduits, raceways, plenums, attics, or roofs, compatible for these specific installations as well as other applicable provisions of this code. The locality shall be responsible for the installation of any additional communication equipment required for the operation of the system.

915.1.2 Operations. The locality will assume all responsibilities for the operation and maintenance of the emergency communication equipment. The building owner shall provide sufficient operational space within the building to allow the locality access to and the ability to operate in-building emergency communication equipment.

915.1.3 Inspection. In accordance with Section 113.3, all installations shall be inspected prior to concealment.

~~U. S.~~ Add Section 915.2 to the IBC to read:

915.2 Acceptance test. Upon completion of installation, after providing reasonable notice to the owner or their representative, emergency public safety personnel shall have the right during normal business hours, or other mutually agreed upon time, to enter onto the property to conduct field tests to verify that the required level of radio coverage is present at no cost to the owner. Any noted deficiencies in the installation of the radiating cable or operational space shall be provided in an inspection report to the owner or the owner's representative.

13VAC5-63-245. Chapter 10 Means of egress.

A. Change Section 1004.3 of the IBC to read:

1004.3 Posting of occupant load. Every room or space that is an assembly occupancy and where the occupant load of that room or space is 50 or more shall have the occupant load of the room or space posted in a conspicuous place, near the main exit or exit access doorway from the room or space. Posted signs shall be of an approved legible permanent design and shall be maintained by the owner or authorized agent.

B. Change the exception to Section 1005.1 1005.3.1 of the IBC to read:

~~1005.1 Minimum required egress width. The means of egress width shall not be less than required by this section. The total width of means of egress in inches (mm) shall not be less than the total occupant load served by the means of egress multiplied by 0.3 inches (7.62 mm) per occupant for stairways and by 0.2 inches (5.08 mm) per occupant for other egress components. The width shall not be less than specified elsewhere in this code. Multiple means of egress shall be sized such that the loss of any one means of egress shall not reduce the available capacity to less than 50% of the required capacity. The maximum capacity required from any story of a building shall be maintained to the termination of the means of egress.~~

~~Exceptions~~ Exception:

~~1. Means of egress complying with Section 1028.~~

~~2. For occupancies other than Groups H-1, H-2, H-3, H-4 Group H and I-2 occupancies, the capacity, in inches (mm), of means of egress stairways shall be calculated by multiplying the occupant load served by such stairway by a means of egress capacity factor of 0.2 inch (5.1 mm) per occupant in buildings equipped with an automatic sprinkler system installed in accordance with Section 903.3.1.1 or 903.3.1.2; the total width of means of egress in inches (mm) shall not be less than the total occupant load served by the means of egress multiplied by 0.2 inches (5.08 mm) per occupant for stairways and by 0.15 inches (3.81 mm) per occupant for other egress components.~~

C. Change the exception to Section 1005.3.2 of the IBC to read:

Exception: For other than Group H and I-2 occupancies, the capacity, in inches (mm), of means of egress components other than stairways shall be calculated by multiplying the occupant load served by such stairway by a means of egress capacity factor of 0.15 inch (3.8 mm) per occupant in buildings equipped with an automatic sprinkler system installed in accordance with Section 903.3.1.1 or 903.3.1.2.

Section 1007.2 of the IBC to read:

~~1007.2 Continuity and components. Each required accessible means of egress shall be continuous to a public way and shall consist of one or more of the following components:~~

- ~~1. Accessible routes complying with Section 1104.~~
- ~~2. Interior exit stairways complying with Sections 1007.3 and 1022.~~
- ~~3. Exterior exit stairways complying with Sections 1007.3 and 1026 and serving levels other than the level of exit discharge.~~
- ~~4. Elevators complying with Section 1007.4.~~
- ~~5. Platform lifts complying with Section 1007.5.~~
- ~~6. Horizontal exits complying with Section 1025.~~
- ~~7. Ramps complying with Section 1010.~~
- ~~8. Areas of refuge complying with Section 1007.6.~~
- ~~9. Exterior area for assisted rescue complying with Section 1007.7 serving exits at the level of exit discharge.~~

D. Change Section 1007.6.2 of the IBC to read:

1007.6.2 Separation. Each area of refuge shall be separated from the remainder of the story by a smoke barrier complying with Section 709 or a horizontal exit complying with Section 1025. Each area of refuge shall be designed to minimize the intrusion of smoke.

Exceptions:

1. Areas of refuge located within an exit enclosure.
2. Areas of refuge where the area of refuge and areas served by the area of refuge are equipped throughout with an automatic sprinkler system installed in accordance with Section 903.3.1.1 or 903.3.1.2.

E. Change Section 1007.7, including subsections, of the IBC to read:

~~1007.7 Exterior area for assisted rescue. The exterior area for assisted rescue shall be an area provided on the exterior landing serving an exit door on an accessible route. The exterior area of assisted rescue shall meet the size and access requirements of Section 1007.6.1.~~

~~1007.7.1 Separation. Exterior walls separating the exterior area of assisted rescue from the interior of the building shall have a minimum fire resistance rating of one hour, rated for exposure to fire from the inside. The fire resistance rated exterior wall construction shall extend horizontally 10 feet (3048 mm) beyond the landing on either side of the landing or~~

~~equivalent fire resistance-rated construction is permitted to extend out perpendicular to the exterior wall four feet (1220 mm) minimum on the side of the landing. The fire resistance-rated construction shall extend vertically from the ground to a point 10 feet (3048 mm) above the floor level of the area for assisted rescue or to the roof line, whichever is lower. Openings within such fire resistance-rated exterior walls shall be protected in accordance with Section 715.~~

~~1007.7.2 Openness. The exterior area for assisted rescue shall be at least 50% open, and the open area above the guards shall be so distributed as to minimize the accumulation of smoke or toxic gases.~~

~~1007.7.3 Exterior stairway. Exterior stairways that are part of the means of egress for the exterior area for assisted rescue shall provide a clear width of 48 inches (1219 mm) between handrails.~~

F. Change Item 2 of Section 1008.1.9.3 of the IBC to read:

2. In buildings in occupancy Groups B, F, M and S, the main exterior door or doors are permitted to be equipped with key-operated locking devices from the egress side provided:

2.1. The locking device is readily distinguishable as locked.

2.2. A readily visible durable sign is posted on the egress side on or adjacent to the door stating: THIS DOOR TO REMAIN UNLOCKED WHEN BUILDING IS OCCUPIED. The sign shall be in letters one inch (25 mm) high on a contrasting background.

2.3. The use of the key-operated locking device is revokable by the building official for due cause.

G. F. Delete Section 1008.1.9.6 of the IBC.

H. G. Change Section 1008.1.9.7 of the IBC to read:

1008.1.9.7 Delayed egress locks. Approved, listed, delayed egress locks shall be permitted to be installed on doors serving any occupancy including Group A-3, airport facilities, except Group A, E and H occupancies in buildings which are equipped throughout with an automatic sprinkler system in accordance with Section 903.3.1.1 or an approved automatic smoke or heat detection system installed in accordance with Section 907, provided that the doors unlock in accordance with Items 1 through 6 below. A building occupant shall not be required to pass through more than one door equipped with a delayed egress lock before entering an exit.

1. The doors unlock upon actuation of the automatic sprinkler system or automatic fire detection system.

2. The doors unlock upon loss of power controlling the lock or lock mechanism.

3. The door locks shall have the capability of being unlocked by a signal from the fire command center.

4. The initiation of an irreversible process which will release the latch in not more than 15 seconds when a force of not more than 15 pounds (67 N) is applied for 1 second to the release device. Initiation of the irreversible process shall activate an audible signal in the vicinity of the door. Once the door lock has been released by the application of force to the releasing device, relocking shall be by manual means only.

Exception: Where approved, a delay of not more than 30 seconds is permitted.

5. A sign shall be provided on the door located above and within 12 inches (305 mm) of the release device reading: PUSH UNTIL ALARM SOUNDS. DOOR CAN BE OPENED IN 15 SECONDS.

Exception: Where approved, such sign shall read: PUSH UNTIL ALARM SOUNDS. DOOR CAN BE OPENED IN 30 SECONDS.

6. Emergency lighting shall be provided at the door.

I. H. Delete the exception in Section 1008.1.10 of the IBC.

J. I. Add Section 1008.1.11 to the IBC to read:

1008.1.11 Locking certain residential sliding doors. In dwelling units of Group R-2 buildings, exterior sliding doors which are one story or less above grade, or shared by two dwelling units, or are otherwise accessible from the outside, shall be equipped with locks. The mounting screws for the lock case shall be inaccessible from the outside. The lock bolt shall engage the strike in a manner that will prevent it from being disengaged by movement of the door.

Exception: Exterior sliding doors which are equipped with removable metal pins or charlie bars.

K. J. Add Section 1008.1.12 to the IBC to read:

1008.1.12 Door viewers in certain residential buildings. Entrance doors to dwelling units of Group R-2 buildings shall be equipped with door viewers with a field of vision of not less than 180 degrees.

Exception: Entrance doors having a vision panel or side vision panels.

L. K. Change Exception 5 of Section ~~1009.4.2~~ 1009.7.2 of the IBC to read:

5. In Group R-3 occupancies; within dwelling units in Group R-2 occupancies; and in Group U occupancies that are accessory to a Group R-3 occupancy or accessory to individual dwelling units in Group R-2 occupancies; the maximum riser height shall be

8.25 inches (210 mm); the minimum tread depth shall be 9 inches (229 mm); the minimum winder tread depth at the walk line shall be 10 inches (254 mm); and the minimum winder tread depth shall be 6 inches (152 mm). A nosing not less than 0.75 inch (19.1 mm) but not more than 1.25 inches (32 mm) shall be provided on stairways with solid risers where the tread depth is less than 11 inches (279 mm).

M. Add Exception 3 to Change Section 1009.7 1013.8 of the IBC to read:

3. Spiral stairways used as a means of egress from technical production areas. 1013.8 Window sills. In Occupancy Groups R-2 and R-3, one- and two-family and multiple-family dwellings, where the opening of the sill portion of an operable window is located more than 72 inches (1829 mm) above the finished grade or other surface below, the lowest part of the clear opening of the window shall be at a height not less than 18 inches (457 mm) above the finished floor surface of the room in which the window is located. Operable sections of windows shall not permit openings that allow passage of a 4-inch-diameter (102 mm) sphere where such openings are located within 18 inches (457 mm) of the finished floor.

Exceptions:

1. Operable windows where the sill portion of the opening is located more than 75 feet (22 860 mm) above the finished grade or other surface below and that are provided with window fall prevention devices that comply with ASTM F 2006.

2. Windows whose openings will not allow a 4-inch diameter (102 mm) sphere to pass through the opening when the window is in its largest opened position.

3. Openings that are provided with window fall prevention devices that comply with ASTM F 2090.

4. Windows that are provided with window opening control devices that comply with Section 1013.8.1.

N. Add Exception 3 to Item 4 of Section 1014.2 of the IBC to read:

3. A maximum of one exit access is permitted to pass through kitchens, store rooms, closets or spaces used for similar purposes provided such a space is not the only means of exit access.

O. Change Table 1015.1 of the IBC to read:

Table 1015.1 Spaces With One Exit or Exit Access Doorway	
Occupancy	Maximum Occupant Load
A, B, E ^a , F, M, U	50
H-1, H-2, H-3	3
H-4, H-5, I-1, I-3, I-4, R	10
S	29

a. Day care maximum occupant load is 10.

P. Change Exception 2 of Section 1015.2.1 of the IBC to read:

2. Where a building is equipped throughout with an automatic sprinkler system in accordance with Section 903.3.1.1 or 903.3.1.2, the separation distance of the exit doors or exit access doorways shall not be less than one-fourth of the length of the maximum overall diagonal dimension of the area served.

Q. Delete Sections 1015.6 and 1015.6.1 of the IBC.

R. Change Table 1018.1 of the IBC to read:

Table 1018.1 Corridor Fire-Resistance Rating				
Occupancy	Occupant Served Corridor	Load By	Required Fire-Resistance Rating (hours)	
			Without sprinkler system	With sprinkler system ^b
H-1, H-2, H-3	All		Not Permitted	1
H-4, H-5	Greater than 30		Not Permitted	1
A, B, E, F, M, S, U	Greater than 30		1	0
R	Greater than 10		1	0.5
I-2 ^a , I-4	All		Not Permitted	0
I-1, I-3	All		Not Permitted	0
a. For requirements for occupancies in Group I-2, see Sections 407.2 and 407.3.				
b. Buildings equipped throughout with an automatic sprinkler system in accordance with Sections 903.3.1.1 or 903.3.1.2 where allowed.				

S. R. Add ~~Exception 7 to Section~~ an additional row to Table 1018.2 of the IBC to read:

~~7. Forty-four inches (1118 mm) — In corridors of Group I-2 assisted living facilities serving areas with wheelchair, walker and gurney traffic where residents are capable of self-preservation or where resident rooms have a means of egress door leading directly to the outside.~~

Occupancy	Width (minimum)
<u>In corridors of Group I-2 assisted living facilities licensed by the Virginia Department of Social Services serving areas with wheelchair, walker and gurney traffic where residents are capable of self-preservation or where resident rooms have a means of egress door leading directly to the outside.</u>	<u>44 inches</u>

T. S. Change the first row in Table ~~1021.2~~ 1021.2(2) to read:

Table 1021.2

Stories With One Exit		
Story	Occupancy	Maximum Occupants (or Dwelling Units) Per Floor and Travel Distance
First story or basement	A, B ^d , E ^e , F ^d , M, U, S ^d	50 occupants and 75 feet travel distance
	H 2, H 3	3 occupants and 25 feet travel distance
	H 4, H 5, I, R	10 occupants and 75 feet travel distance
	S ^a	29 occupants and 100 feet travel distance
Second story	B ^b , F, M, S ^a	29 occupants and 75 feet travel distance
	R-2	4 dwelling units and 50 feet travel distance
Third story	R-2 ^e	4 dwelling units and 50 feet travel distance
<p>For SI: 1 foot = 304.8 mm</p> <p>a. For the required number of exits for parking structures, see Section 1021.1.2.</p> <p>b. For the required number of exits for air traffic control towers, see Section 412.3.</p> <p>c. Buildings classified as Group R-2 equipped throughout with an automatic sprinkler system in accordance with Section 903.3.1.1 or 903.3.1.2 and provided with emergency escape and rescue openings in accordance with Section 1029.</p> <p>d. Group B, F and S occupancies in buildings equipped throughout with an automatic sprinkler system in accordance with Section 903.3.1.1 shall have a maximum travel distance of 100 feet.</p> <p>e. Day care occupancies shall have a maximum occupant load of 10.</p>		

<u>Story</u>	<u>Occupancy</u>	<u>Maximum Occupants Per Story</u>	<u>Maximum Exit Access Travel Distance</u>
<u>First story or basement</u>	<u>A, B^b, E, F^b, M, U, S^b</u>	<u>50 occupants</u>	<u>75 feet</u>

U. Change Exception 6 of Section 1022.1 of the IBC to read:

6. Means of egress stairways as provided for in Section 410.6.2 are not required to be enclosed.

V. T. Change Section 1022.8 1022.9 of the IBC to read:

1022.8 1022.9 Floor identification signs. A sign shall be provided at each floor landing in exit enclosures connecting more than three stories designating the floor level, the terminus of the top and bottom of the exit enclosure and the identification of the stair or ramp by designation with a letter of the alphabet. The signage shall also state the story of, and the direction to, the exit discharge and the availability of roof access from the enclosure for the fire department. The sign shall be located five feet (1524 mm) above the floor landing in a position that is readily visible when the doors are in the open and closed positions.

Floor level identification signs in tactile characters complying with ICC A117.1 shall be located at each floor level landing adjacent to the door leading from the enclosure into the corridor to identify the floor level.

W. U. Change Section 1024.1 of the IBC to read:

1024.1 General. Approved luminous egress path markings delineating the exit path shall be provided in buildings of Groups A, B, E, I, M and R-1 having occupied floors located more than 420 feet (128 016 mm) above the lowest level of fire department vehicle access in accordance with Sections 1024.1 through 1024.5.

Exceptions Exception:

~~1.~~ Luminous egress path markings shall not be required on the level of exit discharge in lobbies that serve as part of the exit path in accordance with Section 1027.1, Exception 1.

~~2. Luminous egress path markings shall not be required in areas of open parking garages that serve as part of the exit path in accordance with Section 1027.1, Exception 3.~~

13VAC5-63-250. Chapter 11 Accessibility.

A. Add an exception to Section 1101.2 of the IBC to read:

Exception: Wall-mounted visible alarm notification appliances in Group I-3 occupancies shall be permitted to be a maximum of 120 inches (3048 mm) above the floor or ground, measured to the bottom of the appliance. Such appliances shall otherwise comply with all applicable requirements.

B. Add Section 1103.2.16 to the IBC to read:

1103.2.16 Raised and lowered areas in places of religious worship. Raised or lowered areas in places of religious worship are not required to be accessible or to be served by an accessible route provided such areas are used exclusively for the performance of religious ceremonies and are located within an accessible story or mezzanine.

C. Add Section 1106.8 to the IBC to read:

1106.8 Identification of accessible parking spaces. In addition to complying with applicable provisions of this chapter, all accessible parking spaces shall be identified by above grade signs. A sign or symbol painted or otherwise displayed on the pavement of a parking space shall not constitute an above grade sign. All above grade parking space signs shall have the bottom edge of the sign no lower than four feet (1219 mm) nor higher than seven feet (2133 mm) above the parking surface. All disabled parking signs shall include the following language: PENALTY, \$100-500 Fine, TOW-AWAY ZONE. Such language may be placed on a separate sign and attached below existing above grade

disabled parking signs, provided that the bottom edge of the attached sign is no lower than four feet above the parking surface.

D. Change Item 1 of Section 1110.1 of the IBC to read:

1. Accessible parking spaces required by Section 1106.1.

13VAC5-63-260. Chapter 12 Interior environment.

A. Add the following definitions to the list of terms in Section 1202.1 of the IBC:

Day-night average sound level (Ldn). ~~A 24-hour energy average sound level expressed in dBA, with a 10-decibel penalty applied to noise occurring between 10 p.m. and 7 a.m.~~

Sound transmission class (STC) rating. ~~A single number characterizing the sound reduction performance of a material tested in accordance with ASTM E90-90, "Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions."~~

B. Add Section 1203.4.4 to the IBC to read:

1203.4.4 Insect screens in occupancies other than Group R. Every door, window and other outside opening for natural ventilation serving structures classified as other than a residential group containing habitable rooms, food preparation areas, food service areas, or any areas where products to be included or utilized in food for human consumption are processed, manufactured, packaged, or stored, shall be supplied with approved tightly fitting screens of not less than 16 mesh per inch (16 mesh per 25 mm) and every screen door used for insect control shall have a self-closing device.

Exception: Screen doors shall not be required for out swinging doors or other types of openings which make screening impractical, provided other approved means, such as air curtains or insect repellent fans are provided.

C. Add Section 1203.4.5 to the IBC to read:

1203.4.5 Insect screens in Group R occupancies. Every door, window and other outside opening required for natural ventilation purposes which serves a structure classified as a residential group shall be supplied with approved tightly fitted screens of not less than 16 mesh per inch (16 mesh per 25 mm) and every screen door used for insect control shall have a self-closing device.

D. Change Section 1207.1 of the IBC to read:

1207.1 Scope. Sections 1207.2 and 1207.3 shall apply to common interior walls, partitions and floor/ceiling assemblies between adjacent dwelling units or between dwelling units and adjacent public areas such as halls, corridors, stairs or service areas. Section 1207.4 applies to the construction of the exterior envelope of Group R occupancies within airport noise zones and to the exterior envelope of Group A, B, E, I and M occupancies in any locality in whose jurisdiction, or adjacent jurisdiction, is located a United States Master

Jet Base, a licensed airport or United States government or military air facility, when such requirements are enforced by a locality pursuant to § 15.2-2295 of the Code of Virginia.

E. Add Section 1207.4 to the IBC to read:

1207.4 Airport noise attenuation standards. Where the Ldn is determined to be 65 dBA or greater, the minimum STC rating of structure components shall be provided in compliance with Table 1207.4. As an alternative to compliance with Table 1207.4, structures shall be permitted to be designed and constructed so as to limit the interior noise level to no greater than 45 Ldn. Exterior structures, terrain and permanent plantings shall be permitted to be included as part of the alternative design. The alternative design shall be certified by an RDP.

F. Add Table 1207.4 to the IBC to read:

Table 1207.4. Airport Noise Attenuation Standards.		
Ldn	STC of exterior walls and roof/ceiling assemblies	STC of doors and windows
65-69	39	25
70-74	44	33
75 or greater	49	38

13VAC5-63-264. Chapter 13 Energy efficiency.

Add Section 1301.1.1.1 to the IBC to read:

1301.1.1.1 Changes to the International Energy Conservation Code (IECC). The following change changes shall be made to the IECC:

1. Delete Section ~~401.3~~ R401.3.
2. Change Section ~~403.2.2~~ R403.2.2 to read:

~~403.2.2~~ R403.2.2 Sealing (Mandatory). ~~All ducts~~ Ducts, air handlers, and filter boxes ~~and building cavities used as ducts~~ shall be sealed. Joints and seams shall comply with Section M1601.4.1 of either the International Mechanical Code or the International Residential Code, as applicable. Verification of compliance with this section shall be in accordance with either Section ~~403.2.2.1~~ R403.2.2.1 or Section ~~403.2.2.2~~ R403.2.2.2.

Exceptions:

1. Air-impermeable spray foam products shall be permitted to be applied without additional joint seals.

2. Where a duct connection is made that is partially inaccessible, three screws or rivets shall be equally spaced on the exposed portion of the joint so as to prevent a hinge effect.

3. Continuously welded and locking-type longitudinal joints and seams in ducts operating at static pressures less than 2 inches of water column (500 Pa) pressure classification shall not require additional closure systems.

3. Add Change Section 403.2.2.1 R403.2.2.1 to read:

403.2.2.1 R403.2.2.1 Testing option. Duct tightness shall be verified by either of the following:

1. Post-construction test: ~~Leakage to outdoors~~ Total leakage shall be less than or equal to ~~8 4 cfm (3.78 L/s 113.3 L/min)~~ 8 4 cfm (3.78 L/s 113.3 L/min) per 100 ~~ft² square feet (9.29 m²)~~ ft² square feet (9.29 m²) of conditioned floor area ~~or a total leakage less than or equal to 12 cfm (5.66 L/s) per 100 ft² (9.29 m²) of conditioned floor area~~ when tested at a pressure differential of 0.1 inch w.g. (25 Pa) across the entire system, including the manufacturer's air handler ~~end closure enclosure~~. All register boots shall be taped or otherwise sealed during the test.

2. Rough-in test: Total leakage shall be less than or equal to ~~6 4 cfm (2.83 L/s 113.3 L/min)~~ 6 4 cfm (2.83 L/s 113.3 L/min) per 100 ~~ft² square feet (9.29 m²)~~ ft² square feet (9.29 m²) of conditioned floor area when tested at a pressure differential of 0.1 inch w.g. (25 Pa) across the ~~roughed-in~~ system, including the manufacturer's air handler enclosure. All register boots shall be taped or otherwise sealed during the test. If the air handler is not installed at the time of the test, total leakage shall be less than or equal to ~~4 3 cfm (1.89 L/s 85 L/min)~~ 4 3 cfm (1.89 L/s 85 L/min) per 100 ~~ft² square feet (9.29 m²)~~ ft² square feet (9.29 m²) of conditioned floor area.

Exception: Duct tightness ~~The total leakage test is not required if the~~ The total leakage test is not required if the ~~for ducts and air handler and all ducts are~~ for ducts and air handler and all ducts are ~~handlers located entirely within conditioned space the building thermal envelope.~~ handlers located entirely within conditioned space the building thermal envelope.

When this option is chosen, testing shall be performed by approved qualified individuals, testing agencies or contractors. Testing and results shall be as prescribed in Section 403.2.2 R403.2.2 and approved recognized industry standards.

4. Add Section ~~403.2.2.2~~ R403.2.2.2 to read:

403.2.2.2 R403.2.2.2 Visual inspection option. In addition to the inspection of ducts otherwise required by this code, when the air handler and all ducts are not within conditioned space and this option is chosen to verify duct tightness, duct tightness shall be considered acceptable when the requirements of Section ~~403.2.2~~ R403.2.2 are field verified.

5. Add Section R403.2.2.3 to read:

R403.2.2.3 Sealed air handler. Air handlers shall have a manufacturer's designation for an air leakage of no more than 2 percent of the design air flow rate when tested in accordance with ASHRAE 193.

13VAC5-63-267. Chapter 14 Exterior walls. (Repealed.)

Change Section 1405.13.2 of the IBC to read:

~~1405.13.2 Window sills. In Occupancy Groups R-2 and R-3, one and two family and multiple family dwellings, where the opening of the sill portion of an operable window is located more than 72 inches (1829 mm) above the finished grade or other surface below, the lowest part of the clear opening of the window shall be at a height not less than 18 inches (457 mm) above the finished floor surface of the room in which the window is located. Glazing between the floor and a height of 18 inches (457 mm) shall be fixed or have openings through which a 4 inch (102 mm) diameter sphere cannot pass.~~

~~Exception: Openings that are provided with window guards that comply with ASTM F2006 or F2090.~~

13VAC5-63-270. Chapter 16 Structural design.

A. Change Section 1609.3 of the IBC to read:

1609.3 Basic wind speed. The basic ultimate design wind speed, V_{ult} , in mph, for the determination of the wind loads shall be determined by ~~Figure 1609~~ Figures 1609A, 1609B and 1609C. The ultimate design wind speed, V_{ult} , for use in the design of Risk Category II buildings and structures shall be obtained from Figure 1609A. The ultimate design wind speed, V_{ult} , for use in the design of Risk Category III and IV buildings and structures shall be obtained from Figure 1609B. The ultimate design wind speed, V_{ult} , for use in the design of Risk Category I buildings and structures shall be obtained from Figure 1609C. ~~Wind~~ The ultimate design wind speeds for localities in special wind regions, near mountainous terrains, and near gorges shall be based on elevation. Areas at 4,000 feet in elevation or higher shall use 140 142 V mph (48.4 62.5 m/s) and areas under 4,000 feet in elevation shall use 90 116 V mph (39.6 51 m/s). Gorge areas shall be based on the highest recorded speed per locality or in accordance with local jurisdiction requirements determined in accordance with Section 6.5.4 26.5.1 of ASCE 7.

In nonhurricane-prone regions, when the basic ultimate design wind speed, V_{ult} , is estimated from regional climatic data, the basic ultimate design wind speed, V_{ult} , shall be not less than the wind speed associated with an annual probability of 0.02 (50-year mean recurrence interval), and the estimate shall be adjusted for equivalence to a three-second gust wind speed at 33 feet (10 m) above ground in exposure Category C. The data analysis shall be performed determined in accordance with Section 6.5.4.2 26.5.3 of ASCE 7.

B. Add Section 1612.1.1 to the IBC to read:

1612.1.1 Elevation of manufactured homes. New or replacement manufactured homes to be located in any flood hazard zone shall be placed in accordance with the applicable elevation requirements of this code.

Exception: Manufactured homes installed on sites in an existing manufactured home park or subdivision shall be permitted to be placed so that the manufactured home chassis is supported by reinforced piers or other foundation elements of at least equivalent strength that are no less than 36 inches (914 mm) above grade in lieu of being elevated at or above the base flood elevation provided no manufactured home at the same site has sustained flood damage exceeding 50% of the market value of the home before the damage occurred.

13VAC5-63-280. Chapter 17 ~~Structural tests and special~~ Special inspections and tests.

A. Change Section 1703.1 of the IBC to read:

1703.1 Approved agency. An approved agency responsible for laboratory testing or special inspections, or both, must comply with the qualification, certification and experience requirements of ASTM E329 or the alternatives listed herein.

B. Change Section 1703.1.1 of the IBC to read:

1703.1.1 ~~Independent~~ Independence. An approved agency shall be objective and competent. The agency shall also disclose possible conflicts of interest so that objectivity can be confirmed. The special inspector and their agents shall be independent from the person, persons or contractor responsible for the physical construction of the project requiring special inspections.

C. Change Section 1703.1.3 of the IBC to read:

1703.1.3 Personnel. An approved agency shall employ experienced personnel educated in conducting, supervising and evaluating tests or inspections, or both. Upon request by the building official, documentation shall be provided demonstrating the applicable agency's accreditation as noted in ASTM E329 and individuals' resumes indicating pertinent training, certifications and other qualifications for special inspection personnel associated with the proposed construction requiring special inspections. The building official may prescribe the manner of qualification documentation and frequency of updating information regarding agency or individual inspector approval.

Firms providing special inspection services or individual inspectors seeking approval of alternative certifications or qualifications, or both, listed in ASTM E329 may submit documentation demonstrating equivalency. This documentation may include evidence of meeting other recognized standards or alternative certifications to demonstrate that the minimum qualifications, certification and experience intended by ASTM E329 have been met. The building official may, if satisfied that equivalency has been demonstrated, approve the credentials of the firm or individual.

D. Change Section ~~1704.1~~ 1704.2 of the IBC to read:

~~1704.1. General~~ 1704.2 Special inspections. Where application is made for construction as described in this section, the owner shall employ one or more special inspectors to provide inspections during construction on the types of work listed under Section 1704. All individuals or agents performing special inspection functions shall operate under the direct supervision of an RDP in responsible charge of special inspection activities, also known as the "special inspector." The special inspector shall ensure that the individuals under their charge are performing only those special inspections or laboratory testing that are consistent with their knowledge, training and certification for the specified inspection or laboratory testing.

Exceptions:

1. Special inspections are not required for work of a minor nature or as warranted by conditions in the jurisdiction as approved by the building official.
2. Special inspections are not required for building components unless the design involves the practice of professional engineering or architecture as defined by the laws of this Commonwealth and regulations governing the professional registration and certification of engineers and architects.
3. Unless otherwise required by the building official, special inspections are not required for occupancies in Groups R-3, R-4 or R-5 and occupancies in Group U that are accessory to a residential occupancy including, but not limited to, those listed in Section 312.1.

E. Change Section ~~1704.1.1~~ 1704.2.3 of the IBC to read:

~~1704.1.1~~ 1704.2.3 Statement of special inspections. The permit applicant shall submit a statement of special inspections prepared by the RDP in responsible charge in accordance with Section 111.1. This statement shall be in accordance with Section ~~1705~~ 1704.3.

Exceptions:

1. A statement of special inspections is not required for structures designed and constructed in accordance with the conventional construction provisions of Section 2308.
2. The statement of special inspections is permitted to be prepared by a qualified person approved by the building official for construction not designed by a registered design professional.

F. Change category "12" of Table ~~1704.4~~ 1705.3 of the IBC to read:

Verification and inspection	Continuous	Periodic	Referenced Standard ^a	IBC Reference
12. Inspect formwork for shape, location and	--	X	ACI 318: 6.1, 6.2 <u>6.1.1</u>	1906 --

dimensions of the concrete member being formed, shoring and reshoring.				
--	--	--	--	--

13VAC5-63-290. Chapter 18 Soils and foundations.

A. Change the exception to Section 1804.5 of the IBC to read:

Exception: Compacted fill material less than 12 inches (305 mm) in depth need not comply with an approved report, provided it is a natural non-organic material that is not susceptible to swelling when exposed to moisture and it has been compacted to a minimum of 90% Modified Proctor in accordance with ASTM D1557. The compaction shall be verified by a qualified inspector approved by the building official. Material other than natural material may be used as fill material when accompanied by a certification from an RDP and approved by the building official.

B. Add an exception to Section 1808.1 of the IBC to read:

Exception: One-story detached accessory structures not exceeding 256 square feet (23.78m²) of building area, provided all of the following conditions are met:

1. The building eave height is 10 feet (3048 mm) or less.
2. The maximum height from the finished floor level to grade does not exceed 18 inches (457.2 mm).
3. The supporting structural elements in direct contact with the ground shall be placed level on firm soil and when such elements are wood they shall be approved pressure preservative treated suitable for ground contact use.
4. The structure is anchored to withstand wind loads as required by this code.
5. The structure shall be of light-frame construction with walls and roof of light weight material, not slate, tile, brick or masonry.

13VAC5-63-300. Chapter 27 Electrical.

A. Change Section 2701.1 of the IBC to read:

2701.1 Scope. This chapter governs the electrical components, equipment and systems used in buildings and structures covered by this code. Electrical components, equipment and systems shall be designed and constructed in accordance with the provisions of this code and NFPA 70.

B. Add Section 2701.1.1 to the IBC to read:

2701.1.1 Changes to NFPA 70. The following change shall be made to NFPA 70:

1. Change Sections 334.10(2) and 334.10(3) of NFPA 70 to read:

(2) Multifamily dwellings not exceeding four floors above grade and multifamily dwellings of any height permitted to be of Types III, IV and V construction except in any case as prohibited in 334.12.

(3) Other structures not exceeding four floors above grade and other structures of any height permitted to be of Types III, IV and V construction except in any case as prohibited in 334.12. In structures exceeding four floors above grade, cables shall be concealed within walls, floors or ceilings that provide a thermal barrier of material that has at least a 15-minute finish rating as identified in listings of fire-rated assemblies.

For the purpose of Items 2 and 3 above, the first floor of a building shall be that floor that has 50% or more of the exterior wall surface area level with or above finished grade. One additional level that is the first level and not designed for human habitation and used only for vehicle parking, storage or similar use shall be permitted.

C. Add Section 2701.1.2 to the IBC to read:

2701.1.2 Temporary connection to dwelling units. The building official shall give permission to energize the electrical service equipment of a one- or two-family dwelling unit when all of the following requirements have been approved:

1. The service wiring and equipment, including the meter socket enclosure, shall be installed and the service wiring terminated.
2. The grounding electrode system shall be installed and terminated.
3. At least one receptacle outlet on a ground fault protected circuit shall be installed and the circuit wiring terminated.
4. Service equipment covers shall be installed.
5. The building roof covering shall be installed.
6. Temporary electrical service equipment shall be suitable for wet locations unless the interior is dry and protected from the weather.

D. Add Section 2701.1.3 to the IBC to read:

2701.1.3 Assisted living facility generator requirements. Generators installed to comply with regulations for assisted living facilities licensed by the Virginia Department of Social Services shall be permitted to be optional standby systems.

E. Change Section 2702.2.17 of the IBC to read:

2702.2.17 Group I-2 and I-3 occupancies. Emergency power shall be provided in accordance with Section 407.11 for Group I-2 occupancies licensed by the Virginia

Department of Health as a hospital, nursing or hospice facility. Emergency power shall be provided for doors in Group I-3 occupancies in accordance with Section 408.4.2.

13VAC5-63-310. Chapter 28 Mechanical systems.

A. Change Section 2801.1 of the IBC to read:

2801.1 Scope. Mechanical appliances, equipment and systems shall be constructed and installed in accordance with this chapter, the ~~International Mechanical Code~~ IMC and the ~~International Fuel Gas Code~~ IFGC. Masonry chimneys, fireplaces and barbecues shall comply with the ~~International Mechanical Code~~ IMC and Chapter 21 of this code.

Exception: This code shall not govern the construction of water heaters, boilers and pressure vessels to the extent which they are regulated by the Virginia Boiler and Pressure Vessel Regulations (16VAC25-50). However, the building official may require the owner of a structure to submit documentation to substantiate compliance with those regulations.

B. Add Section 2801.1.1 to the IBC to read:

2801.1.1 Required heating in dwelling units. Heating facilities shall be required in every dwelling unit or portion thereof which is to be rented, leased or let on terms, either expressed or implied, to furnish heat to the occupants thereof. The heating facilities shall be capable of maintaining the room temperature at 65°F (18°C) during the period from October 15 to May 1 during the hours between 6:30 a.m. and 10:30 p.m. of each day and not less than 60°F (16°C) during other hours when measured at a point three feet (914 mm) above the floor and three feet (914 mm) from the exterior walls. The capability of the heating system shall be based on the outside design temperature required for the locality by this code.

C. Add Section 2801.1.2 to the IBC to read:

2801.1.2 Required heating in nonresidential structures. Heating facilities shall be required in every enclosed occupied space in nonresidential structures. The heating facilities shall be capable of producing sufficient heat during the period from October 1 to May 15 to maintain a temperature of not less than 65°F (18°C) during all working hours. The required room temperature shall be measured at a point three feet (914 mm) above the floor and three feet (914 mm) from the exterior walls.

Processing, storage and operation areas that require cooling or special temperature conditions and areas in which persons are primarily engaged in vigorous physical activities are exempt from these requirements.

D. Add Section 2801.1.3 to the IBC to read:

2801.1.3 Changes to the ~~International Mechanical Code~~ (IMC) IMC. The following changes shall be made to the IMC:

1. Change Section 403.3 of the IMC to read:

403.3 Outdoor airflow rate. Ventilation systems shall be designed to have the capacity to supply the minimum outdoor airflow rate determined in accordance with this section. The occupant load utilized for design of the ventilation system shall not be less than the number determined from the estimated maximum occupant load rate indicated in Table 403.3. Ventilation rates for occupancies not represented in Table 403.3 shall be those for a listed occupancy classification that is most similar in terms of occupant density, activities and building construction; or shall be determined by an approved engineering analysis. The ventilation system shall be designed to supply the required rate of ventilation air continuously during the period the building is occupied, except as otherwise stated in other provisions of the code.

With the exception of smoking lounges and other designated areas where smoking is permitted, the ventilation rates in Table 403.3 are based on the absence of smoking in occupiable spaces.

Exception: The occupant load is not required to be determined based on the estimated maximum occupant load rate indicated in Table 403.3 where approved statistical data document the accuracy of an alternate anticipated occupant density.

2. Add the following areas to Table 403.3 of the IMC in the occupancy classifications shown:

OCCUPANCY CLASSIFICATION	<u>People Outdoor Airflow Rate in Breathing Zone Cfm/person Occupant Density #/1000 ft^{2a}</u>	<u>Area People Outdoor Airflow Rate in Breathing Zone, R_{a,p} cfm/ft^{2a} person</u>	<u>Default Occupant Density #/1000 ft^{2a} Area Outdoor Airflow Rate in Breathing Zone, R_a cfm/ft^{2a}</u>	Exhaust Airflow Rate Cfm/ft ^{2a}
Food and beverage service				
Bars or cocktail lounges designated as an area <u>when where smoking is permitted^b</u>	30 <u>100</u>	- <u>30</u>	100 -	-
Cafeteria or fast food designated as an area <u>when where smoking is permitted</u>	20 <u>100</u>	- <u>20</u>	100 -	-
Dining rooms designated as an area <u>when where smoking is permitted</u>	20 <u>70</u>	- <u>20</u>	70 -	-
Public spaces				
Lounges designated as an area where smoking is permitted ^b	30 <u>100</u>	- <u>30</u>	100 -	-

3. Add Section 801.1.1 to the IMC to read:

801.1.1 Equipment changes. Upon the replacement or new installation of any fuel-burning appliances or equipment in existing buildings, an inspection or inspections shall be conducted to ensure that the connected vent or chimney systems comply with the following:

1. Vent or chimney systems are sized in accordance with this code.
2. Vent or chimney systems are clean, free of any obstruction or blockages, defects or deterioration and are in operable condition.

Where not inspected by the local building department, persons performing such changes or installations shall certify to the building official that the requirements of Items 1 and 2 of this section are met.

4. ~~Change Section 1101.10 of the IMC to read:~~

~~1101.10 Locking access port caps. Refrigerant circuit access ports located outdoors shall be fitted with locking type tamper resistant caps or shall be otherwise secured to prevent unauthorized access.~~

E. Add Section 2801.1.4 to the IBC to read:

2801.1.4 Changes to the ~~International Fuel Gas Code~~ IFGC. The following changes shall be made to the ~~International Fuel Gas Code~~ IFGC:

1. Change Section 301.1 of the ~~International Fuel Gas Code~~ IFGC to read:

301.1 Scope. This code shall apply to the installation of fuel gas piping systems, fuel gas utilization equipment, and related accessories as follows:

1. Coverage of piping systems shall extend from the point of delivery to the connections with gas utilization equipment. (See "point of delivery.")
2. Systems with an operating pressure of 125 psig (862 kPa gauge) or less.

Piping systems for gas-air mixtures within the flammable range with an operating pressure of 10 psig (69 kPa gauge) or less.

LP-Gas piping systems with an operating pressure of 20 psig (140 kPa gauge) or less.

3. Piping systems requirements shall include design, materials, components, fabrication, assembly, installation, testing and inspection.
4. Requirements for gas utilization equipment and related accessories shall include installation, combustion and ventilation air and venting.

This code shall not apply to the following:

1. Portable LP-Gas equipment of all types that are not connected to a fixed fuel piping system.
2. Installation of farm equipment such as brooders, dehydrators, dryers, and irrigation equipment.
3. Raw material (feedstock) applications except for piping to special atmosphere generators.
4. Oxygen-fuel gas cutting and welding systems.
5. Industrial gas applications using gases such as acetylene and acetylenic compounds, hydrogen, ammonia, carbon monoxide, oxygen, and nitrogen.
6. Petroleum refineries, pipeline compressor or pumping stations, loading terminals, compounding plants, refinery tank farms, and natural gas processing plants.
7. Integrated chemical plants or portions of such plants where flammable or combustible liquids or gases are produced by chemical reactions or used in chemical reactions.
8. LP-Gas installations at utility gas plants.
9. Liquefied natural gas (LNG) installations.
10. Fuel gas piping in power and atomic energy plants.
11. Proprietary items of equipment, apparatus, or instruments such as gas generating sets, compressors, and calorimeters.
12. LP-Gas equipment for vaporization, gas mixing, and gas manufacturing.
13. Temporary LP-Gas piping for buildings under construction or renovation that is not to become part of the permanent piping system.
14. Installation of LP-Gas systems for railroad switch heating.
15. Installation of LP-Gas and compressed natural gas (CNG) systems on vehicles.
16. Except as provided in Section 401.1.1, gas piping, meters, gas pressure regulators, and other appurtenances used by the serving gas supplier in the distribution of gas, other than undiluted LP-Gas.

17. Building design and construction, except as specified herein.

2. Add Section ~~404.9.3~~ 404.11.3 to the ~~International Fuel Gas Code~~ IFGC to read:

~~404.9.3~~ 404.11.3 Coating application. Joints in gas piping systems shall not be coated prior to testing and approval.

3. Add Section 501.1.1 to the ~~International Fuel Gas Code~~ IFGC to read:

501.1.1 Equipment changes. Upon the replacement or new installation of any fuel-burning appliances or equipment in existing buildings, an inspection or inspections shall be conducted to ensure that the connected vent or chimney systems comply with the following:

1. Vent or chimney systems are sized in accordance with this code.
2. Vent or chimney systems are clean, free of any obstruction or blockages, defects or deterioration and are in operable condition.

Where not inspected by the local building department, persons performing such changes or installations shall certify to the building official that the requirements of Items 1 and 2 of this section are met.

13VAC5-63-320. Chapter 29 Plumbing systems.

A. Change Section 2901.1 of the IBC to read:

2901.1 Scope. The provisions of this chapter and the ~~International Plumbing Code (IPC)~~ IPC shall govern the design and installation of all plumbing systems and equipment, except that as provided for in Section 103.11 for functional design, water supply sources and sewage disposal systems are regulated and approved by the Virginia Department of Health and the Virginia Department of Environmental Quality. The approval of pumping and electrical equipment associated with such water supply sources and sewage disposal systems shall, however, be the responsibility of the building official.

Note: See also the Memorandum of Agreement in the "Related Laws Package," which is available from DHCD.

B. Add Section 2901.1.1 to the IBC to read:

~~2901.1.1 Use of Appendix C of the IPC for gray water and rain water recycling systems. In addition to other applicable provisions of the IPC, gray water recycling systems and rain water recycling systems shall comply with the provisions in Appendix C of the IPC. In the use of Appendix C of the IPC for rain water recycling systems, the term "rain water" shall be substituted for the term "gray water." Gray water recycling systems and rain water recycling systems shall be separate systems and shall not be interconnected.~~

~~C. Add Section 2901.1.2 to the IBC to read:~~

2901.1.2 Changes to the IPC. The following changes shall be made to the IPC:

1. Change the exception to Section 301.3 of the IPC to read:

~~301.3 Connections to drainage system. All plumbing fixtures, drains, appurtenances and appliances used to receive or discharge liquid wastes or sewage shall be directly connected to the sanitary drainage system of the building or premises, in accordance with the requirements of this code. This section shall not be construed to prevent indirect waste systems required by Chapter 8.~~

Exception: Bathtubs, showers, lavatories, clothes washers and laundry trays shall not be required to discharge to the sanitary drainage system where such fixtures discharge to an approved gray water system or rain water system for flushing of water closets and urinals or for subsurface landscape irrigation.

2. Delete Sections 311 and 311.1 of the IPC.

3. Change Section 602.1 of the IPC to read:

602.1 General. Every structure equipped with plumbing fixtures and utilized for human occupancy or habitation shall be provided with a potable supply of water in the amounts and at the pressures specified in this chapter. This shall not prohibit the use of reclaimed water distribution systems installed in accordance with this code and the Virginia Water Reclamation and Reuse Regulation (9VAC25-740).

4. Change Section 604.1 of the IPC to read:

604.1 General. The design of the water distribution system, including any reclaimed water distribution systems governed by the Virginia Water Reclamation and Reuse Regulation (9VAC25-740), shall conform to accepted engineering practice. Methods utilized to determine pipe sizes shall be approved.

5. Add an exception to Section 608.8 of the IPC to read:

Exception: Reclaimed water supply systems shall be identified in accordance with the provisions of the Virginia Water Reclamation and Reuse Regulation (9VAC25-740).

6. Change Section 608.8.2 of the IPC to read:

608.8.2 Color. The color of the pipe identification shall be discernable and consistent throughout the building. The color purple shall be used to identify rain and gray water distribution systems.

7. Delete Section 701.9 of the IPC.

8. Add Section 703.6 of the IPC to read:

703.6 Tracer wire. Nonmetallic sanitary sewer piping that discharges to public systems shall be locatable. An insulated copper tracer wire, 18 AWG minimum in size and suitable for direct burial or an equivalent product, shall be utilized. The wire shall be installed in the same trench as the sewer within 12 inches (305 mm) of the pipe and shall be installed to within five feet (1524 mm) of the building wall to the point where the building sewer intersects with the public system. At a minimum, one end of the wire shall terminate above grade in an accessible location that is resistant to physical damage, such as with a cleanout or at the building wall.

9. Change Section 1301.1 to read:

1301.1 Scope. The provisions of Chapter 13 shall govern the materials, design, construction and installation of gray water and rain water systems for flushing of water closets and urinals and for subsurface landscape irrigation. See Figures 1301.1(1) and 1301.1(2). In the use of Chapter 13 for rain water systems, the term "rain water" shall be substituted for the term "gray water." Gray water systems and rain water systems shall be separate systems and shall not be interconnected.

13VAC5-63-330. Chapter 30 Elevators and conveying systems.

A. Change Section 3002.4 of the IBC to read:

3002.4 Elevator car to accommodate ambulance stretcher. Where elevators are provided in buildings four or more stories above, or four or more stories below, grade plane, at least one elevator shall be provided for fire department emergency access to all floors. The elevator car shall be of such a size and arrangement to accommodate an ambulance stretcher 24 inches by 84 inches (610 mm by 2134 mm) with not less than five-inch (127 mm) radius corners, in the horizontal, open position and shall be identified by the international symbol for emergency medical services (star of life). The symbol shall not be less than three inches (76 mm) high and shall be placed inside on both sides of the hoistway door frame on the designated and alternate landing floors required to be established by ASME A17.1.

Exception: Elevators in multistory dwelling units or guest rooms.

B. Add Section 3003.2.1 to the IBC to read:

3003.2.1 Standardized fire service elevator keys. Where a key is required to operate the emergency function of an elevator, the key shall be a standardized fire service key in accordance with the Virginia Statewide Fire Prevention Code (13VAC5-51).

C. Change Section 3006.4 of the IBC to read:

3006.4 Machine rooms and machinery spaces. Elevator machine rooms, rooms housing elevator controllers, and machinery spaces shall be enclosed with fire barriers constructed in accordance with Section 707 or horizontal assemblies constructed in accordance with

Section ~~712~~ 711, or both. The fire-resistance rating shall not be less than the required rating of the hoistway enclosure served by the machinery. Openings in the fire barriers shall be protected with assemblies having a fire protection rating not less than that required for the hoistway enclosure doors.

Exceptions:

1. Where machine rooms, rooms housing elevator controllers, and machinery spaces do not abut and have no openings to the hoistway enclosure they serve, the fire barriers constructed in accordance with Section 707 or horizontal assemblies constructed in accordance with Section ~~712~~ 711, or both, shall be permitted to be reduced to a one-hour fire-resistance rating.
2. In buildings four stories or less above grade plane when machine rooms, rooms housing elevator controllers, and machinery rooms do not abut and have no openings to the hoistway enclosure they serve, the machine room, room housing elevator controllers, and machinery spaces are not required to be fire-resistance rated.

D. Add Section 3006.7 to the IBC to read:

3006.7 Machine-room-less designs. Where machine-room-less designs are utilized they shall comply with the provisions of ASME A17.1 and incorporate the following:

1. Where the elevator car-top will be used as a work platform, it shall be equipped with permanently installed guards on all open sides. Guards shall be permitted to be of collapsible design, but otherwise must conform to all applicable requirements of this code for guards.
2. Where the equipment manufacturer's procedures for machinery removal and replacement depend on overhead structural support or lifting points, such supports or lifting points shall be permanently installed at the time of initial equipment installation.
3. Where the structure that the elevator will be located in is required to be fully sprinklered by this code, the hoistway that the elevator machine is located in shall be equipped with a fire suppression system as a machine room in accordance with NFPA 13. Smoke detectors for the automatic initiation of Phase I Emergency Recall Operation, and heat detectors or other approved devices that automatically disconnect the main line power supply to the elevators, shall be installed within the hoistway.

E. Change Section 3008.1 of the IBC to read:

3008.1 General. Where elevators in buildings greater than 420 feet (128 016 mm) in building height are to be used for occupant self-evacuation during fires, all passenger elevators for general public use shall comply with this section.

Delete IBC Sections 3305 and 3305.1.

13VAC5-63-350. Chapter 34 Existing structures.

A. Change Section 3401.1 of the IBC to read:

3401.1 Scope. The provisions of this chapter and the applicable requirements of Chapter 1 shall control the alteration, repair, addition and change of occupancy of existing structures.

B. Delete IBC Sections 3401.2, 3401.3, 3401.4, ~~and 3401.5~~ and 3401.6.

C. Delete IBC Sections 3403, 3404, 3405, and 3406.

D. Change Section 3407.1 of the IBC to read:

3407.1 Standards for replacement glass. In accordance with § 36-99.2 of the Code of Virginia, any replacement glass installed in buildings constructed prior to the first edition of the USBC shall meet the quality and installation standards for glass installed in new buildings as are in effect at the time of installation. In addition, as a requirement of this code, the installation or replacement of glass in buildings constructed under any edition of the USBC shall be as required for new installations.

E. Delete IBC Section 3408.

F. Delete IBC Section 3410.

G. Change Section 3412.2 of the IBC to read:

3412.2 Applicability. When specifically requested by an owner or an owner's agent in structures where there is work involving additions, alterations or changes of occupancy, the provisions in Sections 3412.2.1 through 3412.2.5 shall apply to existing occupancies that will continue to be, or are proposed to be, in Groups A, B, E, F, M, R, S and U. These provisions shall not apply to buildings with occupancies in Group H or I.

H. Add an exception to Section 3412.2.1 of the IBC to read:

Exception: Plumbing, mechanical and electrical systems in buildings undergoing a change of occupancy shall be subject to any applicable requirements of Section 103.3 of this code.

I. Change Section 3412.2.5 of the IBC to read:

3412.2.5 Accessibility requirements. All portions of the buildings proposed for change of occupancy and all alterations to existing buildings shall conform to the applicable accessibility provisions of Section 3411.

J. Add IBC Section 3413 Retrofit Requirements.

K. Add Section 3413.1 to the IBC to read:

3413.1 Scope. In accordance with Section 103.7 and as setout herein, the following buildings are required to be provided with certain fire protection equipment or systems or other retrofitted components.

L. Add Section 3413.2 to the IBC to read:

3413.2 Smoke detectors in colleges and universities. In accordance with Section 36-99.3 of the Code of Virginia, college and university buildings containing dormitories for sleeping purposes shall be provided with battery-powered or AC-powered smoke detector devices installed therein in accordance with this code in effect on July 1, 1982. All public and private college and university dormitories shall have installed such detectors regardless of when the building was constructed. The chief administrative office of the college or university shall obtain a certificate of compliance with the provisions of this subsection from the building official of the locality in which the college or university is located or in the case of state-owned buildings, from the Director of the Virginia Department of General Services. The provisions of this section shall not apply to any dormitory at a state-supported military college or university which is patrolled 24 hours a day by military guards.

M. Add Section 3413.3 to the IBC to read:

3413.3 Smoke detectors in certain juvenile care facilities. In accordance with § 36-99.4 of the Code of Virginia, battery-powered or AC-powered smoke detectors shall be installed in all local and regional detention homes, group homes, and other residential care facilities for children and juveniles which are operated by or under the auspices of the Virginia Department of Juvenile Justice, regardless of when the building was constructed, by July 1, 1986, in accordance with the provisions of this code that were in effect on July 1, 1984. Administrators of such homes and facilities shall be responsible for the installation of the smoke detector devices.

N. Add Section 3413.4 to the IBC to read:

3413.4 Smoke detectors for the deaf and hearing-impaired. In accordance with Section 36-99.5 of the Code of Virginia, smoke detectors providing an effective intensity of not less than 100 candela to warn a deaf or hearing-impaired individual shall be provided, upon request by the occupant to the landlord or proprietor, to any deaf or hearing-impaired occupant of any of the following occupancies, regardless of when constructed:

1. All dormitory buildings arranged for the shelter and sleeping accommodations of more than 20 individuals;
2. All multiple-family dwellings having more than two dwelling units, including all dormitories, boarding and lodging houses arranged for shelter and sleeping accommodations of more than five individuals; or

3. All buildings arranged for use of one-family or two-family dwelling units.

A tenant shall be responsible for the maintenance and operation of the smoke detector in the tenant's unit.

A hotel or motel shall have available no fewer than one such smoke detector for each 70 units or portion thereof, except that this requirement shall not apply to any hotel or motel with fewer than 35 units. The proprietor of the hotel or motel shall post in a conspicuous place at the registration desk or counter a permanent sign stating the availability of smoke detectors for the hearing impaired. Visual detectors shall be provided for all meeting rooms for which an advance request has been made.

O. Add Sections 3413.5, 3413.5.1, and 3413.5.2 to the IBC to read:

3413.5 Assisted living facilities (formerly known as adult care residences or homes for adults). Existing assisted living facilities licensed by the Virginia Department of Social Services shall comply with this section.

3413.5.1 Fire protective signaling system and fire detection system. A fire protective signaling system and an automatic fire detection system meeting the requirements of the USBC, Volume I, 1987 Edition, Third Amendment, shall be installed in assisted living facilities by August 1, 1994.

Exception: Assisted living facilities that are equipped throughout with a fire protective signaling system and an automatic fire detection system.

3413.5.2 Single and multiple station smoke detectors. Battery or AC-powered single and multiple station smoke detectors meeting the requirements of the USBC, Volume I, 1987 Edition, Third Amendment, shall be installed in assisted living facilities by August 1, 1994.

Exception: Assisted living facilities that are equipped throughout with single and multiple station smoke detectors.

P. Add Section 3413.6 to the IBC to read:

3413.6 Smoke detectors in buildings containing dwelling units. AC-powered smoke detectors with battery backup or an equivalent device shall be required to be installed to replace a defective or inoperative battery-powered smoke detector located in buildings containing one or more dwelling units or rooming houses offering to rent overnight sleeping accommodations, when it is determined by the building official that the responsible party of such building or dwelling unit fails to maintain battery-powered smoke detectors in working condition.

Q. Add Section 3413.7 to the IBC to read:

3413.7 Fire suppression, fire alarm and fire detection systems in nursing homes and facilities. Fire suppression systems as required by the edition of this code in effect on

October 1, 1990, shall be installed in all nursing facilities licensed by the Virginia Department of Health by January 1, 1993, regardless of when such facilities or institutions were constructed. Units consisting of certified long-term care beds located on the ground floor of general hospitals shall be exempt from the requirements of this section.

Fire alarm or fire detector systems, or both, as required by the edition of this code in effect on October 1, 1990, shall be installed in all nursing homes and nursing facilities licensed by the Virginia Department of Health by August 1, 1994.

R. Add Section 3413.8 to the IBC to read:

3413.8 Fire suppression systems in hospitals. Fire suppression systems shall be installed in all hospitals licensed by the Virginia Department of Health as required by the edition of this code in effect on October 1, 1995, regardless of when such facilities were constructed.

S. Add Section 3413.9 to the IBC to read:

3413.9 Identification of ~~handicapped~~ disabled parking spaces by above grade signs signage. All parking spaces reserved for the use of ~~handicapped~~ persons with disabilities shall be identified by above grade signs, regardless of whether identification of such spaces by above grade signs was required when any particular space was reserved for the use of ~~handicapped~~ persons with disabilities. A sign or symbol painted or otherwise displayed on the pavement of a parking space shall not constitute an above grade sign. Any parking space not identified by an above grade sign shall not be a parking space reserved for the ~~handicapped~~ disabled within the meaning of this section. All above grade ~~handicapped~~ disabled parking space signs shall have the bottom edge of the sign no lower than four feet (1219 mm) nor higher than seven feet (2133 mm) above the parking surface. Such signs shall be designed and constructed in accordance with the provisions of Chapter 11 of this code. All disabled parking signs shall include the following language: PENALTY, \$100-500 Fine, TOW-AWAY ZONE. Such language may be placed on a separate sign and attached below existing above grade disabled parking signs, provided that the bottom edge of the attached sign is no lower than four feet above the parking surface.

T. Add Section 3413.10 to the IBC to read:

3413.10 Smoke detectors in hotels and motels. Smoke detectors shall be installed in hotels and motels as required by the edition of VR 394-01-22, USBC, Volume II, in effect on March 1, 1990, by the dates indicated, regardless of when constructed.

U. Add Section 3413.11 to the IBC to read:

3413.11 Sprinkler systems in hotel and motels. By September 1, 1997, an automatic sprinkler system shall be installed in hotels and motels as required by the edition of VR 394-01-22, USBC, Volume II, in effect on March 1, 1990, regardless of when constructed.

V. Add Section 3413.12 to the IBC to read:

3413.12 Fire suppression systems in dormitories. An automatic fire suppression system shall be provided throughout all buildings having a Group R-2 fire area which are more than 75 feet (22,860 mm) or six stories above the lowest level of exit discharge and which are used, in whole or in part, as a dormitory to house students by any public or private institution of higher education, regardless of when such buildings were constructed, in accordance with the edition of this code in effect on August 20, 1997, and the requirements for sprinkler systems under the edition of the NFPA 13 standard referenced by that code. The automatic fire suppression system shall be installed by September 1, 1999. The chief administrative office of the college or university shall obtain a certificate of compliance from the building official of the locality in which the college or university is located or in the case of state-owned buildings, from the Director of the Virginia Department of General Services.

Exceptions:

1. Buildings equipped with an automatic fire suppression system in accordance with Section 903.3.1.1 or the 1983 or later editions of NFPA 13.
2. Any dormitory at a state-supported military college or university which is patrolled 24 hours a day by military guards.
3. Application of the requirements of this section shall be modified in accordance with the following:

3.1. Building systems, equipment or components other than the fire suppression system shall not be required to be added or upgraded except as necessary for the installation of the fire suppression system and shall only be required to be added or upgraded where the installation of the fire suppression system creates an unsafe condition.

3.2. Residential sprinklers shall be used in all sleeping rooms. Other sprinklers shall be quick response or residential unless deemed unsuitable for a space. Standard response sprinklers shall be used in elevator hoist ways and machine rooms.

3.3. Sprinklers shall not be required in wardrobes in sleeping rooms that are considered part of the building construction or in closets in sleeping rooms, when such wardrobes or closets (i) do not exceed 24 square feet (2.23 m²) in area, (ii) have the smallest dimension less than 36 inches (914 mm), and (iii) comply with all of the following:

3.3.1. A single station smoke detector monitored by the building fire alarm system is installed in the room containing the wardrobe or closet that will activate the general alarm for the building if the single station smoke detector is not cleared within five minutes after activation.

3.3.2. The minimum number of sprinklers required for calculating the hydraulic demand of the system for the room shall be increased by two and the

two additional sprinklers shall be corridor sprinklers where the wardrobe or closet is used to divide the room. Rooms divided by a wardrobe or closet shall be considered one room for the purpose of this requirement.

3.3.3. The ceiling of the wardrobe, closet or room shall have a fire resistance rating of not less than 1/2 hour.

3.4. Not more than one sprinkler shall be required in bathrooms within sleeping rooms or suites having a floor area between 55 square feet (5.12 m²) and 120 square feet (11.16 m²) provided the sprinkler is located to protect the lavatory area and the plumbing fixtures are of a noncombustible material.

3.5. Existing standpipe residual pressure shall be permitted to be reduced when the standpipe serves as the water supply for the fire suppression system provided the water supply requirements of NFPA 13-94 are met.

3.6. Limited service controllers shall be permitted for fire pumps when used in accordance with their listing.

3.7. Where a standby power system is required, a source of power in accordance with Section 701-11 (d) or 701-11 (e) of NFPA 70—96 shall be permitted.

W. Add Section 3413.13 to the IBC to read:

3413.13 Fire extinguishers and smoke detectors in SRCF's. SRCF's shall be provided with at least one approved type ABC portable fire extinguisher with a minimum rating of 2A10BC installed in each kitchen. In addition, SRCF's shall provide at least one approved and properly installed battery operated smoke detector outside of each sleeping area in the vicinity of bedrooms and bedroom hallways and on each additional floor.

X. Add Section 3413.14 to the IBC to read:

3413.14 Smoke detectors in adult day care centers. Battery-powered or AC-powered smoke detector devices shall be installed in all adult day care centers licensed by the Virginia Department of Social Services, regardless of when the building was constructed. The location and installation of the smoke detectors shall be determined by the provisions of this code in effect on October 1, 1990. The licensee shall obtain a certificate of compliance from the building official of the locality in which the center is located, or in the case of state-owned buildings, from the Director of the Virginia Department of General Services.

Y. Add Section 3413.15 to the IBC to read:

3413.15 Posting of occupant load. Every room or space that is an assembly occupancy, and where the occupant load of that room or space is 50 or more, shall have the occupant load of the room or space as determined by the building official posted in a conspicuous place, near the main exit or exit access doorway from the room or space. Posted signs

shall be of an approved legible permanent design and shall be maintained by the owner or authorized agent.

Z. Add Section 3413.16 to the IBC to read:

3413.16 ALFSTs. Existing ALFSTs, regardless of when constructed, shall by October 1, 2011, meet the applicable requirements of API 653 and TFI RMIP for suitability for service and inspections and shall provide a secondary containment system complying with Section 425.3.

13VAC5-63-360. Chapter 35 Referenced standards.

Change the referenced standards in Chapter 35 of the IBC as follows (standards not shown remain the same):

Standard reference number	Title	Referenced in code section number
ASTM E329-02	Standard Specification for Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction	1703.1, 1703.1.3
API 650-09	Welded Steel Tanks for Oil Storage	425.2 <u>426.2</u>
API 653-09	Tank Inspection, Repair, Alteration and Reconstruction	425.4 <u>426.4</u> , 425.5 <u>426.5</u> , 3413.16
ASME A17.1/CSA B44- 2007 <u>07</u>	Safety Code for Elevators and Escalators with 2008 and 2009 Addenda	907.3.3, 911.1.5, 1007.4, 1607.8.1 <u>1607.9.1</u> , 1613.6.5 , 3001.2, 3001.4, 3002.5, 3003.2, 3007.1, 3008.3 , 3008.12 , 3008.14.1 <u>3007.2</u> , <u>3008.2</u> , <u>3008.2.1</u> , <u>3008.7.6</u> , <u>3008.8.1</u> , 3411.8.2
NFPA 704-07	Identification of the Hazards of Materials for Emergency Response	425.2
TFI RMIP-09	Aboveground Storage Tanks Containing Liquid Fertilizer, Recommended Mechanical Integrity Practices	425.2 <u>426.2</u> , 425.4 <u>426.4</u> , 425.5 <u>426.5</u> , 3413.16
UL 2034-08	Standard for Single and Multiple-station Carbon Monoxide Alarms	908.7.1

13VAC5-63-365. Appendix E Supplementary accessibility requirements.

Appendix E of the IBC shall be part of this code.

13VAC5-63-370. Appendix F Rodent proofing.

The following provisions of Appendix F of the IBC are part of this code:

F101.2 Foundation wall ventilation openings.

F101.6 Pier and wood construction. (Includes all provisions.)

13VAC5-63-380. Appendix H Signs.

The following provisions of Appendix H of the IBC are part of this code:

H101.2 Signs exempt from permits.

H102 Definitions. (Includes all definitions.)

H103 Location. (Includes Section H103.1.)

H105 through H114. (Includes all provisions.)

13VAC5-63-390. Appendix I Patio covers.

~~The following provisions from Appendix I of the IBC are part of this code:~~

~~H101 through H104 (Includes all provisions.)~~ Appendix I of the IBC shall be part of this code.

Part II – Rehabilitation (VRC)

13VAC5-63-400. Chapter 1 Administration; Section 101 General.

A. Section 101.1 Short title. The Virginia Uniform Statewide Building Code, Part II, Rehabilitation, may be cited as the Virginia Rehabilitation Code.

B. Section 101.2 Incorporation by reference. Chapters 2 – 15 16 of the ~~2009~~ 2012 International Existing Building Code, published by the International Code Council, Inc., are adopted and incorporated by reference to be an enforceable part of the Virginia Rehabilitation Code. The term “IEBC” means the ~~2009~~ 2012 International Existing Building Code, published by the International Code Council, Inc. Any codes and standards referenced in the IEBC are also considered to be part of the incorporation by reference, except that such codes and standards are used only to the prescribed extent of each such reference.

C. Section 101.3 Numbering system. A dual numbering system is used in the Virginia Rehabilitation Code to correlate the numbering system of the Virginia Administrative Code with the numbering system of the IEBC. IEBC numbering system designations are provided in the catch-lines of the Virginia Administrative Code sections and cross references between sections or chapters of the Virginia Rehabilitation Code use only the IEBC numbering system designations. The term “chapter” is used in the context of the numbering system of the IEBC and may mean a chapter in the Virginia Rehabilitation Code, a chapter in the IEBC or a chapter in a referenced code or standard, depending on the context of the use of the term. The

term “chapter” is not used to designate a chapter of the Virginia Administrative Code, unless clearly indicated.

D. Section 101.4 Arrangement of code provisions. The Virginia Rehabilitation Code is comprised of the combination of (i) the provisions of Chapter 1, Administration, which are established herein, (ii) Chapters 2 – ~~45~~ 16 of the IEBC, which are incorporated by reference in Section 101.2, and (iii) the changes to the text of the incorporated chapters of the IEBC that are specifically identified. The terminology “changes to the text of the incorporated chapters of the IEBC that are specifically identified” shall also be referred to as the “state amendments to the IEBC.” Such state amendments to the IEBC are set out using corresponding chapter and section numbers of the IEBC numbering system. In addition, since Chapter 1 of the IEBC is not incorporated as part of the Virginia Rehabilitation Code, any reference to a provision of Chapter 1 of the IEBC in the provisions of Chapters 2 - ~~45~~ 16 of the IEBC is generally invalid. However, where the purpose of such a reference would clearly correspond to a provision of Chapter 1 established herein, then the reference may be construed to be a valid reference to such corresponding Chapter 1 provision.

E. Section 101.5 Use of terminology and notes. The term “this code,” or “the code,” where used in the provisions of Chapter 1, in Chapters 2 - ~~45~~ 16 of the IEBC or in the state amendments to the IEBC means the Virginia Rehabilitation Code, unless the context clearly indicates otherwise. The term “this code,” or “the code,” where used in a code or standard referenced in the IEBC means that code or standard, unless the context clearly indicates otherwise. The term “USBC” where used in this code means Part I of the Virginia Uniform Statewide Building Code, also known as the “Virginia Construction Code,” unless the context clearly indicates otherwise. In addition, where the phrase “of the International Building Code under which the building was constructed” is used in the IEBC, it shall be construed to mean the USBC or other code that was in effect when the building was built. Further, the use of notes in Chapter 1 is to provide information only and shall not be construed as changing the meaning of any code provision. Notes in the IEBC, in the codes and standards referenced in the IEBC and in the state amendments to the IEBC may modify the content of a related provision and shall be considered to be a valid part of the provision, unless the context clearly indicates otherwise.

F. Section 101.6 Order of precedence. The provisions of Chapter 1 of this code supersede any conflicting provisions of Chapters 2 - ~~45~~ 16 of the IEBC and any conflicting provisions of the codes and standards referenced in the IEBC. In addition, the state amendments to the IEBC supersede any conflicting provisions of Chapters 2 - ~~45~~ 16 of the IEBC and any conflicting provisions of the codes and standards referenced in the IEBC. Further, the provisions of Chapters 2 – ~~45~~ 16 of the IEBC supersede any conflicting provisions of the codes and standards referenced in the IEBC.

G. Section 101.7 Administrative provisions. The provisions of Chapter 1 establish administrative requirements, which include but are not limited to provisions relating to the scope and enforcement of the code. Any provisions of Chapters 2 – ~~45~~ 16 of the IEBC or any provisions of the codes and standards referenced in the IEBC that address the same subject matter to a lesser or greater extent are deleted and replaced by the provisions of Chapter 1. Further, any administrative requirements contained in the state amendments to the IEBC shall be given the same precedence as the provisions of Chapter 1. Notwithstanding the above,

where administrative requirements of Chapters 2 – 15 16 of the IEBC or of the codes and standards referenced in the IEBC are specifically identified as valid administrative requirements in Chapter 1 of this code or in the state amendments to the IEBC, then such requirements are not deleted and replaced.

Note: The purpose of this provision is to eliminate overlap, conflicts and duplication by providing a single standard for administrative, procedural and enforcement requirements of this code.

H. Section 101.8 Definitions. The definitions of terms used in this code are contained in Chapter 2 along with specific provisions addressing the use of definitions. Terms may be defined in other chapters or provisions of the code and such definitions are also valid.

13VAC5-63-410. Section 102 Purpose and scope.

A. Section 102.1 Purpose. In accordance with § 36-99.01 of the Code of Virginia, the General Assembly of Virginia has declared that (i) there is an urgent need to improve the housing conditions of low and moderate income individuals and families, many of whom live in substandard housing, particularly in the older cities of the Commonwealth; (ii) there are large numbers of older residential buildings in the Commonwealth, both occupied and vacant, which are in urgent need of rehabilitation and must be rehabilitated if the state's citizens are to be housed in decent, sound, and sanitary conditions; and (iii) the application of those building code requirements currently in force to housing rehabilitation has sometimes led to the imposition of costly and time-consuming requirements that result in a significant reduction in the amount of rehabilitation activity taking place.

The General Assembly further declares that (i) there is an urgent need to improve the existing condition of many of the Commonwealth's stock of commercial properties, particularly in older cities; (ii) there are large numbers of older commercial buildings in the Commonwealth, both occupied and vacant, that are in urgent need of rehabilitation and that must be rehabilitated if the citizens of the Commonwealth are to be provided with decent, sound and sanitary work spaces; and (iii) the application of the existing building code to such rehabilitation has sometimes led to the imposition of costly and time-consuming requirements that result in a significant reduction in the amount of rehabilitation activity taking place.

B. Section 102.2 Scope. In accordance with Section 103.6 of the USBC, this code shall be an acceptable alternative to compliance with the Virginia Construction Code for the rehabilitation of existing buildings and structures.

13VAC5-63-420. Section 103 Application of code.

A. Section 103.1 General. The provisions of this code shall control the rehabilitation, alteration, repair, addition and change of occupancy of existing buildings and structures when this code is chosen as an alternative to compliance with the Virginia Construction Code. All administrative provisions of the Virginia Construction Code, including but not limited to, requirements for permits, inspections and approvals by the local building department, provisions for appeals from decisions of the local building department and the issuance of modifications, are applicable to the use of this code, except where this code sets out differing

requirements. Where there is a conflict between a general requirement and a specific requirement in the IEBC, the specific requirement shall govern.

Exception: ~~the~~ The use of this code shall not be permitted for change of occupancy involving Group I-2 or Group I-3.

B. Section 103.1.1 Use of performance code. Compliance with the provisions of a nationally recognized performance code when approved as a modification shall be considered to constitute compliance with this code. All documents submitted as part of such consideration shall be retained in the permanent records of the local building department.

C. Section 103.1.2 Preliminary meeting. When requested by a prospective permit applicant or when determined necessary by the code official, the code official shall meet with the prospective permit applicant prior to the application for a permit to discuss plans for the proposed work or change of occupancy in order to establish the specific applicability of the provisions of this code.

D. Section 103.2 Requirements relating to maintenance. Any requirements of the IEBC requiring the maintenance of existing buildings or structures are invalid.

Note: Requirements for the maintenance of existing buildings and structures and for unsafe conditions are contained in Part III of the Virginia Uniform Statewide Building Code, also known as the "Virginia Maintenance Code."

E. Section 103.3 Use of Appendix A. Appendix A of the IEBC provides guidelines for the seismic retrofit of existing buildings. The use of this appendix is not mandatory but shall be permitted to be utilized at the option of an owner, the owner's agent or the RDP involved in a rehabilitation project. However, in no case shall the use of Appendix A be construed to authorize the lowering of existing levels of health or safety in buildings or structures being rehabilitated.

F. Section 103.4 Use of Appendix B. Appendix B of the IEBC provides supplementary accessibility requirements for existing buildings and facilities. All applicable requirements of Appendix B shall be met in buildings and structures being rehabilitated.

G. Section 103.5 Use of Resource A. Resource A of the IEBC provides guidelines for the evaluation of fire resistance ratings of archaic materials and may be used in conjunction with rehabilitation projects.

13VAC5-63-430. Chapter 2 Definitions.

A. Change Section 201.3 of the IEBC to read:

201.3 Terms defined in other codes. Where terms are not defined in this code and are defined in the other International Codes, such terms shall have the meanings ascribed to them in those codes, except that terms that are not defined in this code and that are defined in the Virginia Construction Code shall take precedence over other definitions.

B. Change the following definition in Section 202 of the IEBC to read:

Existing building. A building for which a legal certificate of occupancy has been issued under any edition of the USBC and that has been occupied for its intended use; or, a building built prior to the initial edition of the USBC.

13VAC5-63-434. Chapter ~~7~~ 8 Alterations -- Level 2.

A. Change Exception 2 of Section ~~705.2~~ 805.2 to read:

2. Means of egress conforming to the requirements of the building code under which the building was constructed shall be considered compliant means of egress.

B. Change Item 7 of Section ~~705.3.1.1~~ 805.3.1.1 of the IEBC to read:

7. In Group R-2, H-4, H-5 and I occupancies and in rooming houses and childcare centers, a single exit is permitted in a one-story building with a maximum occupant load of 10 and the exit access travel distance does not exceed 75 feet (22 860 mm). In dwelling units within Group R-2 buildings, an occupant load of 12 shall be permitted to be substituted for the occupant load established above and, in addition, staff of such family day homes shall not be counted for the purposes of establishing occupant loads.

13VAC5-63-438. Chapter ~~11~~ 12 Historic buildings.

Change Section ~~1101.2~~ 1201.2 of the IEBC to read:

~~1101.2~~ 1201.2 Report. The code official shall be permitted to require that an historic building undergoing repair, alteration or change of occupancy be investigated and evaluated by an RDP or other qualified person or agency as a condition of determining compliance with this code.

13VAC5-63-440. Chapter 13 Performance compliance methods.

A. Change Section ~~1301.2~~ 1401.2 of the IEBC to read:

~~1301.2~~ 1401.2 Applicability. Work involving rehabilitation, additions, alterations or changes of occupancy shall be made to conform to the requirements of this chapter or the provisions of Chapters 4 5 through ~~12~~ 13. The provisions in Sections ~~1301.2.1~~ 1401.2.1 through ~~1301.2.5~~ 1401.2.5 shall apply to existing occupancies that will continue to be, or are proposed to be, in Groups A, B, E, F, M, R, S and U. These provisions shall not apply to buildings with occupancies in Group H or I.

B. Add an exception to Section ~~1301.2.1~~ 1401.2.1 of the IEBC to read:

Exception: Plumbing, mechanical and electrical systems in buildings undergoing a change of occupancy shall be subject to any applicable requirements of Section 103.3 of the Virginia Construction Code.

C. Change Section ~~1301.2.5~~ 1401.2.5 of the IEBC to read:

~~1301.2.5~~ 1401.2.5 Accessibility requirements. All portions of the buildings proposed for change of occupancy and all alterations to existing buildings shall conform to the applicable accessibility provisions of Section 310.

Part III – Maintenance (VMC)

13VAC5-63-450. Chapter 1 Administration; Section 101 General.

A. Section 101.1 Short title. The Virginia Uniform Statewide Building Code, Part III, Maintenance, may be cited as the Virginia Maintenance Code.

B. Section 101.2 Incorporation by reference. Chapters 2 - 8 of the ~~2009~~ 2012 International Property Maintenance Code, published by the International Code Council, Inc., are adopted and incorporated by reference to be an enforceable part of the Virginia Maintenance Code. The term “IPMC” means the ~~2009~~ 2012 International Property Maintenance Code, published by the International Code Council, Inc. Any codes and standards referenced in the IPMC are also considered to be part of the incorporation by reference, except that such codes and standards are used only to the prescribed extent of each such reference.

C. Section 101.3 Numbering system. A dual numbering system is used in the Virginia Maintenance Code to correlate the numbering system of the Virginia Administrative Code with the numbering system of the IPMC. IPMC numbering system designations are provided in the catch-lines of the Virginia Administrative Code sections and cross references between sections or chapters of the Virginia Maintenance Code use only the IPMC numbering system designations. The term “chapter” is used in the context of the numbering system of the IPMC and may mean a chapter in the Virginia Maintenance Code, a chapter in the IPMC or a chapter in a referenced code or standard, depending on the context of the use of the term. The term “chapter” is not used to designate a chapter of the Virginia Administrative Code, unless clearly indicated.

D. Section 101.4 Arrangement of code provisions. The Virginia Maintenance Code is comprised of the combination of (i) the provisions of Chapter 1, Administration, which are established herein, (ii) Chapters 2 - 8 of the IPMC, which are incorporated by reference in Section 101.2, and (iii) the changes to the text of the incorporated chapters of the IPMC which are specifically identified. The terminology “changes to the text of the incorporated chapters of the IPMC which are specifically identified” shall also be referred to as the “state amendments to the IPMC.” Such state amendments to the IPMC are set out using corresponding chapter and section numbers of the IPMC numbering system. In addition, since Chapter 1 of the IPMC is not incorporated as part of the Virginia Maintenance Code, any reference to a provision of Chapter 1 of the IPMC in the provisions of Chapters 2 - 8 of the IPMC is generally invalid. However, where the purpose of such a reference would clearly correspond to a provision of Chapter 1 established herein, then the reference may be construed to be a valid reference to such corresponding Chapter 1 provision.

E. Section 101.5 Use of terminology and notes. The term “this code,” or “the code,” where used in the provisions of Chapter 1, in Chapters 2 - 8 of the IPMC or in the state amendments

to the IPMC means the Virginia Maintenance Code, unless the context clearly indicates otherwise. The term "this code," or "the code," where used in a code or standard referenced in the IPMC means that code or standard, unless the context clearly indicates otherwise. The term "USBC" where used in this code means Part I of the Virginia Uniform Statewide Building Code, also known as the "Virginia Construction Code," unless the context clearly indicates otherwise. In addition, the use of notes in Chapter 1 is to provide information only and shall not be construed as changing the meaning of any code provision. Notes in the IPMC, in the codes and standards referenced in the IPMC and in the state amendments to the IPMC may modify the content of a related provision and shall be considered to be a valid part of the provision, unless the context clearly indicates otherwise.

F. Section 101.6 Order of precedence. The provisions of Chapter 1 of this code supersede any conflicting provisions of Chapters 2 - 8 of the IPMC and any conflicting provisions of the codes and standards referenced in the IPMC. In addition, the state amendments to the IPMC supersede any conflicting provisions of Chapters 2 - 8 of the IPMC and any conflicting provisions of the codes and standards referenced in the IPMC. Further, the provisions of Chapters 2 - 8 of the IPMC supersede any conflicting provisions of the codes and standards referenced in the IPMC.

G. Section 101.7 Administrative provisions. The provisions of Chapter 1 establish administrative requirements, which include but are not limited to provisions relating to the scope of the code, enforcement, fees, permits, inspections and disputes. Any provisions of Chapters 2 - 8 of the IPMC or any provisions of the codes and standards referenced in the IPMC which address the same subject matter to a lesser or greater extent are deleted and replaced by the provisions of Chapter 1. Further, any administrative requirements contained in the state amendments to the IPMC shall be given the same precedence as the provisions of Chapter 1. Notwithstanding the above, where administrative requirements of Chapters 2 - 8 of the IPMC or of the codes and standards referenced in the IPMC are specifically identified as valid administrative requirements in Chapter 1 of this code or in the state amendments to the IPMC, then such requirements are not deleted and replaced.

Note: The purpose of this provision is to eliminate overlap, conflicts and duplication by providing a single standard for administrative, procedural and enforcement requirements of this code.

H. Section 101.8 Definitions. The definitions of terms used in this code are contained in Chapter 2 along with specific provisions addressing the use of definitions. Terms may be defined in other chapters or provisions of the code and such definitions are also valid.

Note: The order of precedence outlined in Section 101.6 may be determinative in establishing how to apply the definitions in the IPMC and in the referenced codes and standards.

13VAC5-63-460. Section 102 Purpose and scope.

A. Section 102.1 Purpose. In accordance with § 36-103 of the Code of Virginia, the Virginia Board of Housing and Community Development may adopt and promulgate as part of the Virginia Uniform Statewide Building Code, building regulations that facilitate the maintenance, rehabilitation, development and reuse of existing buildings at the least possible

cost to ensure the protection of the public health, safety and welfare. Further, in accordance with § 36-99 of the Code of Virginia, the purpose of this code is to protect the health, safety and welfare of the residents of the Commonwealth of Virginia, provided that buildings and structures should be permitted to be maintained at the least possible cost consistent with recognized standards of health, safety, energy conservation and water conservation, including provisions necessary to prevent overcrowding, rodent or insect infestation, and garbage accumulation; and barrier-free provisions for the physically handicapped and aged.

B. Section 102.2 Scope. In accordance with § 36-98 of the Code of Virginia, the Virginia Maintenance Code shall supersede the building codes and regulations of the counties, municipalities and other political subdivisions and state agencies.

C. Section 102.3 Exemptions. This code shall not regulate those buildings and structures specifically exempt from the Virginia Construction Code, except that existing industrialized buildings and manufactured homes shall not be exempt from this code.

13VAC5-63-470. Section 103 Application of code.

A. Section 103.1 General. This code prescribes regulations for the maintenance of all existing buildings and structures and associated equipment, including regulations for unsafe buildings and structures.

B. Section 103.2 Maintenance requirements. Buildings and structures shall be maintained and kept in good repair in accordance with the requirements of this code and when applicable in accordance with the USBC under which such building or structure was constructed. No provision of this code shall require alterations to be made to an existing building or structure or to equipment unless conditions are present which meet the definition of an unsafe structure or a structure unfit for human occupancy.

C. 103.2.1 Maintenance of nonrequired fire protection systems. Nonrequired fire protection systems shall be maintained to function as originally installed. If any such systems are to be reduced in function or discontinued, approval shall be obtained from the building official in accordance with Section 103.8.1 of the Virginia Construction Code.

D. Section 103.3 Continued approval. Notwithstanding any provision of this code to the contrary, alterations shall not be required to be made to existing buildings or structures which are occupied in accordance with a certificate of occupancy issued under any edition of the USBC.

E. Section 103.4 Rental Inspections. In accordance with § 36-105.1:1 of the Code of Virginia, these provisions are applicable to rental inspection programs. For purposes of this section:

“Dwelling unit” means a building or structure or part thereof that is used for a home or residence by one or more persons who maintain a household.

“Owner” means the person shown on the current real estate assessment books or current real estate assessment records.

"Residential rental dwelling unit" means a dwelling unit that is leased or rented to one or more tenants. However, a dwelling unit occupied in part by the owner thereof shall not be construed to be a residential rental dwelling unit unless a tenant occupies a part of the dwelling unit that has its own cooking and sleeping areas, and a bathroom, unless otherwise provided in the zoning ordinance by the local governing body.

The local governing body may adopt an ordinance to inspect residential rental dwelling units for compliance with this code and to promote safe, decent and sanitary housing for its citizens, in accordance with the following:

1. Except as provided for in subdivision 3 of this subsection, the dwelling units shall be located in a rental inspection district established by the local governing body in accordance with this section; and
2. The rental inspection district is based upon a finding by the local governing body that (i) there is a need to protect the public health, safety and welfare of the occupants of dwelling units inside the designated rental inspection district; (ii) the residential rental dwelling units within the designated rental inspection district are either (a) blighted or in the process of deteriorating or (b) the residential rental dwelling units are in the need of inspection by the building department to prevent deterioration, taking into account the number, age and condition of residential dwelling rental units inside the proposed rental inspection district; and (iii) the inspection of residential rental dwelling units inside the proposed rental inspection district is necessary to maintain safe, decent and sanitary living conditions for tenants and other residents living in the proposed rental inspection district. Nothing in this section shall be construed to authorize a one of more locality-wide rental inspection ~~district~~ districts and a local governing body shall limit the boundaries of the proposed rental inspection ~~district~~ districts to such areas of the locality that meet the criteria set out in this subsection; or
3. An individual residential rental dwelling unit outside of a designated rental inspection district is made subject to the rental inspection ordinance based upon a separate finding for each individual dwelling unit by the local governing body that (i) there is a need to protect the public health, welfare and safety of the occupants of that individual dwelling unit; (ii) the individual dwelling unit is either (a) blighted or (b) in the process of deteriorating; or (iii) there is evidence of violations of this code that affect the safe, decent and sanitary living conditions for tenants living in such individual dwelling unit.

For purposes of this section, the local governing body may designate a local government agency other than the building department to perform all or part of the duties contained in the enforcement authority granted to the building department by this section.

Before adopting a rental inspection ordinance and establishing a rental inspection district or an amendment to either, the governing body of the locality shall hold a public hearing on the proposed ordinance. Notice of the hearing shall be published once a week for two successive weeks in a newspaper published or having general circulation in the locality.

Upon adoption by the local governing body of a rental inspection ordinance, the building department shall make reasonable efforts to notify owners of residential rental dwelling units

in the designated rental inspection district, or their designated managing agents, and to any individual dwelling units subject to the rental inspection ordinance, not located in a rental inspection district, of the adoption of such ordinance, and provide information and an explanation of the rental inspection ordinance and the responsibilities of the owner thereunder.

The rental inspection ordinance may include a provision that requires the owners of dwelling units in a rental inspection district to notify the building department in writing if the dwelling unit of the owner is used for residential rental purposes. The building department may develop a form for such purposes. The rental inspection ordinance shall not include a registration requirement or a fee of any kind associated with the written notification pursuant to this subdivision. A rental inspection ordinance may not require that the written notification from the owner of a dwelling unit subject to a rental inspection ordinance be provided to the building department in less than 60 days after the adoption of a rental inspection ordinance. However, there shall be no penalty for the failure of an owner of a residential rental dwelling unit to comply with the provisions of this subsection, unless and until the building department provides personal or written notice to the property owner, as provided in this section. In any event, the sole penalty for the willful failure of an owner of a dwelling unit who is using the dwelling unit for residential rental purposes to comply with the written notification requirement shall be a civil penalty of up to \$50. For purposes of this subsection, notice sent by regular first-class mail to the last known address of the owner as shown on the current real estate tax assessment books or current real estate tax assessment records shall be deemed compliance with this requirement.

Upon establishment of a rental inspection district in accordance with this section, the building department may, in conjunction with the written notifications as provided for above, proceed to inspect dwelling units in the designated rental inspection district to determine if the dwelling units are being used as a residential rental property and for compliance with the provisions of this code that affect the safe, decent and sanitary living conditions for the tenants of such property.

If a multifamily development has more than 10 dwelling units, in the initial and periodic inspections, the building department shall inspect only a sampling of dwelling units, of not less than two and not more than 10% of the dwelling units, of a multifamily development, that includes all of the multifamily buildings that are part of that multifamily development. In no event, however, shall the building department charge a fee authorized by this section for inspection of more than 10 dwelling units. If the building department determines upon inspection of the sampling of dwelling units that there are violations of this code that affect the safe, decent and sanitary living conditions for the tenants of such multifamily development, the building department may inspect as many dwelling units as necessary to enforce these provisions, in which case, the fee shall be based upon a charge per dwelling unit inspected, as otherwise provided in the fee schedule established pursuant to this section.

Upon the initial or periodic inspection of a residential rental dwelling unit subject to a rental inspection ordinance, the building department has the authority under these provisions to require the owner of the dwelling unit to submit to such follow-up inspections of the dwelling unit as the building department deems necessary, until such time as the dwelling unit is

brought into compliance with the provisions of this code that affect the safe, decent and sanitary living conditions for the tenants.

Except as provided for above, following the initial inspection of a residential rental dwelling unit subject to a rental inspection ordinance, the building department may inspect any residential rental dwelling unit in a rental inspection district, that is not otherwise exempted in accordance with this section, no more than once each calendar year.

Upon the initial or periodic inspection of a residential rental dwelling unit subject to a rental inspection ordinance for compliance with these provisions, provided that there are no violations of this code that affect the safe, decent and sanitary living conditions for the tenants of such residential rental dwelling unit, the building department shall provide, to the owner of such residential rental dwelling unit, an exemption from the rental inspection ordinance for a minimum of four years. Upon the sale of a residential rental dwelling unit, the building department may perform a periodic inspection as provided above, subsequent to such sale. If a residential rental dwelling unit has been issued a certificate of occupancy within the last four years, an exemption shall be granted for a minimum period of four years from the date of the issuance of the certificate of occupancy by the building department. If the residential rental dwelling unit becomes in violation of this code during the exemption period, the building department may revoke the exemption previously granted under this section.

A local governing body may establish a fee schedule for enforcement of these provisions, which includes a per dwelling unit fee for the initial inspections, follow-up inspections and periodic inspections under this section.

The provisions of this section shall not in any way alter the rights and obligations of landlords and tenants pursuant to the applicable provisions of Chapter 13 (§ 55-217 et seq.) or Chapter 13.2 (§ 55-248.2 et seq.) of Title 55 of the Code of Virginia.

The provisions of this section shall not alter the duties or responsibilities of the local building department under § 36-105 of the Code of Virginia to enforce the USBC.

Unless otherwise provided for in § 36-105.1:1 of the Code of Virginia, penalties for violation of this section shall be the same as the penalties provided for violations of other sections of the USBC.

13VAC5-63-480. Section 104 Enforcement, generally.

A. Section 104.1 Scope of enforcement. This section establishes the requirements for enforcement of this code in accordance with § 36-105 of the Code of Virginia. The local governing body may also inspect and enforce the provisions of the USBC for existing buildings and structures, whether occupied or not. Such inspection and enforcement shall be carried out by an agency or department designated by the local governing body.

If the local building department receives a complaint that a violation of this code exists that is an immediate and imminent threat to the health or safety of the owner ~~or~~ tenant or occupants of a residential dwelling unit any building or structure, or a or the owner, occupant or tenant of any nearby residential dwelling unit building or structure, and the owner ~~or~~ occupant or

tenant of the ~~residential dwelling unit~~ building or structure that is the subject of the complaint has refused to allow the code official or his agent to have access to the subject ~~dwelling building or structure~~, the code official or his agent may present sworn testimony to a magistrate or court of competent jurisdiction and request that the magistrate or court grant the code official or his agent an inspection warrant to enable the code official or his agent to enter the subject ~~dwelling building or structure~~ for the purpose of determining whether violations of this code exist. The code official or his agent shall make a reasonable effort to obtain consent from the owner ~~or, occupant or~~ tenant of the subject ~~dwelling building or structure~~ prior to seeking the issuance of an inspection warrant under this section.

Note: Generally, official action must be taken by the local government to enforce the Virginia Maintenance Code. Consultation with the legal counsel of the jurisdiction when initiating or changing such action is advised.

B. Section 104.1.1 Transfer of ownership. In accordance with § 36-105 of the Code of Virginia, if the local building department has initiated an enforcement action against the owner of a building or structure and such owner subsequently transfers the ownership of the building or structure to an entity in which the owner holds an ownership interest greater than 50%, the pending enforcement action shall continue to be enforced against the owner.

C. Section 104.2 Fees. In accordance with § 36-105 of the Code of Virginia, fees may be levied by the local governing body in order to defray the cost of enforcement and appeals.

D. Section 104.3 State buildings. In accordance with § 36-98.1 of the Code of Virginia, this code shall be applicable to state-owned buildings and structures. Acting through the Division of Engineering and Buildings, the Department of General Services shall function as the building official for state-owned buildings.

E. Section 104.3.1 Certification of state enforcement personnel. State enforcement personnel shall comply with the applicable requirements of Sections 104.4.2 through 104.4.4 for certification, periodic maintenance training, and continuing education.

F. Section 104.4 Local enforcing agency. In jurisdictions enforcing this code, the local governing body shall designate the agency within the local government responsible for such enforcement and appoint a code official. The local governing body may also utilize technical assistants to assist the code official in the enforcement of this code. A permanently appointed code official shall not be removed from office except for cause after having been afforded a full opportunity to be heard on specific and relevant charges by and before the appointing authority. DHCD shall be notified by the appointing authority within 30 days of the appointment or release of a permanent or acting code official and within 60 days after retaining or terminating a technical assistant.

Note: Code officials and technical assistants are subject to sanctions in accordance with the VCS.

G. Section 104.4.1 Qualifications of code official and technical assistants. The code official shall have at least five years of building experience as a licensed professional engineer or architect, building, fire or trade inspector, contractor, housing inspector or superintendent of

building, fire or trade construction or at least least five years of building experience after obtaining a degree in architecture or engineering, with at least three years in responsible charge of work. Any combination of education and experience that would confer equivalent knowledge and ability shall be deemed to satisfy this requirement. The code official shall have general knowledge of sound engineering practice in respect to the design and construction of structures, the basic principles of fire prevention, the accepted requirements for means of egress and the installation of elevators and other service equipment necessary for the health, safety and general welfare of the occupants and the public. The local governing body may establish additional qualification requirements.

A technical assistant shall have at least three years of experience and general knowledge in at least one of the following areas: building construction, building, fire or housing inspections, plumbing, electrical or mechanical trades, fire protection, elevators or property maintenance work. Any combination of education and experience which would confer equivalent knowledge and ability shall be deemed to satisfy this requirement. The locality may establish additional certification requirements.

H. Section 104.4.2 Certification of code official and technical assistants. An acting or permanent code official shall be certified as a code official in accordance with the VCS within one year after being appointed as acting or permanent code official. A technical assistant shall be certified in the appropriate subject area within 18 months after becoming a technical assistant. When required by a locality to have two or more certifications, a technical assistant shall obtain the additional certifications within three years from the date of such requirement.

Exception: A code official or technical assistant in place prior to April 1, 1995, shall not be required to meet the certification requirements in this section while continuing to serve in the same capacity in the same locality.

I. Section 104.4.3 Noncertified code official. Except for a code official exempt from certification under the exception to Section 104.4.2, any acting or permanent code official who is not certified as a code official in accordance with the VCS shall attend the core module of the Virginia Building Code Academy or an equivalent course in an individual or regional code academy accredited by DHCD within 180 days of appointment. This requirement is in addition to meeting the certification requirement in Section 104.4.2.

J. Section 104.4.4 Requirements for periodic maintenance training and education. Code officials and technical assistants shall attend periodic maintenance training as designated by DHCD. In addition to the periodic maintenance training required above, code officials and technical assistants shall attend 16 hours of continuing education every two years as approved by DHCD. If a code official or technical assistant possesses more than one BHCD certificate, the 16 hours shall satisfy the continuing education requirement for all BHCD certificates.

K. Section 104.4.5 Conflict of interest. The standards of conduct for code officials and technical assistants shall be in accordance with the provisions of the State and Local Government Conflict of Interests Act, Chapter 31 (§ 2.2-3100 et seq.) of Title 2.2 of the Code of Virginia.

L. Section 104.4.6 Records. The local enforcing agency shall retain a record of applications received, permits, certificates, notices and orders issued, fees collected and reports of inspections in accordance with The Library of Virginia's General Schedule Number Six.

M. Section 104.5 Powers and duties, generally. The code official shall enforce this code as set out herein and as interpreted by the State Review Board and shall issue all necessary notices or orders to ensure compliance with the code.

N. Section 104.5.1 Delegation of authority. The code official may delegate powers and duties except where such authority is limited by the local government. When such delegations are made, the code official shall be responsible for assuring that they are carried out in accordance with the provisions of this code.

O. Section 104.5.2 Issuance of modifications. Upon written application by an owner or an owner's agent, the code official may approve a modification of any provision of this code provided the spirit and intent of the code are observed and public health, welfare and safety are assured. The decision of the code official concerning a modification shall be made in writing and the application for a modification and the decision of the code official concerning such modification shall be retained in the permanent records of the local enforcing agency.

P. Section 104.5.2.1 Substantiation of modification. The code official may require or may consider a statement from a professional engineer, architect or other person competent in the subject area of the application as to the equivalency of the proposed modification.

Q. Section 104.5.3 Inspections. The code official may inspect buildings or structures to determine compliance with this code and shall carry proper credentials when performing such inspections.

R. Section 104.5.4 Notices, reports and orders. Upon findings by the code official that violations of this code exist, the code official shall issue a correction notice or notice of violation to the owner or the person responsible for the maintenance of the structure. Work done to correct violations of this code subject to the permit, inspection and approval provisions of the Virginia Construction Code shall not be construed as authorization to extend the time limits established for compliance with this code.

S. Section 104.5.4.1 Correction notice. The correction notice shall be a written notice of the defective conditions. The correction notice shall require correction of the violation or violations within a reasonable time unless an emergency condition exists as provided under the unsafe building provisions of Section 105. Upon request, the correction notice shall reference the code section that serves as the basis for the defects and shall state that such defects shall be corrected and reinspected in a reasonable time designated by the code official.

T. Section 104.5.4.2 Notice of violation. If the code official determines there are violations of this code other than those for unsafe structures, unsafe equipment or structures unfit for human occupancy under Section 105, the code official may issue a notice of violation to be communicated promptly in writing to the owner or the person responsible for the maintenance or use of the building or structure in lieu of a correction notice as provided for in Section 104.5.4.1. In addition, the code official shall issue a notice of violation for any uncorrected

violation remaining from a correction notice established in Section 104.5.4.1. A notice of violation shall be issued by the code official before initiating legal proceedings unless the conditions violate the unsafe building conditions of Section 105 and the provisions established therein are followed. The code official shall provide the section numbers to the owner for any code provision cited in the notice of violation. The notice shall require correction of the violation or violations within a reasonable time unless an emergency condition exists as provided under the building provisions of Section 105. The owner or person to whom the notice of violation has been issued shall be responsible for contacting the code official within the time frame established for any reinspections to assure the violations have been corrected. The code official will be responsible for making such inspection and verifying the violations have been corrected. In addition, the notice of violation shall indicate the right of appeal by referencing the appeals section of this code.

U. Section 104.5.5 Coordination of inspections. The code official shall coordinate inspections and administrative orders with any other state or local agencies having related inspection authority and shall coordinate those inspections required by the Virginia Statewide Fire Prevention Code (13VAC5-51) for maintenance of fire protection devices, equipment and assemblies so that the owners and occupants will not be subjected to numerous inspections or conflicting orders.

Note: The Fire Prevention Code requires the fire official to coordinate such inspections with the code official.

V. Section 104.5.6 Further action when violation not corrected. If the responsible party has not complied with the notice of violation, the code official shall submit a written request to the legal counsel of the locality to institute the appropriate legal proceedings to restrain, correct or abate the violation or to require the removal or termination of the use of the building or structure involved. In cases where the locality so authorizes, the code official may issue or obtain a summons or warrant.

W. Section 104.5.7 Penalties and abatement. Penalties for violations of this code shall be as set out in § 36-106 of the Code of Virginia. The successful prosecution of a violation of the code shall not preclude the institution of appropriate legal action to require correction or abatement of a violation.

13VAC5-63-490. Section 105 Unsafe structures or structures unfit for human occupancy.

A. Section 105.1 General. This section shall apply to existing structures which are classified as unsafe or unfit for human occupancy. All conditions causing such structures to be classified as unsafe or unfit for human occupancy shall be remedied or as an alternative to correcting such conditions, the structure may be vacated and secured against public entry or razed and removed. Vacant and secured structures shall still be subject to other applicable requirements of this code. Notwithstanding the above, when the code official determines that an unsafe structure or a structure unfit for human occupancy constitutes such a hazard that it should be razed or removed, then the code official shall be permitted to order the demolition of such structures in accordance with applicable requirements of this code.

Note: Structures which become unsafe during construction are regulated under the Virginia Construction Code.

B. Section 105.2 Inspection of unsafe or unfit structures. The code official shall inspect any structure reported or discovered as unsafe or unfit for human habitation and shall prepare a report to be filed in the records of the local enforcing agency and a copy issued to the owner. The report shall include the use of the structure and a description of the nature and extent of any conditions found.

C. Section 105.3 Unsafe conditions not related to maintenance. When the code official finds a condition that constitutes a serious and dangerous hazard to life or health in a structure constructed prior to the initial edition of the USBC and when that condition is of a cause other than improper maintenance or failure to comply with state or local building codes that were in effect when the structure was constructed, then the code official shall be permitted to order those minimum changes to the design or construction of the structure to remedy the condition.

D. Section 105.3.1 Limitation to requirements for retrofitting. In accordance with Section 103.2, this code does not generally provide for requiring the retrofitting of any structure. However, conditions may exist in structures constructed prior to the initial edition of the USBC because of faulty design or equipment that constitute a danger to life or health or a serious hazard. Any changes to the design or construction required by the code official under this section shall be only to remedy the serious hazard or danger to life or health and such changes shall not be required to fully comply with the requirements of the Virginia Construction Code applicable to newly constructed buildings or structures.

E. Section 105.4 Notice of unsafe structure or structure unfit for human occupancy. When a structure is determined to be unsafe or unfit for human occupancy by the code official, a written notice of unsafe structure or structure unfit for human occupancy shall be issued by personal service to the owner, the owner's agent or the person in control of such structure. The notice shall specify the corrections necessary to comply with this code, or if the structure is required to be demolished, the notice shall specify the time period within which the demolition must occur. Requirements in Section 104.5.4 for notices of violation are also applicable to notices issued under this section to the extent that any such requirements are not in conflict with the requirements of this section.

Note: Whenever possible, the notice should also be given to any tenants of the affected structure.

F. Section 105.4.1 Vacating unsafe structure. If the code official determines there is actual and immediate danger to the occupants or public, or when life is endangered by the occupancy of an unsafe structure, the code official shall be authorized to order the occupants to immediately vacate the unsafe structure. When an unsafe structure is ordered to be vacated, the code official shall post a notice with the following wording at each entrance: "THIS STRUCTURE IS UNSAFE AND ITS OCCUPANCY (OR USE) IS PROHIBITED BY THE CODE OFFICIAL." After posting, occupancy of or use of the unsafe structure shall be prohibited except when authorized to enter to conduct inspections, make required repairs or as necessary to demolish the structure.

G. Section 105.5 Posting of notice. If the notice is unable to be issued by personal service as required by Section 105.4, then the notice shall be sent by registered or certified mail to the last known address of the responsible party and a copy of the notice shall be posted in a conspicuous place on the premises.

H. Section 105.6 Posting of placard. In the case of a structure unfit for human habitation, at the time the notice is issued, a placard with the following wording shall be posted at the entrance to the structure: "THIS STRUCTURE IS UNFIT FOR HABITATION AND ITS USE OR OCCUPANCY HAS BEEN PROHIBITED BY THE CODE OFFICIAL." In the case of an unsafe structure, if the notice is not complied with, a placard with the above wording shall be posted at the entrance to the structure. After a structure is placarded, entering the structure shall be prohibited except as authorized by the code official to make inspections, to perform required repairs or to demolish the structure. In addition, the placard shall not be removed until the structure is determined by the code official to be safe to occupy, nor shall the placard be defaced.

I. Section 105.7 Revocation of certificate of occupancy. If a notice of unsafe structure or structure unfit for human habitation is not complied with within the time period stipulated on the notice, the code official shall be permitted to request the local building department to revoke the certificate of occupancy issued under the Virginia Construction Code.

J. Section 105.8 Vacant and open structures. When an unsafe structure or a structure unfit for human habitation is open for public entry at the time a placard is issued under Section 105.6, the code official shall be permitted to authorize the necessary work to make such structure secure against public entry whether or not legal action to compel compliance has been instituted.

K. Section 105.9 Emergency repairs and demolition. To the extent permitted by the locality, the code official may authorize emergency repairs to unsafe structures or structures unfit for human habitation when it is determined that there is an immediate danger of any portion of the unsafe structure or structure unfit for human habitation collapsing or falling and when life is endangered. Emergency repairs may also be authorized where there is a code violation resulting in the immediate serious and imminent threat to the life and safety of the occupants. The code official shall be permitted to authorize the necessary work to make the structure temporarily safe whether or not legal action to compel compliance has been instituted. In addition, whenever an owner of an unsafe structure or structure unfit for human habitation fails to comply with a notice to demolish issued under Section 105.4 in the time period stipulated, the code official shall be permitted to cause the structure to be demolished. In accordance with §§ 15.2-906 and 15.2-1115 of the Code of Virginia, the legal counsel of the locality may be requested to institute appropriate action against the property owner to recover the costs associated with any such emergency repairs or demolition and every such charge that remains unpaid shall constitute a lien against the property on which the emergency repairs or demolition were made and shall be enforceable in the same manner as provided in Articles 3 (§ 58.1-3490 et seq.) and 4 (§ 58.1-3965 et seq.) of Chapter 39 of Title 58.1 of the Code of Virginia.

Note: Code officials and local governing bodies should be aware that other statutes and court decisions may impact on matters relating to demolition, in particular whether newspaper

publication is required if the owner cannot be located and whether the demolition order must be delayed until the owner has been given the opportunity for a hearing. In addition, historic building demolition may be prevented by authority granted to local historic review boards in accordance with § 15.2-2306 of the Code of Virginia unless determined necessary by the code official.

L. Section 105.10 Closing of streets. When necessary for public safety, the code official shall be permitted to order the temporary closing of sidewalks, streets, public ways or premises adjacent to unsafe or unfit structures and prohibit the use of such spaces.

13VAC5-63-500. Section 106 Appeals.

A. Section 106.1 Establishment of appeals board. In accordance with § 36-105 of the Code of Virginia, there shall be established within each local enforcing agency a LBBCA. Whenever a county or a municipality does not have such a LBBCA, the local governing body shall enter into an agreement with the local governing body of another county or municipality or with some other agency, or a state agency approved by DHCD for such appeals resulting therefrom. Fees may be levied by the local governing body in order to defray the cost of such appeals. The LBBCA for hearing appeals under the Virginia Construction Code shall be permitted to serve as the appeals board required by this section.

B. Section 106.2 Membership of board. The LBBCA shall consist of at least five members appointed by the locality for a specific term of office established by written policy. Alternate members may be appointed to serve in the absence of any regular members and as such, shall have the full power and authority of the regular members. Regular and alternate members may be reappointed. Written records of current membership, including a record of the current chairman and secretary shall be maintained in the office of the locality. In order to provide continuity, the terms of the members may be of different length so that less than half will expire in any one-year period. The LBBCA shall meet at least once annually to assure a duly constituted board, appoint officers as necessary and receive such training on the code as may be appropriate or necessary from staff of the locality.

C. Section 106.3 Officers and qualifications of members. The LBBCA shall annually select one of its regular members to serve as chairman. When the chairman is not present at an appeal hearing, the members present shall select an acting chairman. The locality or the chief executive officer of the locality shall appoint a secretary to the LBBCA to maintain a detailed record of all proceedings. Members of the LBBCA shall be selected by the locality on the basis of their ability to render fair and competent decisions regarding application of the USBC and shall to the extent possible, represent different occupational or professional fields relating to the construction industry. At least one member should be an experienced builder; at least one member should be an RDP, and at least one member should be an experienced property manager. Employees or officials of the locality shall not serve as members of the LBBCA.

D. Section 106.4 Conduct of members. No member shall hear an appeal in which that member has a conflict of interest in accordance with the State and Local Government Conflict of Interests Act (§ 2.2-3100 et seq. of the Code of Virginia). Members shall not discuss the substance of an appeal with any other party or their representatives prior to any hearings.

E. Section 106.5 Right of appeal; filing of appeal application. Any person aggrieved by the local enforcing agency's application of this code or the refusal to grant a modification to the provisions of this code may appeal to the LBBCA. The applicant shall submit a written request for appeal to the LBBCA within 14 calendar days of the receipt of the decision being appealed. The application shall contain the name and address of the owner of the building or structure and, in addition, the name and address of the person appealing, when the applicant is not the owner. A copy of the code official's decision shall be submitted along with the application for appeal and maintained as part of the record. The application shall be marked by the LBBCA to indicate the date received. Failure to submit an application for appeal within the time limit established by this section shall constitute acceptance of a code official's decision.

F. Section 106.6 Meetings and postponements. The LBBCA shall meet within 30 calendar days after the date of receipt of the application for appeal, except that a longer time period shall be permitted if agreed to by all the parties involved in the appeal. A notice indicating the time and place of the hearing shall be sent to the parties in writing to the addresses listed on the application at least 14 calendar days prior to the date of the hearing, except that a lesser time period shall be permitted if agreed to by all the parties involved in the appeal. When a quorum of the LBBCA is not present at a hearing to hear an appeal, any party involved in the appeal shall have the right to request a postponement of the hearing. The LBBCA shall reschedule the appeal within 30 calendar days of the postponement, except that a longer time period shall be permitted if agreed to by all the parties involved in the appeal.

G. Section 106.7 Hearings and decision. All hearings before the LBBCA shall be open meetings and the appellant, the appellant's representative, the locality's representative and any person whose interests are affected by the code official's decision in question shall be given an opportunity to be heard. The chairman shall have the power and duty to direct the hearing, rule upon the acceptance of evidence and oversee the record of all proceedings. The LBBCA shall have the power to uphold, reverse or modify the decision of the official by a concurring vote of a majority of those present. Decisions of the LBBCA shall be final if no further appeal is made. The decision of the LBBCA shall be by resolution signed by the chairman and retained as part of the record of the appeal. Copies of the resolution shall be sent to all parties by certified mail. In addition, the resolution shall contain the following wording:

"Any person who was a party to the appeal may appeal to the State Review Board by submitting an application to such Board within 21 calendar days upon receipt by certified mail of this resolution. Application forms are available from the Office of the State Review Board, 600 East Main Street, Richmond, Virginia 23219, (804) 371-7150."

H. Section 106.8 Appeals to the State Review Board. After final determination by the LBBCA in an appeal, any person who was a party to the appeal may further appeal to the State Review Board. In accordance with § 36-98.2 of the Code of Virginia for state-owned buildings and structures, appeals by an involved state agency from the decision of the code official for state-owned buildings or structures shall be made directly to the State Review Board. The application for appeal shall be made to the State Review Board within 21 calendar days of the receipt of the decision to be appealed. Failure to submit an application within that time limit shall constitute an acceptance of the code official's decision. For appeals from a LBBCA, a

copy of the code official's decision and the resolution of the LBBCA shall be submitted with the application for appeal to the State Review Board. Upon request by the Office of the State Review Board, the LBBCA shall submit a copy of all pertinent information from the record of the appeal. In the case of appeals involving state-owned buildings or structures, the involved state agency shall submit a copy of the code official's decision and other relevant information with the application for appeal to the State Review Board. Procedures of the State Review Board are in accordance with Article 2 (§ 36-108 et seq.) of Chapter 6 of Title 36 of the Code of Virginia. Decisions of the State Review Board shall be final if no further appeal is made.

13VAC5-63-510. Chapter 2 Definitions.

A. Change Section 201.3 of the IPMC to read:

201.3 Terms defined in other codes. Where terms are not defined in this code and are defined in the International Building Code, International Fire Code, International Fuel Gas Code, International Plumbing Code, International Mechanical Code, International Existing Building Code, International Residential Code, International Zoning Code or the ICC Electrical Code NFPA 70, such terms shall have the meanings ascribed to them as stated in those codes, except that terms defined in the Virginia Construction Code shall be used for this code and shall take precedence over other definitions.

B. Add the following definitions to Section 202 of the IPMC to read:

Structure unfit for human occupancy. An existing structure determined by the code official to be dangerous to the health, safety and welfare of the occupants of the structure or the public because (i) of the degree to which the structure is in disrepair or lacks maintenance, ventilation, illumination, sanitary or heating facilities or other essential equipment, or (ii) the required plumbing and sanitary facilities are inoperable.

Unsafe equipment. Unsafe equipment includes any boiler, heating equipment, elevator, moving stairway, electrical wiring or device, flammable liquid containers or other equipment that is in such disrepair or condition that such equipment is determined by the code official to be dangerous to the health, safety and welfare of the occupants of a structure or the public.

Unsafe structure. An existing structure (i) determined by the code official to be dangerous to the health, safety and welfare of the occupants of the structure or the public, (ii) that contains unsafe equipment, or (iii) that is so damaged, decayed, dilapidated, structurally unsafe or of such faulty construction or unstable foundation that partial or complete collapse is likely. A vacant existing structure unsecured or open shall be deemed to be an unsafe structure.

13VAC5-63-520. Chapter 3 General requirements.

A. Delete Section 302.1 of the IPMC.

B. Change Section 302.2 of the IPMC to read:

302.2 Grading and drainage. All premises shall be graded and maintained to protect the foundation walls or slab of the structure from the accumulation and drainage of surface or stagnant water in accordance with the Virginia Construction Code.

C. Change Section 302.3 of the IPMC to read:

302.3 Sidewalks and driveways. All sidewalks, walkways, stairs, driveways, parking spaces and similar spaces regulated under the Virginia Construction Code shall be kept in a proper state of repair, and maintained free from hazardous conditions. Stairs shall comply with the requirements of Sections 305 and 702.

D. Delete Section 302.4 of the IPMC.

E. Change Section 302.5 of the IPMC to read:

302.5 Rodent harborage. All structures and adjacent premises shall be kept free from rodent harborage and infestation where such harborage or infestation adversely affects the structures.

F. Delete Sections 302.8 and 302.9 of the IPMC.

G. Delete Section 304.1.1 of the IPMC.

H. Change Section 304.7 of the IPMC to read:

304.7 Roofs and drainage. The roof and flashing shall be sound, tight and not have defects that admit rain. Roof drainage shall be adequate to prevent dampness or deterioration in the walls or interior portion of the structure. Roof drains, gutters and downspouts shall be maintained in good repair and free from obstructions. Roof water shall be discharged in a manner to protect the foundation or slab of buildings and structures from the accumulation of roof drainage.

I. Change Section 304.14 of the IPMC to read:

304.14 Insect screens. During the period from April 1 to December 1, every door, window and other outside opening required for ventilation of habitable rooms, food preparation areas, food service areas or any areas where products to be included or utilized in food for human consumption are processed, manufactured, packaged or stored, shall be supplied with approved tightly fitting screens of not less than 16 mesh per inch (16 mesh per 25 mm) and every screen door used for insect control shall have a self-closing device in good working condition.

Exception: Screens shall not be required where other approved means, such as mechanical ventilation, air curtains or insect repellant fans, are used.

J. Delete Sections 304.18, 304.18.1, 304.18.2 and 304.18.3 of the IPMC.

K. Delete Section 305.1.1 of the IPMC.

L. Add Section 305.7 to the IPMC to read:

305.7 Carbon monoxide alarms. Carbon monoxide alarms shall be maintained as approved.

M. Delete Section 306 of the IPMC in its entirety.

N. Change Section 308.1 of the IPMC to read as follows and delete the remaining provisions of Section 308:

308.1 Accumulation of rubbish and garbage. The interior of every structure shall be free from excessive accumulation of rubbish or garbage.

O. Change Section 309.1 of the IPMC to read:

309.1 Infestation. This section shall apply to the extent that insect and rodent infestation adversely affects a structure. All structures shall be kept free from insect and rodent infestation. All structures in which insects or rodents are found shall be promptly exterminated by approved processes that will not be injurious to human health. After extermination, proper precautions shall be taken to prevent reinfestation.

P. Add IPMC Section 310 Lead-Based Paint.

Q. Add Section 310.1 to the IPMC to read:

310.1 General. Interior and exterior painted surfaces of dwellings and child care facilities, including fences and outbuildings, that contain lead levels equal to or greater than 1.0 milligram per square centimeter or in excess of 0.50% lead by weight shall be maintained in a condition free from peeling, chipping and flaking paint or removed or covered in an approved manner. Any surface to be covered shall first be identified by an approved warning as to the lead content of such surface.

R. Add IPMC Section 311 Aboveground Liquid Fertilizer Storage Tanks (ALFSTs).

S. Add Section 311.1 to the IPMC to read:

311.1 General. ALFSTs shall be maintained in accordance with the requirements of Section 3413.16 of the Virginia Construction Code and the requirements of the Virginia Construction Code applicable to such ALFSTs when newly constructed, undergoing a change of occupancy to an ALFST and when repaired, altered or reconstructed, including the requirements for inspections and for a secondary containment system.

~~13VAC5-63-525. Chapter 4 Light, ventilation and occupancy limitations. (Repealed.)~~

~~A. Change Section 404.4.1 of the IMPC to read:~~

~~404.4.1 Room area. Every living room shall contain at least 120 square feet (11.2 m²) and every bedroom shall contain at least 70 square feet (6.5 m²) and every bedroom occupied by more than one person shall contain at least 50 square feet (4.6 m²) of floor area for each occupant thereof.~~

~~B. Change Section 404.5 of the IPMC and add new Table 404.5 to the IPMC to read:~~

~~404.5 Overcrowding. Dwelling units shall not be occupied by more occupants than permitted by the minimum area requirements of Table 404.5.~~

Table 404.5 Minimum Area Requirements			
Space	Minimum Area in Square Feet		
	1-2 occupants	3-5 occupants	6 or more occupants
Living room ^{a,b}	120	120	150
Dining room ^{a,b}	No requirement	80	100
Bedrooms	Shall comply with Section 404.4.1		
For SI: 1 square foot = 0.093 m ²			
^a See Section 404.5.2 for combined living room/dining room spaces.			
^b See Section 404.5.1 for limitations on determining the minimum occupancy area for sleeping purposes.			

~~C. Add Sections 404.5.1 and 404.5.2 to the IPMC to read:~~

~~404.5.1 Sleeping area. The minimum occupancy area required by Table 404.5 shall not be included as a sleeping area in determining the minimum occupancy area for sleeping purposes. All sleeping areas shall comply with Section 404.4.~~

~~404.5.2 Combined spaces. Combined living room and dining room spaces shall comply with the requirements of Table 404.5 if the total area is equal to that required for separate rooms and if the space is located so as to function as a combination living room/dining room.~~

13VAC5-63-530. Chapter 5 Plumbing facilities and fixture requirements.

A. Add Section 505.5 to the IPMC to read:

505.5 Inspection and testing of backflow prevention assemblies. Inspection and testing shall comply with Sections 505.5.1 and 505.5.2.

B. Add Section 505.5.1 to the IPMC to read:

505.5.1 Inspections. Inspections shall be made of all backflow prevention assemblies and air gaps to determine whether they are operable.

C. Add Section 505.5.2 to the IMPC to read:

505.5.2 Testing. Reduced pressure principle backflow preventer assemblies, double check-valve assemblies, double-detector check valve assemblies and pressure vacuum breaker assemblies shall be tested at the time of installation, immediately after repairs or relocation and at least annually. The testing procedure shall be performed in accordance with one of the following standards: ASSE 5010-1013-1, Sections 1 and 2; ASSE 5010-1015-1, Sections 1 and 2; ASSE 5010-1015-2; ASSE 5010-1015-3, Sections 1 and 2; ASSE 5010-1015-4, Sections 1 and 2; ASSE 5010-1020-1, Sections 1 and 2; ASSE 5010-1047-1, Sections 1, 2, 3 and 4; ASSE 5010-1048-1, Sections 1, 2, 3 and 4; ASSE 5010-1048-2; ASSE 5010-1048-3, Sections 1, 2, 3 and 4; ASSE 5010-1048-4, Sections 1, 2, 3 and 4; or CAN/CSA B64.10.

D. ~~Change Section 506.3 of the IPMC to read:~~

~~506.3 Grease interceptors. Grease interceptors, grease traps, and automatic grease removal devices shall be maintained in accordance with this code and the manufacturer's installation instructions. Grease interceptors, grease traps, and automatic grease removal devices shall be regularly serviced and cleaned to prevent the discharge of oil, grease, and other substances harmful or hazardous to the building drainage system, the public sewer, the private sewage disposal system, or the sewage treatment plant or processes. All records of maintenance, cleaning, and repairs shall be available for inspection by the code official.~~

E. ~~Change Section 507.1 of the IPMC to read:~~

~~507.1 General. Drainage of roofs and paved areas, yards and courts, and other open areas on the premises shall be discharged in a manner to protect the buildings and structures from the accumulation of overland water runoff.~~

13VAC5-63-540. Chapter 6 Mechanical and electrical requirements.

A. Change Section 602 of the IPMC to read:

Section 602 Heating and Cooling Facilities.

B. Change Section 602.1 of the IPMC to read:

602.1 Facilities required. Heating and cooling facilities shall be maintained and operated in structures as required by this section.

C. Change Section 602.2 of the IPMC to read:

602.2 Heat supply. Every owner and operator of any building who rents, leases or lets one or more dwelling unit, rooming unit, dormitory or guestroom on terms, either expressed or implied, to furnish heat to the occupants thereof shall supply heat during the period from October 15 to May 1 to maintain a temperature of not less than 65°F (18°C) in all habitable rooms, bathrooms, and toilet rooms.

Exception: When the outdoor temperature is below the winter outdoor design temperature for the locality, maintenance of the minimum room temperature shall not be required provided that the heating system is operating at its full design capacity. The winter outdoor design temperature for the locality shall be as indicated in Appendix D of the International Plumbing Code.

D. Add Section 602.2.1 to the IPMC to read:

602.2.1 Prohibited use. In dwelling units subject to Section 602.2, one or more unvented room heaters shall not be used as the sole source of comfort heat in a dwelling unit.

E. Change Section 602.3 of the IPMC to read:

602.3 Occupiable work spaces. Indoor occupiable work spaces shall be supplied with heat during the period from October 1 to May 15 to maintain a temperature of not less than 65°F (18°C) during the period the spaces are occupied.

Exceptions:

1. Processing, storage and operation areas that require cooling or special temperature conditions.
2. Areas in which persons are primarily engaged in vigorous physical activities.

F. Change Section 602.4 of the IPMC to read:

602.4 Cooling supply. Every owner and operator of a Group R-2 apartment building who rents, leases or lets one or more dwelling units, rooming units or guestrooms on terms, either expressed or implied, to furnish cooling to the occupants thereof shall supply cooling during the period from May 15 to October 1 to maintain a temperature of not more than 80°F (27°C) in all habitable rooms.

Exception: When the outdoor temperature is higher than the summer design temperature for the locality, maintenance of the room temperature shall not be required provided that the cooling system is operating at its full design capacity. The summer outdoor design temperature for the locality shall be as indicated in the International Energy Conservation Code.

G. Change the exception to Section 604.3.1.1 of the IPMC to read:

Exception: The following equipment shall be allowed to be repaired or reused where an inspection report from the equipment manufacturer, an approved representative of the equipment manufacturer, a third party licensed or certified electrician, or an electrical engineer indicates that the exposed equipment has not sustained damage that requires replacement:

1. Enclosed switches, rated 600 volts or less;

2. Busway, rated 600 volts or less;
3. Panelboards, rated 600 volts or less;
4. Switchboards, rated 600 volts or less;
5. Fire pump controllers, rated 600 volts or less;
6. Manual and magnetic motor controllers;
7. Motor control centers;
8. Alternating current high-voltage circuit breakers;
9. Low-voltage power circuit breakers;
10. Protective relays, meters and current transformers;
11. Low- and medium-voltage switchgear;
12. Liquid-filled transformers;
13. Cast-resin transformers;
14. Wire or cable that is suitable for wet locations and whose ends have not been exposed to water;
15. Wire or cable, not containing fillers, that is suitable for wet locations and whose ends have not been exposed to water;
16. Luminaires that are listed as submersible;
17. Motors;
18. Electronic control, signaling and communication equipment.

H. Change Section 606.1 to the IPMC to read:

606.1 General. Elevators, dumbwaiters and escalators shall be maintained in compliance with ASME A17.1. The most current certificate of inspection shall be on display at all times within the elevator or attached to the escalator or dumbwaiter, be available for public inspection in the office of the building operator or be posted in a publicly conspicuous location approved by the code official. An annual periodic inspection and test is required of elevators and escalators. A locality shall be permitted to require a six-month periodic inspection and test. All periodic inspections shall be performed in accordance with Section 8.11 of ASME A17.1. The code official may also provide for such inspection by an approved agency or through agreement with other local certified elevator inspectors.

An approved agency includes any individual, partnership or corporation who has met the certification requirements established by the VCS.

TAB 2

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): X ☐ Individual ☐ Government Entity ☐ Company

Name: John Catlett

Representing: VBCOA Administration Committee

Mailing Address: 301 King Street, Alexandria, Virginia 22314

Email Address: john.catlett@alexandriava.gov

Telephone Number: 703.746.4182

Proposal Information

Code(s) and Section(s): 108.2 Exemptions from Permit (Revised 9/27/120)

Proposed Change (including all relevant section numbers, if multiple sections):

108.2 Exemptions from application for permit. . . .

2. One story detached ~~accessory~~ structures used as tool and storage sheds, playhouses or similar uses, provided the ~~floor building~~ area does not exceed ~~200~~ 256 square feet (18 m²) and the structures are not classified as a Group F-1 or H occupancy.

(No other changes)

Supporting Statement (including intent, need, and impact of the proposal):

This change would provide consistency with the provisions for the permanent foundation requirement threshold of 256 square feet found in the IBC; additionally, the word "accessory" is proposed for removal so that this exception can apply to tool and storage buildings that are not accessory to a specific building. An example would be a stand-alone storage shed at a park or cemetery. This only exempts the structure from building permit, not compliance with the VCC or local zoning requirements. This provides consistency with the model codes. **There is consensus within the VBCOA Administration Committee on this Code change.**

Submittal Information

Date Submitted: August 1, 2012

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
600 East Main Street
Suite 300
Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov

Fax Number: (804) 371-7092

Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: DRAFT

Proponent Information

(Check one): ☒ Individual ☐ Government Entity ☐ Company

Name: John Catlett

Representing: VBCOA Administration Committee

Mailing Address: 301 King Street, Alexandria, Virginia 22314

Email Address: john.catlett@alexandriava.gov

Telephone Number: 703.746.4182

Proposal Information

Code(s) and Section(s): VCC Section 108.2

Proposed Change (including all relevant section numbers, if multiple sections):

108.2 Exemptions from application for permit. Notwithstanding the requirements of Section 108.1, application for a permit and any related inspections shall not be required for the following; however, this section shall not be construed to exempt such activities from other applicable requirements of this code. In addition, when an owner or an owner's agent requests that a permit be issued for any of the following, then a permit shall be issued and any related inspections shall be required.

1 through 4 no change.

5. Fences of any height unless required for pedestrian safety as provided for by Section 3306 or of that form the barrier for a swimming pool.

6. Concrete or masonry walls, provided such walls do not exceed six feet in height above the finished grade. Ornamental column caps shall not be considered to contribute to the height of the wall and shall be permitted to extend above the six feet height measurement.

Supporting Statement (including intent, need, and impact of the proposal):

No technical provisions are provided in the building codes regardless of their height. The requirement that fences less than 6' contain less of a hazard than fences over that height has no technical support in the building code. Fences, regardless of height, receive no footing inspection nor are there technical standards for fences over 6 feet. This code change proposes removing all light weight material fences from a permit requirement. The provision retains that concrete and masonry walls do have a greater hazard and must support their weight on a proper foundation. In addition, the provision still requires a permit for any pool barrier and now adds pedestrian safety barriers for construction sites adjacent to public pedestrian ways.

Submittal Information

Date Submitted: August 2, 2012

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TSO (Technical Assistance and Services Office)
600 East Main Street
Suite 300
Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov

Fax Number: (804) 371-7092

Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☒ Individual ☐ Government Entity ☐ Company

Name: John Catlett

Representing: VBCOA Administration Committee

Mailing Address: 301 King Street, Alexandria, Virginia 22314

Email Address: john.catlett@alexandriava.gov

Telephone Number: 703.746.4182

Proposal Information

Code(s) and Section(s): 108.2 Exemptions from Permit

Proposed Change (including all relevant section numbers, if multiple sections):

108.2 Exemptions from application for permit. . . .

6. Retaining walls supporting less than ~~two~~ three feet of unbalanced fill which are not constructed for the purpose of. ~~This exemption shall not apply to any wall impounding class I, II or III-A liquids or supporting a surcharge other than ordinary unbalanced fill.~~

(No other changes)

Supporting Statement (including intent, need, and impact of the proposal):

It is generally felt throughout the construction community and code administrators alike that the current language is too restrictive and requires small area retaining walls around plantings and minor changes in grade to obtain a permit. The risk at 2' is negligible unless supporting a surcharge which is addressed in the code. The current requirement for flammable and combustible liquid enclosures would remain.

Submittal Information

Date Submitted: August 1, 2012

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
600 East Main Street

Email Address: taso@dhcd.virginia.gov

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name _____ Representing: _____

Mailing Address: _____

Email Address: _____ Telephone Number: _____

Proposal Information

Code(s) and Section(s): VCC section 108.2

Proposed Change (including all relevant section numbers, if multiple sections):

Add new exemption #11 VCC section 108.2 Exemptions from application.

#11. Crypts, mausoleums, and columbaria structures not exceeding 1500 square feet in area if the building or structure is non-occupiable and used solely for the interment of human or animal remains unless such structure is subject to special inspections.

Supporting Statement (including intent, need, and impact of the proposal):

Submittal Information

Date Submitted: _____

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
The Jackson Center
501 N. 2nd Street
Richmond, VA 23219-1321

Email Address: taso@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): X ☐ Individual ☐ Government Entity ☐ Company

Name: John Catlett

Representing: VBCOA Administration Committee

Mailing Address: 301 King Street, Alexandria, Virginia 22314

Email Address: john.catlett@alexandriava.gov

Telephone Number: 703.746.4182

Proposal Information

Code(s) and Section(s): 117.1 Temporary Buildings, Structures and Uses

Proposed Change (including all relevant section numbers, if multiple sections):

117.1 Temporary building and, structures. The building official is authorized to issue a permit for temporary buildings or structures, and. Such permits shall be limited as to time of service, but shall not be permitted for more than one year, except that upon the permit holder's written request, the building official may grant one or more extensions of time, not to exceed one year per extension. The building official is authorized to terminate the approval and order the demolition, removal of temporary buildings or structures during the period authorized by the permit when determined necessary.

117.1.1 Temporary uses within existing buildings and structures. The building official shall review and may approve conditions or modifications for temporary uses, including hypothermia and hyperthermia shelters, that may be necessary as long as the use meets the spirit and functional intent intended by this code. The building official is authorized to terminate the approval and order the discontinuance of the temporary use during the period authorized by the permit when determined necessary. The building official shall notify the appropriate fire official or fire chief of the approved temporary use.

Supporting Statement (including intent, need, and impact of the proposal):

It has been identified that some localities have not allowed temporary uses such as shelters and other uses except in buildings meeting all of the requirements for the proposed uses. The proposed changes will clearly allow the building officials to consider alternatives and approve them for temporary uses. This will allow consideration of the risk vs. benefit associated with short term temporary uses. This can provide flexibility to consider temporary uses for things such as hyper/hypothermia shelters, overnight events such as Club or youth group overnight events at churches, fundraising events of very limited duration while considering alternatives such as fire watches, occupancy limitations, single station smoke detection, etc.

Submittal Information

Date Submitted: August 21, 2012 (Revised November 27, 2012)

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☒ Individual ☐ Government Entity ☐ Company

Name: John Catlett

Representing: VBCOA Administration Committee

Mailing Address: 301 King Street, Alexandria, Virginia 22314

Email Address: john.catlett@alexandriava.gov

Telephone Number: 703.746.4182

Proposal Information

Code(s) and Section(s): VCC Section 118 Unsafe Buildings (Revised September 17, 2012)

Proposed Change (including all relevant section numbers, if multiple sections):

Proposed VCC definition of unsafe structure

UNSAFE BUILDINGS AND STRUCTURES. Any building or structure that is under construction and has not received a permanent certificate of occupancy, final inspection, or in which a permit was never issued or has expired and has been determined by the building official to be of faulty construction that is so damaged, decayed, dilapidated, structurally unsafe or of such faulty construction or unstable foundation that partial or complete collapse is likely; or any unfinished construction that does not have a valid permit or the permit has been revoked, and the condition of the unfinished construction presents an immediate serious and imminent threat to the life and safety of the occupants or the public.

Proposed Revision to 118 of the VCC:

SECTION 118

BUILDINGS AND STRUCTURES BECOMING UNSAFE DURING CONSTRUCTION

118.1 Applicability. This section applies to buildings and structures for which a construction permit has been issued under this code and construction has not been completed or a certificate of occupancy has not been issued, or both defined as an unsafe building or structure by the VCC. In addition, this section applies to any building or structure that is under construction regardless of permit activity status or that was constructed without obtaining the required permits under this edition or any edition of the USBC.

Note: Existing buildings and structures other than those under construction or subject to this section are subject to the Virginia Maintenance Code that also has requirements for unsafe conditions.

118.2 Repair or removal of unsafe buildings or structures. Any building or structure subject to this section that is either deteriorated, ~~improperly maintained~~, of faulty construction, deficient in adequate exit facilities, a fire hazard or dangerous to life or the public welfare, or both, or any combination of the foregoing, is an unsafe building or structure and shall be made safe through compliance with this code or shall be taken down and removed if determined necessary by the building official.

118.3 Inspection report and notice of unsafe building or structure. The building official shall inspect any building or structure reported to be unsafe and shall prepare a report to be filed in the records of the local building department. In addition to a description of any unsafe conditions found, the report shall include the occupancy classification of the building or structure and the nature and extent of any damages caused by collapse or failure of any building components. If the building or structure is determined by the building official to be unsafe, a notice of unsafe building or structure shall be issued in person to the owner and any permit holder. The notice shall describe any unsafe conditions and specify any repairs or improvements necessary to make the building or structure safe, or alternatively, when determined necessary by the building official, require the unsafe building or structure, or any portion of it, to be taken down and removed.

The notice of an unsafe building or structure shall stipulate a time period for the repair or demolition of the unsafe building or structure and contain a statement requiring the person receiving the notice to determine whether to accept or reject the terms of the notice. If any persons to which the notice of unsafe building or structure is to be issued cannot be found after diligent search, as equivalent service, the notice shall be sent by registered or certified mail to the last known address of such persons and a copy of the notice posted in a conspicuous place on the premises.

118.4 Vacating the unsafe building or structure. If any portion of an unsafe building or structure has collapsed or fallen, or if the building official determines there is actual and immediate danger of any portion collapsing or falling, and when life is endangered by the occupancy of the unsafe building or structure, the building official shall be authorized to order the occupants to immediately vacate the unsafe building or structure. When an unsafe building or structure is ordered to be vacated, the building official shall post a notice at each entrance that reads as follows:

"This Building (or Structure) is Unsafe and its Occupancy (or Use) is Prohibited by the Building Official." After posting, occupancy or use of the unsafe structure shall be prohibited except when authorized to enter to conduct inspections, make required repairs or as necessary to demolish the building or structure.

118.5 Emergency repairs and demolition. To the extent permitted by the locality, the building official may authorize emergency repairs to unsafe buildings or structures when it is determined that there is an immediate danger of any portion of the unsafe building or structure collapsing or falling and when life is endangered. Emergency repairs may also be authorized when there is a code violation resulting in the immediate, serious and imminent threat to the life and safety of the occupants. The building official shall be permitted to authorize the necessary work to make the building or structure temporarily safe whether or not legal action to compel compliance has been instituted.

In addition, whenever an owner of an unsafe building or structure fails to comply with a notice to demolish issued under Section 118.3 in the time period stipulated, the building official shall be permitted to cause the unsafe building or structure to be demolished. In accordance with Sections 15.2-906 and 15.2-1115 of the Code of Virginia, the legal counsel of the locality may be requested to institute appropriate action against the property owner to recover the costs associated with any such emergency repairs or demolition and every such charge that remains unpaid shall constitute a lien against the property on which the emergency repairs or demolition were made and shall be enforceable in the same manner as provided in Articles 3 (Section 58.1-3940 et seq.) and 4 (Section 58.1-3965 et seq.) of Chapter 39 of Title 58.1 of the Code of Virginia.

Note: Building officials and local governing bodies should be aware that other statutes and court decisions may impact on matters relating to demolition, in particular whether newspaper publication is required if the owner cannot be located and whether the demolition order must be delayed until the owner has been given the opportunity for a hearing.

118.4 Notice of unsafe building or structure. When a building or structure is determined to be unsafe by the building official, a written notice of unsafe structure shall be issued by personal service to the owner, the owner's agent or the person in control of such structure. The notice shall specify the corrections necessary to

comply with this code, or if the structure is required to be demolished, the notice shall specify the time period within which the repairs or demolition must occur. Requirements in Section 115 for notices of violation are also applicable to notices issued under this section to the extent that any such requirements are not in conflict with the requirements of this section.

Note: Whenever possible, the notice should also be given to any tenants or occupants of the affected structure.

118.4.1 Vacating unsafe structure. If the building official determines there is actual and immediate danger to the occupants or public, or when life is endangered by the occupancy of an unsafe structure, the building official shall be authorized to order the occupants to immediately vacate the unsafe structure. When an unsafe structure is ordered to be vacated, the building official shall post a notice with the following wording at each entrance: "THIS STRUCTURE IS UNSAFE AND ITS OCCUPANCY (OR USE) IS PROHIBITED BY THE BUILDING OFFICIAL." After posting, occupancy or use of the unsafe structure shall be prohibited except when authorized to enter to conduct inspections, make required repairs or as necessary to demolish the structure.

118.5 Posting of notice. If the notice is unable to be issued by personal service as required by Section 118.4, then the notice shall be sent by registered or certified mail to the last known address of the responsible party and a copy of the notice shall be posted in a conspicuous place on the premises.

118.6 Posting of placard. In the case of an unsafe building or structure, if the notice is not complied with, a placard with the following wording shall be posted at the entrance to the structure: "THIS STRUCTURE IS UNFIT FOR HABITATION AND ITS USE OR OCCUPANCY HAS BEEN PROHIBITED BY THE BUILDING OFFICIAL." After a structure is placarded, entering the structure shall be prohibited except as authorized by the building official to make inspections, to perform required repairs or to demolish the structure. In addition, the placard shall not be removed until the structure is determined by the building official to be safe to occupy, nor shall the placard be defaced.

118.7 Emergency repairs and demolition. To the extent permitted by the locality, the building official may authorize emergency repairs to unsafe buildings or structures when it is determined that there is an immediate danger of any portion of the unsafe structure or structure unfit for human habitation collapsing or falling and when life is endangered. Emergency repairs may also be authorized where there is a code violation resulting in a serious and imminent threat to the life and safety of the occupants or public.

The building official shall be permitted to authorize the necessary work to make the structure temporarily safe whether or not legal action to compel compliance has been instituted. In addition, whenever an owner of an unsafe structure or structure unfit for human habitation fails to comply with a notice to demolish issued under Section 118.4 in the time period stipulated, the building official shall be permitted to cause the structure to be demolished. In accordance with Sections 15.2-906 and 15.2-1115 of the Code of Virginia, the legal counsel of the locality may be requested to institute appropriate action against the property owner to recover the costs associated with any such emergency repairs or demolition and every such charge that remains unpaid shall constitute a lien against the property on which the emergency repairs or demolition were made and shall be enforceable in the same manner as provided in Articles 3 (Section 58.1-3490 et seq.) and 4 (Section 58.1-3965 et seq.) of Chapter 39 of Title 58.1 of the Code of Virginia.

Note: Building officials and local governing bodies should be aware that other statutes and court decisions may impact on matters relating to demolition, in particular whether newspaper publication is required if the owner cannot be located and whether the demolition order must be delayed until the owner has been given the opportunity for a hearing.

118.8 Closing of streets. When necessary for public safety, the building official shall be permitted to order the temporary closing of sidewalks, streets, public ways or premises adjacent to unsafe or unfit structures and prohibit the use of such spaces.

Supporting Statement (including intent, need, and impact of the proposal):

During the last economic downturn, several localities were left with construction projects that occasionally exceeded the norm when it comes to health and safety, especially in established neighborhoods. Some localities looked at spot blight provisions and some utilized the Virginia Maintenance Code to address the concerns. However the Virginia Maintenance Code is intended to address buildings and structures that either currently and legally exist, or have completed the construction process through the VCC and received an occupancy permit or final inspection.

It is generally felt that the provisions of the VMC were adequate to address those few situations that result in imminent danger to the health and safety of the community. This code change takes defining an unsafe structure out of Section 118 and places it in the definition provisions of the code. It further proposes duplicated processes and procedures from the VMC that not only provide consistency, a proven track record, and predictability, but it also provides a clear path to administrative appeals that spot blight does not allow.

These provisions are comprehensive enough to deal with any unsafe provision while requiring the building official to provide multiple levels of notification and documentation which protect the property rights of the building owner.

There is consensus within the VBCOA Administration Committee on this code change.

Submittal Information

Date Submitted: August 21, 2012 (Revised November 17, 2012)

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
600 East Main Street
Suite 300
Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov

Fax Number: (804) 371-7092

Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☒ Government Entity ☐ Company

Name: Joseph Moncrief

Representing: Chesterfield County

Mailing Address: 9800 Government Center Parkway P.O. Box 40 Chesterfield, VA 23832

Email Address: moncriefj@chesterfield.gov

Telephone Number: (804) 317-3038

Proposal Information Draft code change #1

Code(s) and Section(s): USBC part 1 section 118.3

Proposed Change (including all relevant section numbers, if multiple sections):

Amend section 118.3 to state:

118.3 Inspection report and notice of unsafe building or structure. The building official shall inspect any building or structure reported to be unsafe and shall prepare a report to be filed in the records of the local building department. In addition to a description of any unsafe conditions found, the report shall include the occupancy classification of the building or structure and the nature and extent of any damages caused by collapse or failure of any building components. If the building or structure is determined by the building official to be unsafe, a notice of unsafe building or structure shall be issued in person to the owner and any permit holder. The notice shall describe any unsafe conditions and specify any repairs or improvements necessary to make the building or structure safe, or alternatively, when determined necessary by the building official, require the unsafe building or structure, or any portion of it, to be taken down and removed. The notice shall stipulate a time period for the repair or demolition of the unsafe building or structure and contain a statement requiring the person receiving the notice to determine whether to accept or reject the terms of the notice. If any persons to which the notice of unsafe building or structure is to be issued cannot be found after diligent search, as equivalent service, the notice shall be sent by registered or certified mail to the last known address of such persons and a copy of the notice posted in a conspicuous place on the premises.

Supporting Statement (including intent, need, and impact of the proposal):

The section currently requires a person receiving a Notice of Unsafe Structure to either accept or reject the terms of the notice. The acceptance or rejection of the terms of the notice has no effect of the notice and does not require the responsible party to appeal the action if they reject the terms. The rejection of the terms has no meaningful purpose. The rejection does not stop enforcement simply because there is a disagreement. This requirement is unnecessary because a statement of the right to appeal a Notice of Unsafe Structure is already required in the notice. Further, this same requirement was removed from the 2009 Virginia Maintenance Code (USBC part 3). The removal of this requirement will make both parts of the USBC consistent in the requirements for the Notice of Unsafe Structure. **There is consensus within the VBCOA Administration Committee to support this change regardless of the outcome of the unsafe**

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: John Catlett

Representing: VBCOA Administrative Committee

Mailing Address: 301 King Street, Room 4200 Alexandria Va. 22314

Email Address: john.catlett@alexandriava.gov

Telephone Number: 703.746.4182

Proposal Information

Code(s) and Section(s): VUSBC Section 119.2

Proposed Change (including all relevant section numbers, if multiple sections):

1.1 Establishment of appeals board. In accordance with Section 36-105 of the Code of Virginia, there shall be established within each local building department a LBBCA. Whenever a county or a municipality does not have such a BCA, the local governing body shall enter into an agreement with the local governing body of another county or municipality or with some other agency, or a state agency approved by DHCD for such appeals resulting therefrom. Fees may be levied by the local governing body in order to defray the cost of such appeals. In addition, as an authorization in this code, separate LBBCAs may be established to hear appeals of different enforcement areas such as electrical, plumbing or mechanical requirements. Each such LBBCA shall comply with the requirements of this section. The locality is responsible for maintaining a duly constituted LBBCA(s) prepared to hear appeals within the time limits established in this section. The LBBCA shall meet as necessary to assure a duly constituted board, appoint officers as necessary, and receive such training on the code as may be appropriate or necessary from staff of the locality.

Section 119.2 Membership of board. The LBBCA shall consist of at least five members appointed by the locality for a specific term of office established by written policy. Alternate members may be appointed to serve in the absence of any regular members and as such, shall have the full power and authority of the regular members. Regular and alternate members may be reappointed. Written records of current membership, including a record of the current chairman and secretary shall be maintained in the office of the locality. In order to provide continuity, the terms of the members may be of different length so that less than half will expire in any one-year period. ~~The LBBCA shall meet at least once annually to assure a duly constituted board, appoint officers as necessary, and receive such training on the code as may be appropriate or necessary from staff of the locality.~~

Supporting Statement (including intent, need, and impact of the proposal):

Meeting of an appeals board requires the locality to incur some costs. The current provisions require an annual meeting even though they may not have any appeals to hear. The code change recognizes that it is not necessary for the board to meet annually just to receive proper training or to select officers. This can be accomplished electronically or through other means such as attendance at code modules. It is important to point out that there is currently no training programs developed by DHCD specifically on appeals processes. Since many localities do not have many appeals, there may not be anyone in the locality to properly train the appeals board. In addition, there should be consideration regarding the possible perception of favoritism from the board if the code official provides the boards training. The board may want to consider requesting DHCD staff to prepare an online program for local appeals board members use which could serve as the necessary training. **There is consensus within the VBCOA Administration Committee on this Code change.**

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: John Catlett

Representing: VBCOA Admin Committee

Mailing Address: 301 King Street, Room 4200 Alexandria Va 22314

Email Address: john.catlett@alexandriava.gov

Telephone Number: 703.746.4182

Proposal Information

Code(s) and Section(s): Virginia Construction Code and Virginia Maintenance Code (119.6 and 106.6)

Proposed Change (including all relevant section numbers, if multiple sections):

Change Section 119.6 of the VCC and Section 106.6 of the VMC to read as shown:

The LBBCA shall meet within 30 calendar days after the date of receipt of the application for appeal, except that a period of up to 45 calendar days shall be permitted where the LBBCA has regularly scheduled monthly meetings. A longer time period shall be permitted if agreed to by all the parties involved in the appeal. (Remainder of sections unchanged)

Supporting Statement (including intent, need, and impact of the proposal):

This change takes into consideration a local board which has established monthly meetings to permit enough time for an appeal to be processed if it comes in too close to a regularly scheduled meeting. It adds an additional 15 days to allow for the 14 day notification to be published. This avoids a potential additional meeting and cost to the locality while providing a reasonable time for the appeal to be heard.

Submittal Information

Date Submitted: August 1, 2012

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
600 East Main Street
Suite 300
Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name (Representing): *Ken Fredgren*, Chairman, Reston Accessibility Committee of Reston Citizens Association, 703-391-9019, fredgren.k@gmail.com. (Lead contact.)

Teri Barker-Morgan, Program Manager, Virginia Board for People with Disabilities, Richmond, 804-786-9381, Teri.Barker@vbpd.virginia.gov.

Gayl Brunk, Executive Director, Valley Associates for Independent Living (VAIL), Harrisonburg, 540-433-6513, gayl@govail.org.

Marcia DuBois, Program Coordinator, Community Based Services-Field Rehabilitative Services, Department for Aging and Rehabilitative Services, Richmond, 804-662-7083, Marcia.DuBois@dars.virginia.gov.

Karen Michalski-Karney, Executive Director, Blue Ridge Independent Living Center, Roanoke, 540-342-1231, kmichalski@brilc.org.

Proposal Information

Code(s) and Section(s): USBC, Virginia Construction Code Sections 108.1 and 3411.9.5

Proposed Change (including all relevant section numbers, if multiple sections):

Add new Item #5 to Section 108.1 and add new Section 3411.9.5 to read as follows:

5. Restriping a parking lot which would be required to provide accessible parking spaces if newly constructed.

3411.9.5 Accessible parking spaces. When existing parking lots are restriped, accessible parking spaces shall be provided as required for newly constructed parking lots.

Supporting Statement (including intent, need, and cost impact of the proposal):

This proposal results from the initial review by DHCD workgroups of proposals submitted by a legislative study group (the HJR 648 study group). This proposal is offered as a compromise proposal to the one submitted by the HJR 648 study group and is being submitted by groups involved in the HJR 648 study. The compromise is to limit the language in the proposal to only that in the U.S. Department of Justice publication, "ADA Business Brief: Restriping Parking Lots," which only covers restriping. The HJR 648 study group proposal included reconfiguring and resurfacing of parking lots, which may be more difficult to enforce and extend further than the Department of Justice's concern.

Submittal Information

Date Submitted: _____

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name (Representing): *Ken Fredgren*, Chairman, Reston Accessibility Committee of Reston Citizens Association, 703-391-9019, fredgren.k@gmail.com. (Lead contact.)

Teri Barker-Morgan, Program Manager, Virginia Board for People with Disabilities, Richmond, 804-786-9381, Teri.Barker@vbpd.virginia.gov.

Gayl Brunk, Executive Director, Valley Associates for Independent Living (VAIL), Harrisonburg, 540-433-6513, gayl@govail.org.

Marcia DuBois, Program Coordinator, Community Based Services-Field Rehabilitative Services, Department for Aging and Rehabilitative Services, Richmond, 804-662-7083, Marcia.DuBois@dars.virginia.gov.

Karen Michalski-Karney, Executive Director, Blue Ridge Independent Living Center, Roanoke, 540-342-1231, kmichalski@brilc.org.

Proposal Information

Code(s) and Section(s): USBC, Virginia Construction Code Table 1106.1

Proposed Change (including all relevant section numbers, if multiple sections):

Modify table as shown:

TABLE 1106.1
ACCESSIBLE PARKING SPACES

TOTAL PARKING SPACES PROVIDED	REQUIRED MINIMUM NUMBER OF ACCESSIBLE SPACES
1 to 25	1
26 to 50	2
51 to 75	3
76 to 100	4
101 to 150	5
151 to 200	6
201 to 300	7
301 to 400	8
401 to 500	9
501 to 1000	2 3% of total
1,001 and over	20 30, plus one two for each 100, or fraction thereof, over 1,000

Supporting Statement (including intent, need, and impact of the proposal):

This proposal results from the initial review by DHCD workgroups of proposals submitted by a legislative study group (the HJR-648 study group). This proposal is offered as a compromise proposal to the one submitted by the HJR 648 study group and is being submitted by groups involved in the HJR 648 study. The compromise is only to require additional accessible parking spaces in larger parking lots whereas the HJR 648 proposal increased the number of accessible spaces across the board. It is believed that a companion proposal requiring accessible spaces to be provided, if not already present, when a parking lot is restriped, will serve to increase accessible spaces in the smaller parking lots.

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: 2011 HJR 648 Workgroup

Representing: _____

Email Address: _____

Telephone Number: _____

Proposal Information

Code(s) and Section(s): USBC, Virginia Construction Code Section 1106.3

Proposed Change (including all relevant section numbers, if multiple sections):

Change Section 1106.3 to read as follows:

1106.3 ~~Hospital-outpatient~~ Outpatient clinics and ambulatory health care facilities. At least 10 percent, but not less than one, of care recipient and visitor parking spaces provided to serve hospital outpatient clinics and ambulatory health care facilities shall be accessible.

Supporting Statement (including intent, need, and impact of the proposal):

This proposal would require slightly more accessible spaces at newly constructed outpatient clinics and ambulatory surgery centers. The IBC already requires the additional spaces for medical facilities which are on hospital campuses.

Submittal Information

Date Submitted: _____

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
The Jackson Center
501 N. 2nd Street
Richmond, VA 23219-1321

Email Address: taso@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☒ Government Entity ☐ Company

Name: Stephen Turchen

Representing: Virginia Building & Code Officials Association

Mailing Address: Suite 316 / 12055 Government Center Parkway, Fairfax, VA 22035

Email Address: Stephen.turchen@Fairfaxcounty.gov

Telephone Number: 703-324-1653

Proposal Information

Code(s) and Section(s): 2012 IECC R402.2.1

Proposed Change (including all relevant section numbers, if multiple sections):

R402.2.1 Ceilings with attic spaces. When Section R402.1.1 would require R38 in the ceiling, installing R30 over 100% of the ceiling area shall be deemed to satisfy the requirement for R38 whenever the full height of uncompressed R30 insulation extends over the wall top plate at the eaves. Similarly, when Section R402.1.1 would require R49 in the ceiling, installing R38 over 100% of the ceiling area shall be deemed to satisfy the requirement for R49 whenever the full height of uncompressed R30 insulation extends over the wall top plate at the eaves. This reduction shall not apply to the U-factor alternative approach in Section R402.1.3 and the total UA alternative in Section R402.1.4.

Supporting Statement (including intent, need, and impact of the proposal):

Revised language clarifies how to interpret the "alternative" ceiling insulation requirement. It has come to VBCOA's attention that some code officials have interpreted R402.1.1 as permitting R38 over the wall top plate when using "raised heel" or "energy" trusses, but where R49 could be installed in the interior of the attic where height permits, R49 would in fact be required in those areas. The amendment seeks to clarify that R38 could be used throughout the entire attic, where a full R38 could be installed over the top plate. This approach is consistent with US DOE analysis of heat flow through insulated attics (ca. 1996), accounting for actual insulation thicknesses and framing members. Depending on how this particular provision had been previously enforced, impact may be to reduce overall installed insulation materials in attics with no appreciable difference in heat flow rate through this part of the thermal envelope.

Submittal Information

Date Submitted: _____

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☒ Company

Name: Alan Meeks

Representing: The Marwin Company, Inc.

Mailing Address: PO Box 9126, Columbia, SC 29290

Email Address: alan@marwincompany.com

Telephone Number: 803-776-2396

Proposal Information

Code(s) and Section(s): 2012 IECC R402.2.4 Access Hatches & Doors / 2012 IRC N1102.2.4 Access Hatches & Doors

Proposed Change (including all relevant section numbers, if multiple sections):

R402.2.4 Access hatches and doors. Access doors from conditioned spaces to unconditioned spaces (e.g. attics and crawl spaces) shall be weather-stripped and insulated to a level equivalent to the insulation on the surrounding surfaces. in accordance with the following insulation values:

1. Hinged vertical doors shall have a minimum overall R-5 insulation value;

2. Hatches/scuttle hole covers shall have a minimum of R-49 insulation;
and

3. Pull down stairs shall have a minimum of 75 percent of the panel area having R-5 rigid insulation.

Access shall be provided to all equipment that prevents damaging or compressing the insulation. A wood framed or equivalent baffle or retainer is required to be provided when loose fill insulation is installed, the purpose of which is to prevent the loose fill insulation from spilling into the living space when the attic access is opened, and to and provide a permanent means of maintaining the installed R-value of the loose fill insulation."

Supporting Statement (including intent, need, and impact of the proposal):

The intent of the amendment is to provide an easier, safer and cost effective means of insulating the attic access opening while maintaining the intent of the energy code. Energy saving estimates for Chesterfield, Va. are minimal (less than 10 dollars a year) when insulating and weather-stripping beyond an R-5 minimum in the small square foot area that an attic stairway represents in an attic area. Construction savings would be a minimum of \$200. Energy Star® requirements for the same application only requires "a durable \geq R-10 insulated cover that is gasketed."

This is a revised amendment to the initial change dated August 1, 2012.

Submittal Information

Date Submitted: 10/18/12

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
600 East Main Street
Suite 300
Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: Matt Westheimer

Representing: VBCOA Energy Committee

Email Address: tmwestheimer@co.hanover.va.us

Telephone Number: (804) 365-6344

Proposal Information

Code(s) and Section(s): VCC (IECC Section R402.3.6)

Proposed Change (including all relevant section numbers, if multiple sections):

Delete Section R402.3.6 in its entirety as shown below:

~~R402.3.6 Replacement fenestration. Where some or all of an existing fenestration unit is replaced with a new fenestration product, including sash and glazing, the replacement fenestration unit shall meet the applicable requirements for U factor and SHGC in Table R402.1.1.~~

Supporting Statement (including intent, need, and impact of the proposal):

While Section R402.3.6 is addressing alterations to existing buildings and would be deleted due to Chapter 1 of the Virginia Construction Code anyway, deleting it in the IECC will make it clear that it cannot be applied.

Submittal Information

Date Submitted: 3/21/12

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)

600 East Main Street

Suite 300

Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov

Fax Number: (804) 371-7092

Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☒ Government Entity ☐ Company

Name: Bruce Cornwall

Representing: VBCOA Energy Committee

Mailing Address: 302 N Main St., Culpeper, VA 22701

Email Address: bcomwall@culpepercounty.gov

Telephone Number: 540-727-3444, Ext. 395

Proposal Information

Code(s) and Section(s): VCC (IECC R402.4.1.2.1), (IRC N1102.4.1.2.1)

Proposed Change (including all relevant section numbers, if multiple sections):

Add new Section R402.4.1.2.1 to the IECC to read as follows:

R402.4.1.2.1 Visual inspection option. Field verification by visual inspection of items listed in Table R402.4.1.1, applicable to the methods of construction, shall be an acceptable alternative to complying with Section R402.4.1.2.

Add new Section N1102.4.1.1 to the IRC to read as follows:

N1102.4.1.2.1 Visual inspection option. Field verification by visual inspection of items listed in Table N1102.4.1.1, applicable to the methods of construction, shall be an acceptable alternative to complying with Section N1102.4.1.2. When this option is chosen, it is assumed that the air infiltration rate is less than 5 air changes per hour and a whole-house mechanical ventilation shall be provided in accordance with Section R303.4.

Supporting Statement (including intent, need, and impact of the proposal):

A thorough visual inspection of the air sealing done before drywall will be more cost effective and save more energy than air sealing done after a failed blower door test.

Complying with Section R303.4 for IRC buildings will assure that adequate air changes per hour are being met.

Submittal Information

Date Submitted: 7/9/12

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)

600 East Main Street

Suite 300

Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov

Fax Number: (804) 371-7092

Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: Matt Westheimer

Representing: VBCOA Energy Committee

Email Address: tmwestheimer@co.hanover.va.us

Telephone Number: (804) 365-6344

Proposal Information

Code(s) and Section(s): VCC (IECC Section R402.4.2 and Table R402.4.1.1)

Proposed Change (including all relevant section numbers, if multiple sections):

Change Section R402.4.2 and the last row of Table 402.4.1.1 as shown:

R402.4.2 Fireplaces. New wood-burning fireplaces shall be provided with outdoor combustion air and shall have gasketed doors or tight-fitting flue dampers and outdoor combustion air.

Table R402.4.1.1

Fireplace	An air barrier shall be installed on fireplace walls. Fireplaces shall have gasketed doors <u>or tight-fitting flue dampers.</u>
-----------	--

Supporting Statement (including intent, need, and impact of the proposal):

The proposal is to permit fireplaces to either have gasketed doors or tight-fitting dampers to accommodate common practice in both site-built masonry fireplaces and factory-built fireplaces. Either method will satisfy energy conservation goals.

Submittal Information

Date Submitted: 3/21/12

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
600 East Main Street
Suite 300
Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☒ Government Entity ☐ Company

Name: Matt Westheimer

Representing: VBCOA Energy Conservation Committee

Mailing Address: 401 Lafayette Street, Williamsburg, VA. 23185

Email Address: mwest@williamsburgva.gov

Telephone Number: 757-220-6135

Proposal Information

Code(s) and Section(s): VCC (IECC R404.1)

Proposed Change (including all relevant section numbers, if multiple sections):

R404.1 Lighting equipment (Mandatory). A minimum of 75 percent of the lamps in permanently installed ~~lighting fixtures~~ luminaries shall be high-efficacy lamps or a minimum of 75 percent of the permanently installed ~~lighting fixtures~~ luminaries shall contain only high efficacy lamps.

(no change to the exception)

Supporting Statement (including intent, need, and impact of the proposal):

To make the wording when referring to lighting consistent with NEC

Submittal Information

Date Submitted: 6/25/12

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)

600 East Main Street

Suite 300

Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov

Fax Number: (804) 371-7092

Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☒ Government Entity ☐ Company

Name: Lynn Underwood, Brian Foley

Representing: City of Norfolk, Fairfax County

Mailing Address: 400 Granby, Norfolk, Virginia 23503

Email Address: lynn.underwood@norfolk.gov

Telephone Number: (757) 664-6511

Proposal Information Draft code change #1

Code(s) and Section(s): USBC new Section R602.7.4 and Table R602.7.4

Proposed Change (including all relevant section numbers, if multiple sections):

Amend Section R602.7.1 to state:

R602.7 Headers For header spans see Tables R502.5(1), R502.5(2) and R602.7.1.

Exception: Fully open porches or decks with simply supported headers used to support uniform loads that meet the requirements of Section R602.7.4.

Add a new section R602.7.4 to state:

R602.7.4 The allowable spans for nominal 2 inch double headers in bearing walls shall not exceed the spans in Table R602.7.4.

Add a new Table R602.7.4 to state:

Table R602.7.4

Maximum Spans For Headers Located Over Openings In Porches, Decks or Similar Locations (feet)

<u>Size of Headers</u>	<u>①Supporting One Floor</u>	<u>②Supporting One Roof</u>	<u>③Supporting One Floor and One Roof</u>	<u>④Supporting Two Floors and One Roof</u>
<u>2 - 2 X 4</u> <u>2 - 2 X 6</u> <u>2 - 2 X 8</u> <u>2 - 2 X 10</u> <u>2 - 2 X 12</u>				

Add a new figure R602.7.4 to illustrate:

Submittal Information

1. Please see attached calculations that form the engineering basis for the size of structural members with reduced tributary spans.
2. Please see copies of referenced documents from Section 602.6 and Table 602.6 in the 1995 edition of the One and Two Family Dwelling Code published by the Council of American Building Officials (CABO).
3. Please see supporting documentation submitted by the Home Builder's Association of Virginia (HBAV)

Supporting Statement (including intent, need, and impact of the proposal):

The 2012 International Residential Code (IRC) and its predecessors regulated the size of headers based on the provisions in Chapter Five. Note that Tables R502.5(1) and (2) has categories of building width that begins at 20 feet. The size of headers in this table assumes a rectangular tributary area that was at least 10 feet (20/2). Because of the lower end limit of 20 feet, headers over posts or columns that create porches or decks with less than 10 foot of tributary load must use that, much higher criteria. For instance a 6 foot porch with columns spaced at 10' O.C. must use 3 – 2 X 10s or 3 – 2 X 12s to comply with the code. The option for the builder is to seek an engineering rationalization to use anything different.

This table was created based on engineering principles that included analyzing for flexural bending, deflection, and horizontal shear. In addition, the design strength of lumber was set at the weakest allowed by the code for this condition and followed the standards recently created by the American Lumber Standards Committee. It is important to note that the 1995 edition of the One and Two Family Dwelling Code had a table that was very similar to this table. Note that this table is slightly more conservative when considering floor and roof loading conditions.

Date Submitted: June 15, 2012

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
Main Street Center
600 East Main Street
Richmond, VA 23219-1321

Email Address: taso@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7140 or (804) 371-7150



Practical Wall Bracing for the 2012 Virginia Residential Code

602.10 Wall bracing. Lateral load shall be resisted by braced wall panels constructed and placed in accordance with this section or, as an alternative, the 2012 International Residential Code as published by the International Code Council. Townhouses in Seismic Design Category C, buildings on elevated post or pier foundations and any building, or portion thereof, that does not comply with one or more of the bracing requirements in this section shall be designed and constructed in accordance with Section R301.1.

The building official shall be permitted to require the permit applicant to identify braced wall panels on the construction documents and provide associated analysis. The building official shall be permitted to waive the analysis of the upper floors where the cumulative length of wall openings of each upper floor wall is less than or equal to the wall directly below.

R602.10.1 Sheathing materials. The following sheathing materials shall be used to construct a braced wall panel. Exterior walls shall be sheathed on all sheathable surfaces including infill areas between braced wall panels, above and below wall openings and on gable end walls.

1. Wood structural panels with a minimum thickness of $\frac{7}{16}$ inch (9.5 mm) fastened in accordance with Table R602.3(3).
2. Structural fiberboard sheathing with a minimum thickness of $\frac{1}{2}$ inch (12.7 mm) fastened in accordance with Table R602.3(1).
3. Gypsum board on interior walls with a minimum thickness of $\frac{1}{2}$ inch (12.7 mm) fastened in accordance with Table R702.3.5.

R602.10.2 Braced wall panels. Braced wall panels shall be full-height wall sections sheathed with the materials listed in Section R602.10.1 and complying with following.

1. Exterior braced wall panels shall have a minimum length of 36 inches (914 mm).
 - 1.1 Braced wall panels sheathed in wood structural panels shall be permitted to be reduced to a length specified in Table R602.10.2 where edge nailing is reduced to 4 inches (102 mm) on center. Panels with openings on both sides of differing heights shall be governed by the taller opening when determining panel length.

TABLE R602.10.2
PANEL LENGTH REDUCTIONS ^a


Adjacent clear opening height (inches)	Minimum Panel Length				
	Wall Height				
	8 feet	9 feet	10 feet	11 feet	12 feet
≤ 64	24	27	30	33	36
≤ 72	27	27	30	33	36

^a Interpolation shall be permitted; extrapolation shall be prohibited.

1.2 Braced wall panels sheathed in wood structural panels shall be permitted to be reduced to a length of 24 inch (610 mm) where adjacent to a garage door opening of a one-story garage.

2. Interior braced wall panels shall have a minimum length of 48 inches (1220 mm) when sheathing material is applied to one side. Doubled sided applications shall be permitted to be considered two braced wall panels.
3. Portal frame braced wall panels shall have a minimum length as specified in Section R602.10.7.
4. Exterior braced wall panels, other than portal frames, shall have a finish material installed on the interior. The finish material shall consist of $\frac{1}{2}$ inch (12.7 mm) gypsum board or equivalent and shall be permitted to be omitted where the required length of bracing, as determined in Section R602.10.4, is multiplied by 1.40, unless otherwise required by Section R302.6.
5. Vertical sheathing joints shall occur over and be fastened to common studs.
6. Horizontal sheathing joints shall be edge nailed to $1\frac{1}{2}$ inch (38 mm) minimum thick common blocking.

R602.10.3 Circumscribed rectangle. Required length of bracing shall be determined by circumscribing one or more rectangles around the entire building or portions thereof, as shown in Figure R602.10.3. Rectangles shall surround all enclosed offsets and projections such as sunrooms and attached garages. Chimneys, partial height projections, and open structures, such as carports and decks, shall be excluded from the rectangle. Each rectangle shall have no side greater than 60 feet (18 288 mm) with a maximum 3:1 ratio between the long side and short side. Rectangles shall be permitted to be skewed to accommodate diagonal walls.



R602.10.3.1 Townhouses. Rectangles shall be circumscribed around individual townhouses.

R602.10.4 Required length of bracing. The required length of bracing for each side of a circumscribed rectangle shall be determined using Table R602.10.4. The cumulative contributing length of braced wall panels assigned to a rectangle side shall be greater than or equal to the required length of bracing. As shown in Figure R602.10.4, braced wall panels shall be assigned and contribute to the applicable rectangle side as specified below.

1. Exterior braced wall panels shall be assigned to the parallel rectangle side on which they are located or in which they face and shall contribute their actual length.
2. Interior braced wall panels shall be assigned to the parallel rectangle side on which they are located or in which they face up to 4 feet (1220 mm) away. Interior braced wall panels sheathed in gypsum board shall contribute 0.5 times their actual length. Interior braced wall panels sheathed in wood structural panel or structural fiberboard shall contribute their actual length.
3. Projected contributing lengths of angled braced wall panels shall be assigned to the closest rectangle sides.
4. Portal frame braced wall panels shall contribute 1.5 times their actual length to their assigned rectangle side.

TABLE R602.10.4
REQUIRED LENGTH OF BRACING ALONG EACH SIDE OF A CIRCUMSCRIBED RECTANGLE ^{a, b, c}

WIND SPEED	EAVE-TO RIDGE HEIGHT (FEET)	NUMBER OF LEVELS ABOVE	REQUIRED LENGTH OF BRACING ON FRONT/REAR SIDE						REQUIRED LENGTH OF BRACING ON LEFT/RIGHT SIDE					
			Length of left/right side (ft)						Length of front/rear side (ft)					
			10	20	30	40	50	60	10	20	30	40	50	60
90	10	None	2.0	3.5	5.0	6.0	7.5	9.0	2.0	3.5	5.0	6.0	7.5	9.0
		One story	3.5	6.5	9.0	12.0	14.5	17.0	3.5	6.5	9.0	12.0	14.5	17.0
		Two stories	5.0	9.5	13.5	17.5	21.5	25.0	5.0	9.5	13.5	17.5	21.5	25.0
	15	None	2.6	4.6	6.5	7.8	9.8	11.7	2.6	4.6	6.5	7.8	9.8	11.7
		One story	4.0	7.5	10.4	13.3	16.7	19.6	4.0	7.5	10.4	13.3	16.7	19.6
		Two stories	5.5	10.5	14.9	19.3	23.7	27.5	5.5	10.5	14.9	19.3	23.7	27.5
	20	None	2.9	5.2	7.1	8.8	11.1	13.2	2.9	5.2	7.1	8.8	11.1	13.2
		One story	4.5	8.5	11.8	15.6	18.9	22.1	4.5	8.5	11.8	15.6	18.9	22.1
		Two stories	6.2	11.9	16.8	21.8	27.3	31.1	6.2	11.9	16.8	21.8	27.3	31.1
100	10	None	2.5	4.0	6.0	7.5	9.5	11.0	2.5	4.0	6.0	7.5	9.5	11.0
		One story	4.5	8.0	11.0	14.5	18.0	21.0	4.5	8.0	11.0	14.5	18.0	21.0
		Two stories	6.0	11.5	16.5	21.5	26.5	31.0	6.0	11.5	16.5	21.5	26.5	31.0
	15	None	3.4	5.2	7.8	9.8	12.4	14.9	3.4	5.2	7.8	9.8	12.4	14.9
		One story	5.2	9.2	12.7	16.7	20.7	24.2	5.2	9.2	12.7	16.7	20.7	24.2
		Two stories	6.6	12.7	18.2	23.7	29.2	34.1	6.6	12.7	18.2	23.7	29.2	34.1
	20	None	3.8	5.9	8.8	11.1	14.0	16.2	3.8	5.9	8.8	11.1	14.0	16.2
		One story	5.9	10.4	14.4	18.9	23.4	27.3	5.9	10.4	14.4	18.9	23.4	27.3
		Two stories	7.5	14.4	20.6	26.8	33.0	38.5	7.5	14.4	20.6	26.8	33.0	38.5

For SI: 1 ft = 304.8 mm

^a. Interpolation shall be permitted; extrapolation shall be prohibited.

^b. For Exposure Category C, multiply the required length of bracing by a factor of 1.30.

^c. Wall height adjustment: multiply the required length of bracing by the following factors: 0.90 for 8 feet (2438 mm), 0.95 for 9 feet (2743 mm), 1.0 for 10 feet (3048 mm), 1.05 for 11 feet (3353 mm) and 1.10 for 12 feet (3658 mm).




FIGURE R602.10.4
REQUIRED LENGTH OF BRACING

R602.10.4.1 Common sides of multiple rectangles. Where multiple rectangles share a common side or sides, as shown in Figure R602.10.4, the required length of bracing shall equal the sum of the required lengths from all shared rectangle sides.

R602.10.4.2. Common sides with skewed rectangles. Braced wall panels located on a common wall where skewed rectangles intersect, as shown in Figure R602.10.4.2, shall be permitted to apply its contributing length towards the required length of bracing for the parallel rectangle side and its projected contributing lengths towards the adjacent skewed rectangle sides.





FIGURE R602.10.4.2
COMMON SIDES WITH SKEWED RECTANGLES

R602.10.5 Cripple walls and framed walls of walk-out basements. For cripple walls with a maximum height of 48 inches (1220 mm) or less along its entire length, the required length of bracing shall be equal to the wall above. For rectangles constructed with cripple walls with a height greater than 48 inches (1220 mm) at any location along its length or for framed walls of a walk-out basement, the required length of bracing shall be determined using Table R602.10.4. All cripple walls and walls of walk-out basements shall comply with item 5 of Section R602.10.2.

R602.10.6 Distribution of braced wall panels. Braced wall panels shall be distributed in accordance with the following requirements as shown in Figure R602.10.6.

1. The edge of a braced wall panel shall be no more than 12 feet (3658 mm) from any wall corner.
2. The distance between adjacent edges of braced wall panels shall be no more than 20 feet (6096 mm).
3. Segments of exterior walls greater than 8 feet (2438 mm) in length shall have a minimum of one braced wall panel.
4. Segments of exterior wall 8 feet (2438 mm) or less in length shall be permitted to have no bracing.
5. Interior and exterior wall segments which contribute to the common sides of multiple rectangles shall be permitted to apply the distribution requirements to each wall segment independently.




For SI: 1 ft = 304.8 mm

FIGURE R602.10.6
DISTRIBUTION OF BRACED WALL PANELS

R602.10.6.1 Braced wall panels adjacent balloon framed walls. Braced wall panels shall be placed on each side of each story adjacent to balloon framed walls designed in accordance with Section R602.3 with a maximum height of two stories.

R602.10.7 Portal frames. Portal frames shall be constructed in accordance with Figure R602.10.7.




For SI: 1 inch = 25.4 mm, 1 foot = 305 mm, 1 lb = 4.45 N

FIGURE R602.10.7
PORTAL FRAME PANEL CONSTRUCTION

R602.10.8 Bracing connections. Braced wall panels shall be connected to other structural elements in accordance with this sections R602.10.8.1 through R602.10.8.3.

R602.10.8.1 Connections to foundation. Braced wall panels shall be connected to the foundation per Section R403.1.6 and as required in Figure R602.10.7. Masonry stem walls with a length of 48 inches (1220 mm) or less supporting braced wall panels shall be reinforced in accordance with Figure R602.10.8.1. Concrete stem walls with a length of 48 inches (1220 mm) or less, a height greater than 12 inches (305 mm) and a thickness less than 6 inches (152 mm) shall have reinforcement sized and located in accordance with Figure R602.10.8.1.



For SI: 1 in=25.4 mm

FIGURE R602.10.8.1
MASONRY STEM WALLS SUPPORTING BRACED WALL PANELS


R602.10.8.2 Connections to floor framing. When parallel to floor framing, braced wall panels shall be connected to a band, rim or header joist or floor framing. When perpendicular to floor framing, braced wall panels shall be connected to full-height solid blocking between floor framing. Attachments shall be in accordance with Table R602.3(1). Manufactured lumber or truss blocking panels shall be permitted to substitute for full-height solid blocking.

R602.10.8.3 Connections to roof framing. When parallel to roof framing, braced wall panels shall be connected to a band, rim or header joist, or roof truss. When perpendicular to roof framing, the top plates of exterior braced wall panels shall be connected to the rafters or roof trusses above in accordance with Table R602.10.8.3 and fastened in accordance with Table R602.3(1).

TABLE R602.10.8.3
BRACED WALL PANEL CONNECTIONS TO PERPENDICULAR ROOF FRAMING


DISTANCE FROM TOP OF BRACED WALL PANEL TO TOP OF RAFTER OR ROOF TRUSS, (in)	REQUIREMENT	REFERENCED FIGURE
≤ 9.25	No blocking required	NA
9.25 – 15.25	Solid 2x blocking between rafters or trusses	R602.10.8.3(1)
15.25 – 48	Vertical blocking panels	R602.10.8.3(2)
> 48	Designed in accordance with accepted engineering practice	NA

For SI: 1 inch = 25.4 mm




For SI: 1 inch = 25.4 mm

FIGURE R602.10.8.3(1)
BRACED WALL PANEL CONNECTION TO PERPENDICULAR RAFTERS



A SECTION



B ELEVATION

FIGURE R602.10.8.3(2)
BRACED WALL PANEL CONNECTION TO PERPENDICULAR RAFTERS OR ROOF TRUSSES

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☒ Company

Name: Jim Harrell

Representing: Blue Ridge Masonry Association

Mailing Address: 120 Wood Pine Drive, Stoneville, NC 27048

Email Address: jharrell@triad.rr.com

Telephone Number: (336)548-5815

Proposal Information

Code(s) and Section(s): IRC R1001.8

Proposed Change (including all relevant section numbers, if multiple sections):

Smoke chamber walls shall be constructed of *solid masonry* units, hollow masonry units grouted solid, stone or concrete. The total minimum thickness of front, back and side walls shall be 8 inches (203mm) of *solid masonry*. ~~When the inside surface of the smoke chamber is formed by corbelled masonry, the inside surface shall be parged smooth with refractory mortar conforming to ASTM C 199. When a lining of firebrick at least 2 inches (51mm) thick, or a lining of vitrified clay at least 5/8 inch (16mm) thick is provided, the total minimum thickness of front, back and side walls shall be 6 inches (152mm) of *solid masonry*, including the lining. Firebrick shall conform to ASTM C 1261 and be laid with medium duty refractory mortar conforming to ASTM C 199. Vitrified clay linings shall conform to ASTM C 315.~~

Supporting Statement (including intent, need, and impact of the proposal):

The noted Section is inconsistent with Section R1001.5 in regards to standard masonry wall thickness for fireplaces, which are typically exposed to more extreme temperatures. Safety is assured with the minimum thickness of solid masonry prescribed. Nonaqueous mortars are not practical for applying in the thicknesses required for constructing and parging the smoke chamber. Refractory mortar is not a readily available product which adds considerable cost and inconsistent enforcement, without the benefit of increasing the level of safety from historically proven industry standard practices.

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: DHCD Workgroup 4, sub-workgroup 2 (pools and marinas)

Proposal Information

Code(s) and Section(s): VCC (IBC and IRC)

Proposed Change (including all relevant section numbers, if multiple sections):

In Chapter 2 of the IBC, change the following definition to read as follows:

Swimming pool. An aquatic vessel as defined in the International Swimming Pool and Spa Code. Where the use of the term is indicative of a specific type of aquatic vessel, such as a public swimming pool or a residential swimming pool, then the term may be deemed to mean that specific type of aquatic vessel.

Change the title of Section 3109 of the IBC to read as follows and replace the text of Section 3109 with the following:

Section 3109

Swimming Pools, Swimming Pool Enclosures and Aquatic Recreational Facilities

3109.1 General. Swimming pools, swimming pool enclosures and aquatic recreational facilities, as that term is defined in the International Swimming Pool and Spa Code, shall comply with applicable provisions of the International Swimming Pool and Spa Code.

Change Items 27 and 28 of Section 310.6 of the VCC(IBC) to read as follows:

27. Add Section R325 Swimming Pools, Spas and Hot Tubs.

28. Add Section R325.1 to read:

R325.1 Use of Appendix G for swimming Swimming pools, spas and hot tubs. In addition to other applicable provisions of this code, swimming pools, spas and hot tubs as defined in the Virginia Construction Code, shall comply with the applicable provisions of Appendix G the International Swimming Pool and Spa Code.

Supporting Statement (including intent, need, and impact of the proposal):

This proposal will incorporate the International Swimming Pool and Spa Code (ISPSC) for the construction of aquatic vessels, as defined by the ISPSC, which includes both residential and public swimming pools, spas and hot tubs. This proposal would also have the ISPSC apply to the construction of new aquatic recreational facilities, such as wave pools or lazy rivers. The existing exception for when a permit is needed for a pool is left intact, however the threshold for what constitutes a pool under the ISPSC is different than what is currently under the IBC, reducing the depth of water from 24 inches to 12 inches, but not applying unless the aquatic vessel is designed to have a circulating system.

Submittal Information

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: DHCD Workgroup 4, sub-workgroup 2 (pools and marinas)

Proposal Information

Code(s) and Section(s): VCC (IBC and IPC)

Proposed Change (including all relevant section numbers, if multiple sections):

Change Section 303.6 of the IBC as shown:

303.6 Assembly Group A-5. Assembly used intended for participation in or viewing outdoor activities including, but not limited to:

Amusement park structures
Bleachers
Grandstands
Stadiums
Swimming pools

Change the Group A-5 row of Table 403.1 of the IPC and Table 2902.1 of the IBC and add a new footnote "h" as shown:

OCCUPANCY	DESCRIPTION	(remainder unchanged)
A-5	Stadiums, amusement parks, <u>pools</u> , bleachers and grandstands for outdoor sporting events and activities ^h	(remainder unchanged)

h. The occupant load for pools shall be in accordance with the "Skating rinks, swimming pools" category of Table 1004.1.2 of the International Building Code (of "this code" for the IBC table).

Supporting Statement (including intent, need, and impact of the proposal):

This proposal is to set minimum plumbing fixture requirements for bathrooms at outdoor swimming pools to correlate with requirements of the Virginia Department of Health (VDH) for fixtures at swimming pools under their authority as a matter of functional design and to permit VDH to delete the requirements in their regulations since they could be perceived as "building regulations" which would be superseded by the USBC.

Submittal Information

Date Submitted: _____

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☒ Organization

Name: J. Kenneth Payne, Jr., AIA

Representing: VSAIA

Mailing Address: 3200 Norfolk Street, Richmond, VA 23230

Email Address: kpayne@moseleyarchitects.com

Telephone Number: 804.794.7555

Proposal Information

Code(s) and Section(s): 2012 ISPSC, Table of Contents, and Sections 410 and 609.3.1

Proposed Change (including all relevant section numbers, if multiple sections):

Revise Table of Contents, as follows:

CHAPTER 6 AQUATIC RECREATION FACILITIES

609 ~~Toilet Rooms and Bathrooms~~ Dressing and Sanitary Facilities

Add new Section 410.2, as follows:

410.2 Showers. Showers shall be in accordance with Sections 410.2.1 through 410.2.5.

410.2.1 Deck hand shower or shower spray unit. Not less than one and not greater than half of the total number of showers required by Section 410.1 shall be a hand shower or spray shower unit located on the deck of or at the entrance of each pool.

410.2.2 Anti-scald device. Where heated water is provided to the showers, the shower water supply shall be controlled by an anti-scald device.

410.2.3 Water heater and mixing valve. Bather access to water heaters and thermostatically controlled mixing valves for showers shall be prohibited.

410.2.4 Flow rate. Each showerhead shall have a water flow of not less than 2 gallons per minute (7.6 lpm).

410.2.5 Temperature. At each showerhead, the heated shower water temperature shall not exceed 120°F (49°C) and shall not be less than 90°F (32°C).

Revise title of Section 609, as follows:

SECTION 609
TOILET ROOMS AND BATHROOMS DRESSING AND SANITARY FACILITIES

Revise Section 609.3.1, as follows:

609.3.1 Deck hand shower or shower spray unit. Not less than one ~~shower~~ and not greater than half of the total number of showers required by Section 609.2 shall be a hand shower or shower spray unit located on the deck of or at the entrance of each pool.

Supporting Statement (including intent, need, and impact of the proposal):

Revised the title of Section 609 to be the same as Section 410, and because Section 609.3.1 includes showers that are required on the pool deck, which is not a part of a *toilet room* or *bathroom* – but are a part of *sanitary facilities*. In this case, the term “sanitary facilities” is more inclusive than the terms “toilet room” or “bathroom” when it comes to a showerhead on a pool deck.

The Sub-workgroup 2 ISPSC Committee felt public swimming pools (or anything governed by Chapter 4) should also have a showerhead facility on the pool deck. The language is duplicated from Section 609.3.

The terms “hand shower” (term used by ICC A117.1) and “shower spray unit” (term used by the 2004 ADAAG) are substituted for the term “shower(s)” to avoid the interpretation that full-size transfer and/or roll-in type showers would need to be provided to meet the accessibility requirements for “showers” (which include grab bars, seats, dispensers, etc.). By using the terms “hand shower” and “shower spray unit,” it is clear the intent is not to provide a transfer and/or roll-in type shower with grab bars or seats, but merely a showerhead with controls that must meet the accessibility requirements for a hand-held showerhead.

Submittal Information

Date Submitted: August 16, 2012

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
300 East Main Street
Suite 300
Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☒ Government Entity ☐ Company

Name: Frank Castelvocchi, III PE

Representing: County of Henrico Building Inspections

Mailing Address: PO Box 90775, Henrico VA 23273

Email Address: cas13@co.henrico.va.us

Telephone Number: 804 501 4375

Proposal Information

Code(s) and Section(s): IBC and IFC [F] 907.2.3

Proposed Change (including all relevant section numbers, if multiple sections):

[F] 907.2.3 Group E.

A manual fire alarm system that ~~initiates~~ activates the occupant notification signal ~~utilizing an emergency voice/alarm communication~~ system meeting the requirements of Section 907.5.2.2 and installed in accordance with Section 907.6 shall be installed in Group E occupancies. When *automatic sprinkler systems* or smoke detectors are installed, such systems or detectors shall be connected to the building fire alarm system.

Exceptions:

1. A manual fire alarm system is not required in Group E occupancies with an *occupant load* of ~~30~~ 50 or less.
2. Manual fire alarm boxes are not required in Group E occupancies where all of the following apply:
 - 2.1. Interior *corridors* are protected by smoke detectors.
 - 2.2. Auditoriums, cafeterias, gymnasiums and similar areas are protected by *heat detectors* or other *approved* detection devices.
 - 2.3. Shops and laboratories involving dusts or vapors are protected by *heat detectors* or other *approved* detection devices.
3. Manual fire alarm boxes shall not be required in Group E occupancies where the building is equipped throughout with an *approved automatic sprinkler system* installed in accordance with Section 903.3.1.1, the ~~emergency voice/alarm communication~~ occupant notification system will activate on sprinkler water flow and manual activation is provided from a normally occupied location.

Supporting Statement (including intent, need, and impact of the proposal):

This proposed change is to maintain the requirements currently in the 2009 USBC for educational occupancies. Requiring a voice alarm system for educational uses will impose significant unnecessary costs to daycares and school systems that are already short of funds. Most schools already have public address systems that can be used for emergency notification. No other occupancy requires voice alarms until you reach 1000 occupants or a high rise building.

Changing the threshold from 50 to 30 would impose this requirement on most school trailers and small daycare centers by moving the classroom size from 1000 sq ft to 600 sq ft. Requiring an expensive voice alarm system in a school trailer or small storefront daycare center is a ludicrous imposition of significant costs to schools and small businesses.

There is no record of fire deaths and injuries in these occupancies to justify these added expenses. The children in these occupancies are required to be under competent adult supervision.

Submittal Information

Date Submitted: 9/28/12

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR SBCO (State Building Codes Office)
600 East Main Street
Suite 300
Richmond, VA 23219

Email Address: Vernon.hodge@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information (Check one):

☐ Individual ☐ Government Entity ☐ Company

Name: Workgroup 4, Subgroup 1

Representing:

Proposal Information

Code(s) and Section(s): VCC, International Plumbing Code, Chapter 13

Proposed Change (including all relevant section numbers, if multiple sections):

See attached.

Supporting Statement (including intent, need, and cost impact of the proposal):

This proposal to add provisions for gray water, rainwater and reclaimed water for non-potable use was a collaborative effort of stakeholders forming a subworkgroup from DHCD's Workgroup 4 for trade code issues. Many state agencies participated including the Virginia Department of Environmental Quality and the Virginia Department of Health. Also participating were the Virginia Building and Code Officials Association and the Virginia Plumbing and Mechanical Inspectors Association as well as independent consultants and companies involved in designing such systems. The Virginia Society of the American Institute of Architects also participated.

Submittal Information

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR SBCO (State Building Codes Office)
600 East Main Street
Suite 300
Richmond, VA 23219

Email Address: Vernon.hodge@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7150



Chapter 2 Definitions - Add new terms as follows:

Non-potable water systems. Water systems for the collection, treatment, storage, distribution and use or reuse of non-potable water. Non-potable systems include reclaimed water, rainwater and gray water systems.

Reclaimed water. Reclaimed water means water resulting from the treatment of domestic, municipal or industrial wastewater that is suitable for a water reuse that would not otherwise occur. Specifically excluded from this definition is "gray water."

Rainwater. Natural precipitation, including snow melt, from roof surfaces only.

Gray Water . Water discharged from lavatories, bathtubs, showers, clothes washers and laundry trays

Non-Potable fixtures and outlets. Fixtures and outlets that are not dependent on potable water for the safe operation to perform their intended use. Such fixtures and outlets may include, but are not limited to, water closets, urinals, irrigation, mechanical equipment and hose connections to perform operations, such as vehicle washing and lawn maintenance.

Stormwater. Precipitation that is discharged across the land surface or through conveyances to one or more waterways and that may include stormwater runoff, snow melt runoff, and surface runoff and drainage.

Modify and add new sections to existing text in the Sections below as follows

IPC 301.3 - Exception: Bathtubs, showers, lavatories, clothes washers and laundry trays shall not be required to discharge to the sanitary drainage system where such fixtures discharge to an approved non-potable gray water system in accordance with applicable provisions of Chapter 13.

(Add new section as follows) **IPC 602.2.1. Non-potable fixtures and outlets.** Non-potable water shall be permitted to serve non-potable type fixtures and outlets in accordance with Chapter 13.

IPC 1101.2. Where required. To remain unchanged

(Add new exception as follows) **Exception:** Rainwater non-potable water systems shall be permitted in accordance with Chapter 13.

Add new Chapter 13 Non-Potable Water Systems

1301 General

1302 Gray Water Systems

1303 Rainwater Water Systems

1304 Reclaimed Water Systems

CHAPTER 13

NON-POTABLE WATER SYSTEMS SECTION 1301

GENERAL

1301.1 Scope. The provisions of Chapter 13 shall govern the materials, design, construction and installation of non-potable water systems subject to this code. In addition to the applicable provision of this Section, Reclaimed water shall comply with the requirements of Section 1304.

1301.1.1 Design of non-potable water systems. All portions of non-potable water systems subject to this code shall be constructed using the same standards and requirements for the potable water systems or drainage systems as provided for in this code unless otherwise specified in this Chapter.

1301.2 Makeup water. Makeup water shall be provided for all non potable water supply systems. The makeup water system shall be designed and installed to provide supply of water in the amounts and at the pressures specified in this code. The makeup water supply shall be potable and be protected against backflow in accordance with the applicable requirements of Section 608.

1301.2.1 Makeup water Sources. Potable water shall be provided as makeup water for reclaimed water systems. Non potable water shall be permitted to serve as make up water for gray water and rainwater systems.

1301.2.2 Makeup water supply valve. A full-open valve shall be provided on the makeup water supply line.

1301.2.3 Control valve alarm. Makeup water systems shall be fitted with a warning mechanism that alerts the user to a failure of the inlet control valve to close correctly. The alarm shall activate before the water within the storage tank begins to discharge into the overflow system.

1301.3 Sizing. Non potable water distribution systems shall be designed and sized for peak demand in accordance with approved engineering practice methods that comply with the applicable provisions of Chapter 6.

1301.4 Signage required. All non-potable water outlets, other than water closets and urinals, such as hose connections, open ended pipes, and faucets shall be identified at the point of use for each outlet with signage that reads as follows: "Non-potable water is utilized for [application name]. Caution: non-potable water. DO NOT DRINK." The words shall be legibly and indelibly printed on a tag or sign constructed of corrosion-resistant waterproof material or shall be indelibly printed on the fixture. The letters of the words shall be not less than 0.5 inches in height and in colors in contrast to the background on which they are applied. The pictograph shown in Figure 1301.4 shall appear on the signage required by this section.




Figure 1301.4 – Pictograph DO NOT DRINK

1301.5 Potable water supply system connections. Where a *potable* water supply system is connected to a non-potable water system, the *potable* water supply shall be protected against backflow in accordance with the applicable provisions of Section 608.

1301.6 Non-potable water system connections. Where a non-potable water system is connected and supplies water to another non-potable water system, the non-potable water system that supplies water shall be protected against backflow in accordance with the applicable provisions of Section 608.

1301.7 Approved components and materials. Piping, plumbing components, and materials used in the non-potable water drainage and distribution systems shall be *approved* for the intended application and compatible with the water and any disinfection or treatment systems used.

1301.8 Insect and vermin control. Non-potable water systems shall be protected to prevent the entrance of insects and vermin into storage and piping systems. Screen materials shall be compatible with system material and shall not promote corrosion of system components.

1301.9 Freeze protection. Non-potable water systems shall be protected from freezing in accordance with the applicable provisions of Chapter 3.

1301.10 Non-potable water storage tanks. Non-potable water storage tanks shall be approved for the intended application and comply with Sections 1301.10.1 through 1301.10.12.

1301.10.1 Sizing. The holding capacity of storage tanks shall be sized for the intended use.

1301.10.2 Inlets. *Storage tank* inlets shall be designed to introduce water into the tank and avoid agitating the contents of the *storage tank*. The water supply to *storage tanks* shall be controlled by fill valves or other automatic supply valves designed to stop the flow of incoming water before the tank contents reach the overflow pipes.

1301.10.3 Outlets. Outlets shall be located at least 4 inches (102 mm) above the bottom of the *storage tank*, and shall not skim water from the surface.

1301.10.4 Materials and Location. Storage tanks shall be constructed of material compatible with treatment systems used to treat water. Above grade storage vessels shall be constructed using opaque, UV-resistant materials such as tinted plastic, lined metal, concrete, wood, or painted to prevent algae growth. Above grade storage tanks shall be protected from direct sunlight unless their design specifically incorporates the use of the sunlight heat transfer. Wooden storage tanks shall be provided with a flexible liner. Storage tanks and their manholes shall not be located directly under soil or waste piping or sources of contamination.

1301.10.5 Foundation and supports. Storage tanks shall be supported on a firm base capable of withstanding the storage tank's weight when filled to capacity. Storage tanks shall be supported in accordance with the applicable provisions of the *International Building Code*.

1301.10.5.1 Ballast. Where the soil can become saturated, an underground storage tank shall be ballasted, or otherwise secured, to prevent the effects of buoyancy. The combined weight of the tank and hold down ballast shall meet or exceed the buoyancy force of the tank. Where the installation requires a foundation, the foundation shall be flat and shall be designed to support the storage tank weight when full, consistent with the bearing capability of adjacent soil.

1301.10.5.2 Structural support. Where installed below grade, storage tank installations shall be designed to withstand earth and surface structural loads without damage.

1301.10.6 Overflow. The storage tank shall be equipped with an overflow pipe having a diameter not less than that shown in Table 606.5.4. The overflow outlet shall discharge at a point not less than 6 inches (152 mm) above the roof or roof drain; floor or floor drain; or over an open water-supplied fixture. The overflow outlet shall terminate through a check valve. Overflow pipes shall not be directed on walkways. The overflow drain shall not be equipped with a shutoff valve. A minimum of one cleanout shall be provided on each overflow pipe in accordance with the applicable provisions of Section 708.

1301.10.7 Access. A minimum of one access opening shall be provided to allow inspection and cleaning of the tank interior. Access openings shall have an approved locking device or other approved method of securing access. Below grade storage tanks, located outside of the building, shall be provided with either a manhole not less than 24 inches (610 mm) square or a manhole with an inside diameter not less than 24 inches (610 mm). The design and installation of access openings shall prohibit surface water from entering the tank. Each manhole cover shall have an approved locking device or other approved method of securing access.

Exception: Storage tanks under 800 gallons in volume installed below grade shall not be required to be equipped with a manhole, but shall have an access opening not less than 8 inches (203 mm) in diameter to allow inspection and cleaning of the tank interior.

1301.10.8 Venting. Storage tanks shall be vented. Vents shall not be connected to sanitary drainage system. Vents shall be at least equal in size to the internal diameter of the drainage inlet pipe(s) connected to the tank. Where installed at grade, vents shall be protected from contamination by means of a U-bend installed with the opening directed downward. Vent outlets shall extend a minimum of 12" above grade, or as necessary to prevent surface water from entering the storage tank. Vent openings shall be protected against the entrance of vermin and insects. Vents serving gray water tanks shall terminate in accordance with the applicable provisions of Section 903 and 1301.8.

1301.10.9 Drain. Where drains are provided they shall be located at the lowest point of the *storage tank*. The tank drain pipe shall discharge as required for overflow pipes and shall not be smaller in size than specified in Table 606.5.7. A minimum of one cleanout shall be provided on each drain pipe in accordance with Section 708.

1301.10.10 Labeling and signage. Each non-potable water storage tank shall be *labeled* with its rated capacity and the location of the upstream bypass valve. Underground and otherwise concealed storage tanks shall be labeled at all access points. The label shall read "CAUTION: NON-POTABLE WATER – DO NOT DRINK". Where an opening is provided that could allow the entry of personnel, the opening shall be marked with the words, "DANGER – CONFINED SPACE." Markings shall be indelibly printed on a tag or sign constructed of corrosion-resistant waterproof material mounted on the tank or shall be indelibly printed on the tank. The letters of the words shall be not less than 0.5 inches in height and shall be of a color in contrast with the background on which they are applied.

1301.10.11 Storage tank tests. Storage tanks shall be tested in accordance with the following:

1. Storage tanks shall be filled with water to the overflow line prior to and during inspection. All seams and joints shall be left exposed and the tank shall remain water tight without leakage for a period of 24 hours.
2. After 24 hours, supplemental water shall be introduced for a period of 15 minutes to verify proper drainage of the overflow system and verify that there are no leaks.
3. Following a successful test of the overflow, the water level in the tank shall be reduced to a level that is at 2 inches below the makeup water off set point. The tank drain shall be observed for proper operation. The makeup water system shall be observed for proper operation, and successful automatic shutoff of the system at the refill threshold shall be verified. Water shall not be drained from the overflow at any time during the refill test.
4. Air tests shall be permitted in lieu of water testing as recommended by the tank manufacturer or the tank standard.

1301.10.12 Structural strength. Storage tanks shall meet the applicable structural strength requirements of the International Building Code.

1301.11 Trenching requirements for non-potable water system piping. Underground non-potable water system piping shall be horizontally separated from the *building sewer* and *potable* water piping by 5 feet (1524 mm) of undisturbed or compacted earth. Non-potable water system piping shall not be located in, under or above sewage systems cesspools, septic tanks, septic tank drainage fields or seepage pits. Buried non-potable system piping shall comply with the requirements of this code for the piping material installed.

Exceptions:

1. The required separation distance shall not apply where the bottom of the non-potable water pipe within 5 feet (1524 mm) of the sewer is equal or greater than 12 inches (305 mm) above the top of the highest point of the sewer and the pipe materials conforms to Table 702.3.
2. The required separation distance shall not apply where the bottom of the potable water service pipe within 5 feet (1524 mm) of the non-potable water pipe is a minimum of 12 inches (305 mm) above the top of the highest point of the non-potable water pipe and the pipe materials comply with the requirements of Table 605.4
3. Non-potable water pipe is permitted to be located in the same trench with building sewer piping, provided that such sewer piping is constructed of materials that comply with the requirements of Table 702.2.
4. The required separation distance shall not apply where a non-potable water pipe crosses a sewer pipe, provided that the pipe is sleeved to at least 5 feet (1524 mm) horizontally from the sewer pipe centerline on both sides of such crossing with pipe materials that comply with Table 702.2.
5. The required separation distance shall not apply where a potable water service pipe crosses a non-potable water pipe provided that the potable water service pipe is sleeved for a distance of at least 5 feet (1524 mm) horizontally from the centerline of the non-potable pipe on both sides of such crossing with pipe materials that comply with Table 702.2.

1301.12 Outdoor outlet access. Sillcocks, hose bibs, wall hydrants, yard hydrants, and other outdoor outlets that are supplied by non-potable water shall be located in a locked vault or shall be operable only by means of a removable key.

1301.13 Drainage and vent piping and fittings. Non-potable drainage and vent pipe and fittings shall comply with the applicable material standards and installation requirements in accordance with provisions of Chapter 7.

1301.14.1. Labeling and marking. Identification of non-potable drainage and vent piping shall not be required.

1301.14 Pumping and control system. Mechanical equipment including pumps, valves and filters shall be accessible and removable in order to perform repair, maintenance and cleaning. The minimum flow rate and flow pressure delivered by the pumping system shall be designed for the intended application in accordance with the applicable provisions of Section 604.

1301.15 Water-pressure reducing valve or regulator. Where the water pressure supplied by the pumping system exceeds 80 psi (552 kPa) static, a pressure-reducing valve shall be installed to reduce the pressure in the non-potable water distribution system piping to 80 psi (552 kPa) static or less. Pressure-reducing valves shall be specified and installed in accordance with the applicable provisions of Section 604.8.

1301.16 Distribution pipe. *Distribution piping* utilized in non-potable water stems shall comply with Sections 1301.16.1 through 1301.16.4.

1301.16.1 Materials, joints and connections. *Distribution piping* and fittings shall comply with the applicable material standards and installation requirements in accordance with applicable provisions of Chapter 6.

1302.16.2 Design. *Distribution piping* shall be designed and sized in accordance with the applicable provisions of Chapter 6.

1302.16.3 Labeling and marking. *Distribution piping* labeling and marking shall comply with Section 608.8.

1301.16.4 Backflow prevention. *Backflow preventers* shall be installed in accordance with the applicable provisions of Section 608.

1301.17 Tests and inspections. Tests and inspections shall be performed in accordance with Sections 1301.17.1 through 1301.17.6.

1301.17.1 Drainage and vent pipe test. *Drain, waste and vent piping* used for gray water and rainwater non-potable water systems shall be tested in accordance with the applicable provisions of Section 312.

1301.17.2 Storage tank test. *Storage tanks* shall be tested in accordance with the Section 1301.10.11.

1301.17.3 Water supply system test. *Non-potable distribution piping* shall be tested in accordance with Section 312.5.

1301.17.4 Inspection and testing of backflow prevention assemblies. The testing of backflow preventers and *backwater valves* shall be conducted in accordance with Section 312.10.

1301.17.5 Inspection of vermin and insect protection. Inlets and vent terminations shall be visually inspected to verify that each termination is installed in accordance with Section 1301.10.8.

1301.18 Operation and maintenance manuals. Operations and maintenance materials for non-potable water systems shall be provided as prescribed by the system component manufacturers, and supplied to the owner to be kept in a readily accessible location.

SECTION 1302

GRAY WATER NON-POTABLE WATER SYSTEMS

1302.1 Gray water non-potable water systems. This code is applicable to the plumbing fixtures, piping or piping systems, storage tanks, drains, appurtenances and appliances which are part of the distribution system for gray water within buildings and to storage tanks and associated piping which are part of the distribution system for gray water outside of buildings. This code does not regulate equipment used for, or the methods of, processing.

filtering or treating gray water, which may be regulated by the Virginia Department of Health or Virginia Department of Environmental Quality.

1302.1.1 Separate systems. Gray water non-potable water systems, unless approved otherwise under the permit from the Virginia Department of Health, shall be separate from the potable water system of a building with no cross connections between the two systems except as permitted by the Virginia Department of Health.

1302.2 Water quality. Each application of gray water reuse shall meet the minimum water quality requirements set forth in 1302.2.1 through 1302.2.4 unless otherwise superseded by other state agencies.

1302.2.1 Disinfection. Where the intended use or reuse application for non-potable water requires disinfection or other treatment or both, it shall be disinfected as needed to ensure that the required water quality is delivered at the point of use or reuse.

1302.2.2 Residual disinfectants. Where chlorine is used for disinfection, the non-potable water shall contain not more than 4.0 mg/L of free chlorine, combined chlorine or total chlorine. Where ozone is used for disinfection, the non-potable water shall not exceed 0.1 ppm (by volume) of ozone at the point of use.

1302.2.3 Filtration. Water collected for reuse shall be filtered as required for the intended end use. Filters shall be accessible for inspection and maintenance. Filters shall utilize a pressure gage or other approved method to indicate when a filter requires servicing or replacement. Shutoff valves installed immediately upstream and downstream of the filter shall be included to allow for isolation during maintenance

1302.2.4 Filtration required. Gray water utilized for water closet and urinal flushing applications shall be filtered by a 100 micron or finer filter. .

1302.3 Storage tanks. Storage tanks utilized in gray water non-potable water systems shall comply with Section 1301.10.

1302.4 Retention Time Limits – Untreated gray water shall be retained in storage tanks for a maximum of 24 hours.

1302.5 Tank Location. Storage tanks shall be located with a minimum horizontal distance between various elements as indicated in Table 1302.5.1.

**TABLE 1302.5.1
LOCATION OF NON-POTABLE GRAY WATER REUSE STORAGE TANKS**

<u>Element</u>	<u>Minimum Horizontal Distance from Storage Tank (feet)</u>
<u>Lot line adjoining private lots</u>	<u>5</u>
<u>Sewage systems</u>	<u>5</u>
<u>Septic tanks</u>	<u>5</u>

<u>Element</u>	<u>Minimum Horizontal Distance from Storage Tank (feet)</u>
<u>Water wells</u>	<u>50</u>
<u>Streams and lakes</u>	<u>50</u>
<u>Water service</u>	<u>5</u>
<u>Public water main</u>	<u>10</u>

1302.6 Valves. Valves shall be supplied on gray water non-potable water drainage systems in accordance with Sections 1302.6.1 and 1302.6.2.

1302.6.1 Bypass valve. One three-way diverter valve certified to NSF 50 or other *approved* device shall be installed on collection piping upstream of each *storage tank*, or drainfield, as applicable, to divert untreated gray water to the sanitary sewer to allow servicing and inspection of the system. Bypass valves shall be installed downstream of fixture traps and vent connections. Bypass valves shall be *labeled* to indicate the direction of flow, connection and *storage tank* or drainfield connection. Bypass valves shall be provided with access for operation and maintenance. Two shutoff valves shall not be installed to serve as a bypass valve.

1302.6.2 Backwater valve. *Backwater valves* shall be installed on each overflow and tank drain pipe to prevent unwanted water from draining back into the storage tank. If the overflow and drain piping arrangement is installed to physically not allow water to drain back into the tank, such as the form of an air gap, backwater valves shall not be required. *Backwater valves* shall be constructed and installed in accordance with Section 715.

SECTION 1303

RAINWATER NON-POTABLE WATER SYSTEMS

1303.1 General. The provisions of Section 1303 shall govern the design, construction, installation, *alteration*, and *repair* of *rainwater non-potable water systems* for the collection, storage, treatment and distribution of rainwater for non-potable applications, as permitted in accordance with Section 1301.3.

1303.2 Water quality. Each application of rainwater reuse shall meet the minimum water quality requirements set forth in 1303.2.1 through 1303.2.4 unless otherwise superseded by other state agencies.

1303.2.1 Disinfection. Where the intended use or reuse application for non-potable water requires disinfection or other treatment or both, it shall be disinfected as needed to ensure that the required water quality is delivered at the point of use or reuse.

1303.2.2 Residual disinfectants. Where chlorine is used for disinfection, the *non-potable* water shall contain not more than 4.0 mg/L of free chlorine, combined chlorine or total chlorine. Where ozone is used for disinfection, the *non-potable* water shall not exceed 0.1 ppm (by volume) of ozone at the point of use.

1303.2.3 Filtration. Water collected for reuse shall be filtered as required for the intended end use. Filters shall be accessible for inspection and maintenance. Filters shall utilize a pressure gage or other approved method to indicate when a filter requires servicing or replacement. Shutoff valves installed immediately upstream and downstream of the filter shall be included to allow for isolation during maintenance

1303.2.4 Filtration required. Rainwater utilized for water closet and urinal flushing applications shall be filtered by a 100 micron or finer filter.

1303.3 Collection surface. Rainwater shall be collected only from above-ground impervious roofing surfaces constructed from approved materials. Overflow or discharge piping from appliances/equipment including but not limited to evaporative coolers, water heaters, and solar water heaters shall not discharge onto rainwater collection surfaces.

1303.4 Collection surface diversion. At a minimum, the first 0.04" of each rain event (25 gallons per 1000 sq. ft.) shall be diverted from the storage tank, by automatic means and not require the operation of manually operated valves or devices. Diverted water shall not drain onto other collection surfaces that are discharging to the rainwater system or to the sanitary sewer. Such water shall be diverted from the storage tank and discharged in an approved location.

1303.5 Pretank filtration. Downspouts, conductors and leaders shall be connected to a pretank filtration device. The filtration device shall not permit materials larger than 0.4 mm.

1303.6 Roof gutters and downspouts. Gutters and downspouts shall be constructed of materials that are compatible with the collection surface and the rainwater quality for the desired end use. Joints shall be made water-tight.

1303.6.1 Slope. Roof gutters, leaders, and rainwater collection piping shall slope continuously toward collection inlets. Gutters and downspouts shall have a slope of not less than 1/8 inch per foot along their entire length, and shall not permit the collection or pooling of water at any point.

Exception: Siphonic roof drainage systems installed in accordance with Chapter 11 shall not be required to have slope.

1303.6.2 Size. Gutters and downspouts shall be installed and sized in accordance with Section 1106.6 and local rainfall rates.

1303.6.3 Cleanouts. Cleanouts or other approved openings shall be provided to permit access to all filters, flushes, pipes and downspouts.

1303.7 Storage tanks. Storage tanks utilized in rainwater non-potable water systems shall comply with Section 1301.10.

1303.8 Location. Storage tanks shall be located with a minimum horizontal distance between various elements as indicated in Table 1303.9.1.

TABLE 1303.8.1
LOCATION OF RAINWATER STORAGE TANKS

<u>Element</u>	<u>Minimum Horizontal Distance from Storage Tank (feet)</u>
<u>Lot line adjoining private lots</u>	<u>5</u>
<u>Sewage Systems</u>	<u>5</u>
<u>Septic tanks</u>	<u>5</u>

1303.9 Valves. Valves shall be installed in collection and conveyance drainage piping of rainwater non-potable water systems in accordance with Sections 1303.9.1 and 1303.9.2.

1303.9.1 Influent Diversion. A means shall be provided to divert storage tank influent to allow maintenance and repair of the storage tank system.

1303.9.2 Backwater valve. Backwater valves shall be installed on each overflow and tank drain pipe to prevent unwanted water from draining back into the storage tank. If the overflow and drain piping arrangement is installed to physically not allow water to drain back into the tank, such as the form of an air gap, backwater valves shall not be required. Backwater valves shall be constructed and installed in accordance with Section 715.

1303.10 Tests and inspections. Tests and inspections shall be performed in accordance with Sections 1303.10.1 through 1303.10.2.

1303.10.1 Roof gutter inspection and test. Roof gutters shall be inspected to verify that the installation and slope is in accordance with Section 1303.6.1. Gutters shall be tested by pouring a minimum of one gallon of water into the end of the gutter opposite the collection point. The gutter being tested shall not leak and shall not retain standing water.

1303.10.2 Collection surface diversion test. A collection surface diversion test shall be performed by introducing water into the gutters or onto the collection surface area. Diversion of the first quantity of water in accordance with the requirements of Section 1303.4 shall be verified.

SECTION 1304

RECLAIMED WATER SYSTEMS

1304.1 General. Reclaimed water, water reclamation systems, reclaimed water distribution systems and allowable non-potable reuses of reclaimed water are as defined or specified in and governed by the Virginia Water Reclamation and Reuse Regulation (9 VAC 25-740). Permits from the Virginia State Water Control Board are required for such systems and reuses. The provisions of Section 1304 shall govern the design, construction, installation, alterations, and repair of plumbing fixtures, piping or piping systems, storage tanks, drains, appurtenances and appliances which are part of the distribution system for reclaimed water

within buildings and to storage tanks for reclaimed water as defined in the Water Reclamation and Reuse Regulation (9VAC25-740) and associated piping outside of buildings that deliver reclaimed water into buildings. Where conflicts occur between this code and 9 VAC25-740, the provisions of 9 VAC25-740 shall apply unless determined otherwise by the Virginia State Water Control Board and the Board of Housing and Community Development through a memorandum of agreement.

1304.2 Design of reclaimed water systems. The design of reclaimed water systems shall conform to applicable requirements of Section 1301.

Exceptions:

The design of reclaimed water systems shall conform to applicable requirements of the Water Reclamation and Reuse Regulation (9VAC25-740) for the following:

1. Identification, labeling and posting of signage for reclaimed water systems in lieu of signage requirements described in Section 1301.4.
2. Sizing of system storage as defined in the Water Reclamation and Reuse Regulation (9VAC25-740), in addition to storage sizing requirements described in Section 1301.10.1.
3. Signage and labeling for reclaimed water storage in addition to labeling and signage requirements described in Section 1301.10.10.
- 4 Minimum separation distances and configurations for in-ground reclaimed water distribution piping in lieu of trenching requirements for non-potable water systems described in Section 1301.11.

C

C

C

TAB 3

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: DRAFT

Proponent Information

(Check one): ☒ Individual ☐ Government Entity ☐ Company

Name: John Catlett

Representing: VBCOA Administration Committee

Mailing Address: 301 King Street, Alexandria, Virginia 22314

Email Address: john.catlett@alexandriava.gov

Telephone Number: 703.746.4182

Proposal Information

Code(s) and Section(s): VCC Section 103 Change of Occupancy, alterations, repairs, renovations and additions deleted and replaced with the Virginia Rehabilitation code except for IRC regulated buildings.

Proposed Change (including all relevant section numbers, if multiple sections):

Changes to the VCC:

**SECTION 103
APPLICATION OF CODE**

103.1 General. In accordance with Section 36-99 of the Code of Virginia, the USBC shall prescribe building regulations to be complied with in the construction and rehabilitation of buildings and structures, and the equipment therein.

103.2 When applicable to new construction. Construction for which a permit application is submitted to the local building department after the effective date of the 2009 edition of the code shall comply with the provisions of this code, except for permit applications submitted during a one-year period after the effective date of the 2009 edition of the code.

The applicant for a permit during such one-year period shall be permitted to choose whether to comply with the provisions of this code or the provisions of the edition of the code in effect immediately prior to the 2009 edition. This provision shall also apply to subsequent amendments to this code based on the effective date of such amendments. In addition, when a permit has been properly issued under a previous edition of this code, this code shall not require changes to the approved construction documents, design or construction of such a building or structure, provided the permit has not been suspended or revoked.

103.3 Change of occupancy. No change of occupancy shall be made in any structure when the current USBC requires a greater degree of accessibility, structural strength, fire protection, means of egress, ventilation or sanitation. When such a greater degree is required, the owner or the owner's agent shall make written application to the local building department for a new certificate of occupancy and shall obtain the new certificate of occupancy prior to the new use of the structure. shall meet the provisions of the Virginia Rehabilitation Code (VRC) for change of occupancy.

~~When impractical to achieve compliance with this code for the new occupancy classification, the building official shall consider modifications upon application and as provided for in Section 106.3.~~

~~Exception: This section shall not be construed to permit noncompliance with any applicable flood load or floodresistant construction requirements of this code.~~

103.4 Additions. Additions to buildings and structures shall comply with the requirements of this code for new construction or the provisions of the VRC. ~~and~~ An existing building or structure plus additions shall comply with the height and area provisions of Chapter 5 and the applicable provisions of Chapter 9. Further, this code shall not require changes to the design or construction of any portions of the building or structure not altered or affected by an addition, unless the addition has the effect of lowering the current level of safety.

Exception: This section shall not be construed to permit noncompliance with any applicable flood load or flood-resistant construction requirements of this code.

103.5 Reconstruction, alteration or repair for buildings subject to the International Residential Code. The following criteria are applicable to reconstruction, alteration or repair of buildings or structures for buildings subject to the International Residential Code:

1. Any reconstruction, alteration or repair shall not adversely affect the performance of the building or structure, or cause the building or structure to become unsafe or lower existing levels of health and safety.
2. Parts of the building or structure not being reconstructed, altered or repaired shall not be required to comply with the requirements of this code applicable to newly constructed buildings or structures.
3. The installation of material or equipment, or both, that is neither required nor prohibited shall only be required to comply with the provisions of this code relating to the safe installation of such material or equipment.
4. Material or equipment, or both, may be replaced in the same location with material or equipment of a similar kind or capacity.
5. Any reconstruction, alteration or repair may utilize the provisions of this code or the VRC at the owner's or owner's agent discretion.

Exceptions:

1. This section shall not be construed to permit noncompliance with any applicable flood load or flood-resistant construction requirements of this code.
2. Reconstructed decks, balconies, porches and similar structures located 30 inches (762 mm) or more above grade shall meet the current code provisions for structural loading capacity, connections and structural attachment. This requirement excludes the configuration and height of handrails and guardrails.

103.5.1 Equipment changes. Upon the replacement or new installation of any fuel-burning appliances or equipment in existing buildings, an inspection or inspections shall be conducted to ensure that the connected vent or chimney systems comply with the following:

1. Vent or chimney systems are sized in accordance with either the International Residential Code, the International Mechanical Code or the International Fuel Gas Code, depending on which is applicable based on the fuel source and the occupancy classification of the structure.
2. Vent or chimney systems are clean, free of any obstruction or blockages, defects or deterioration and are in operable condition. Where not inspected by the local building department, persons performing such changes or installations shall certify to the building official that the requirements of Items 1 and 2 of this section are met.

103.6 Use of rehabilitation code. Reconstruction, alteration, change of use or repair for buildings subject to the International Building Code. Reconstruction, alteration, change of use, or repair of buildings or structures subject to the International Building Code shall comply with Part II of the Virginia Uniform Statewide Building Code, also known as the "Virginia Rehabilitation Code," shall be an acceptable alternative to compliance with this code for the rehabilitation of such existing buildings and structures within the scope of that code. For the purposes of this section, the term "rehabilitation" shall be as defined in the Virginia Rehabilitation Code. Chapter 34 of the IBC shall be deleted.

103.107 Use of certain provisions of referenced codes. The following provisions of the IBC and of other indicated codes or standards are to be considered valid provisions of this code. Where any such provisions have been modified by the state amendments to the IBC, then the modified provisions apply.

1. Special inspection requirements in Chapters 2–35.
2. ~~Chapter 34, Existing Structures, except that Section 3412, Compliance Alternatives, shall not be used to comply with the retrofit requirements identified in Section 103.7 and shall not be construed to permit noncompliance with any applicable flood load or flood-resistant construction requirements of this code.~~
3. 2. Testing requirements and requirements for the submittal of construction documents in any of the ICC codes referenced in Chapter 35 and in the IRC.
4. 3. Section R301.2 of the International Residential Code authorizing localities to determine climatic and geographic design criteria.

~~§ 4.~~ Flood load or flood-resistant construction requirements in the IBC or the International Residential Code, including, but not limited to, any such provisions pertaining to flood elevation certificates that are located in Chapter 1 of those codes. Any required flood elevation certificate pursuant to such provisions shall be prepared by a land surveyor licensed in Virginia or an RDP.

6. Section R101.2 of the IRC.

~~103.7.8 Retrofit requirements.~~ The local building department shall enforce the provisions of Section 3413 VRC Appendix D, which require certain existing buildings to be retrofitted with fire protection systems and other safety equipment. Retroactive fire protection system requirements contained in the International Fire Code shall not be applicable unless required for compliance with the provisions of Section 3413 VRC Appendix D.

~~103.8 Nonrequired equipment.~~ The following criteria for nonrequired equipment is in accordance with Section 36-103 of the Code of Virginia. Building owners may elect to install partial or full fire alarms or other safety equipment that was not required by the edition of the USBC in effect at the time a building was constructed without meeting current requirements of the code, provided the installation does not create a hazardous condition. Permits for installation shall be obtained in accordance with this code. In addition, as a requirement of this code, when such nonrequired equipment is to be installed, the building official shall notify the appropriate fire official or fire chief.

~~103.8.1 Reduction in function or discontinuance of nonrequired fire protection systems.~~ When a nonrequired fire protection system is to be reduced in function or discontinued, it shall be done in such a manner so as not to create a false sense of protection. Generally, in such cases, any features visible from interior areas shall be removed, such as sprinkler heads, smoke detectors or alarm panels or devices, but any wiring or piping hidden within the construction of the building may remain. Approval of the proposed method of reduction or discontinuance shall be obtained from the building official.

~~103.9 Equipment changes.~~ Upon the replacement or new installation of any fuel burning appliances or equipment in existing buildings, an inspection or inspections shall be conducted to ensure that the connected vent or chimney systems comply with the following:

~~1. Vent or chimney systems are sized in accordance with either the International Residential Code, the International Mechanical Code or the International Fuel Gas Code, depending on which is applicable based on the fuel source and the occupancy classification of the structure.~~

~~2. Vent or chimney systems are clean, free of any obstruction or blockages, defects or deterioration and are in operable condition. Where not inspected by the local building department, persons performing such changes or installations shall certify to the building official that the requirements of Items 1 and 2 of this section are met.~~

CHAPTER 34 EXISTING STRUCTURES

~~3401.1 Scope.~~ The provisions of this chapter and the applicable requirements of Chapter 1 shall control the alteration, repair, addition and change of occupancy of existing structures.

~~Delete IBC Sections 3401.2, 3401.3, 3401.4, and 3401.5.~~

~~Delete IBC Sections 3403, 3404, 3405, and 3406.~~

~~Change Section 3407.1 of the IBC to read:~~

~~3407.1 Standards for replacement glass.~~ In accordance with Section 36-99.2 of the Code of Virginia, any replacement glass installed in buildings constructed prior to the first edition of the USBC shall meet the quality and installation standards for glass installed in new buildings as are in effect at the time of installation. In addition, as a requirement of this code, the installation or replacement of glass in buildings constructed under any edition of the USBC shall be as required for new installations.

~~Delete IBC Section 3408.~~

~~Delete IBC Section 3410.~~

~~Change Section 3412.2 of the IBC to read:~~

~~3412.2 Applicability.~~ When specifically requested by an owner or an owner's agent in structures where there is work involving additions, alterations or changes of occupancy, the provisions in Sections 3412.2.1 through 3412.2.5 shall apply to existing

occupancies that will continue to be, or are proposed to be, in Groups A, B, E, F, M, R, S and U. These provisions shall not apply to buildings with occupancies in Group H or I.

Add an exception to Section 3412.2.1 of the IBC to read:

Exception: Plumbing, mechanical and electrical systems in buildings undergoing a change of occupancy shall be subject to any applicable requirements of Section 103.3 of this code.

Change Section 3412.2.5 of the IBC to read:

3412.2.5 Accessibility requirements. All portions of the buildings proposed for change of occupancy and all alterations to existing buildings shall conform to the applicable accessibility provisions of Section 3411.

Add IBC Section 3413 Retrofit Requirements.

Add Section 3413.1 to the IBC to read:

3413.1 Scope. In accordance with Section 103.7 and as set out herein, the following buildings are required to be provided with certain fire protection equipment or systems or other retrofitted components.

Add Section 3413.2 to the IBC to read:

3413.2 Smoke detectors in colleges and universities. In accordance with Section 36-99.3 of the Code of Virginia, college and university buildings containing dormitories for sleeping purposes shall be provided with battery powered or AC powered smoke detector devices installed therein in accordance with this code in effect on July 1, 1982. All public and private college and university dormitories shall have installed such detectors regardless of when the building was constructed. The chief administrative officer of the college or university shall obtain a certificate of compliance with the provisions of this subsection from the building official of the locality in which the college or university is located or in the case of state-owned buildings, from the Director of the Virginia Department of General Services. The provisions of this section shall not apply to any dormitory at a state-supported military college or university which is patrolled 24 hours a day by military guards.

Add Section 3413.3 to the IBC to read:

3413.3 Smoke detectors in certain juvenile care facilities. In accordance with Section 36-99.4 of the Code of Virginia, battery powered or AC powered smoke detectors shall be installed in all local and regional detention homes, group homes, and other residential care facilities for children and juveniles which are operated by or under the auspices of the Virginia Department of Juvenile Justice, regardless of when the building was constructed, by July 1, 1986, in accordance with the provisions of this code that were in effect on July 1, 1984. Administrators of such homes and facilities shall be responsible for the installation of the smoke detector devices.

Add Section 3413.4 to the IBC to read:

3413.4 Smoke detectors for the deaf and hearing-impaired. In accordance with Section 36-99.5 of the Code of Virginia, smoke detectors providing an effective intensity of not less than 100 candela to warn a deaf or hearing impaired individual shall be provided, upon request by the occupant to the landlord or proprietor, to any deaf or hearing impaired occupant of any of the following occupancies, regardless of when constructed:

1. All dormitory buildings arranged for the shelter and sleeping accommodations of more than 20 individuals;
2. All multiple family dwellings having more than two dwelling units, including all dormitories, boarding and lodging houses arranged for shelter and sleeping accommodations of more than five individuals; or
3. All buildings arranged for use of one family or two family dwelling units.

A tenant shall be responsible for the maintenance and operation of the smoke detector in the tenant's unit.

A hotel or motel shall have available no fewer than one such smoke detector for each 70 units or portion thereof, except that this requirement shall not apply to any hotel or motel with fewer than 35 units. The proprietor of the hotel or motel shall post in a conspicuous place at the registration desk or counter a permanent sign stating the availability of smoke detectors for the hearing impaired. Visual detectors shall be provided for all meeting rooms for which an advance request has been made.

Add Sections 3413.5, 3413.5.1, and 3413.5.2 to the IBC to read:

3413.5 Assisted living facilities (formerly known as adult care residences or homes for adults). Existing assisted living facilities licensed by the Virginia Department of Social Services shall comply with this section.

3413.5.1 Fire-protective signaling system and fire detection system. A fire-protective signaling system and an automatic fire detection system meeting the requirements of the USBC, Volume I, 1987 Edition, Third Amendment, shall be installed in assisted living facilities by August 1, 1994.

Exception: Assisted living facilities that are equipped throughout with a fire-protective signaling system and an automatic fire detection system.

3413.5.2 Single and multiple station smoke detectors. Battery or AC powered single and multiple station smoke detectors meeting the requirements of the USBC, Volume I, 1987 Edition, Third Amendment, shall be installed in assisted living facilities by August 1, 1994.

Exception: Assisted living facilities that are equipped throughout with single and multiple station smoke detectors.

Add Section 3413.6 to the IBC to read:

3413.6 Smoke detectors in buildings containing dwelling units. AC powered smoke detectors with battery backup or an equivalent device shall be required to be installed to replace a defective or inoperative battery powered smoke detector located in buildings containing one or more dwelling units or rooming houses offering to rent overnight sleeping accommodations, when it is determined by the building official that the responsible party of such building or dwelling unit fails to maintain battery powered smoke detectors in working condition.

Add Section 3413.7 to the IBC to read:

3413.7 Fire suppression, fire alarm and fire detection systems in nursing homes and facilities. Fire suppression systems as required by the edition of this code in effect on October 1, 1990, shall be installed in all nursing facilities licensed by the Virginia Department of Health by January 1, 1993, regardless of when such facilities or institutions were constructed. Units consisting of certified long term care beds located on the ground floor of general hospitals shall be exempt from the requirements of this section.

Fire alarm or fire detector systems, or both, as required by the edition of this code in effect on October 1, 1990, shall be installed in all nursing homes and nursing facilities licensed by the Virginia Department of Health by August 1, 1994.

Add Section 3413.8 to the IBC to read:

3413.8 Fire suppression systems in hospitals. Fire suppression systems shall be installed in all hospitals licensed by the Virginia Department of Health as required by the edition of this code in effect on October 1, 1995, regardless of when such facilities were constructed.

Add Section 3413.9 to the IBC to read:

3413.9 Identification of handicapped parking spaces by above grade signs. All parking spaces reserved for the use of handicapped persons shall be identified by above grade signs, regardless of whether identification of such spaces by above grade signs was required when any particular space was reserved for the use of handicapped persons. A sign or symbol painted or otherwise displayed on the pavement of a parking space shall not constitute an above grade sign.

Any parking space not identified by an above grade sign shall not be a parking space reserved for the handicapped within the meaning of this section. All above grade handicapped parking space signs shall have the bottom edge of the sign no lower than four feet (1219 mm) nor higher than seven feet (2133 mm) above the parking surface. Such signs shall be designed and constructed in accordance with the provisions of Chapter 11 of this code. All disabled parking signs shall include the following language: PENALTY, \$100-500 Fine, TOW-AWAY ZONE. Such language may be placed on a separate sign and attached below existing above grade disabled parking signs, provided that the bottom edge of the attached sign is no lower than four feet above the parking surface.

Add Section 3413.10 to the IBC to read:

3413.10 Smoke detectors in hotels and motels. Smoke detectors shall be installed in hotels and motels as required by the edition of VR 394-01-22, USBC, Volume II, in effect on March 1, 1990, by the dates indicated, regardless of when constructed.

Add Section 3413.11 to the IBC to read:

3413.11 Sprinkler systems in hotel and motels. By September 1, 1997, an automatic sprinkler system shall be installed in hotels and motels as required by the edition of VR 394-01-22, USBC, Volume II, in effect on March 1, 1990, regardless of when constructed.

Add Section 3413.12 to the IBC to read:

3413.12 Fire suppression systems in dormitories. An automatic fire suppression system shall be provided throughout all buildings having a Group R-2 fire area which are more than 75 feet (22,860 mm) or six stories above the lowest level of exit discharge and which are used, in whole or in part, as a dormitory to house students by any public or private institution of higher education, regardless of when such buildings were constructed, in accordance with the edition of this code in effect on August 20, 1997, and the requirements for sprinkler systems under the edition of the NFPA 13 standard referenced by that code. The automatic fire suppression system shall be installed by September 1, 1999. The chief administrative officer of the college or university shall obtain a certificate of compliance from the building official of the locality in which the college or university is located or in the case of state-owned buildings, from the Director of the Virginia Department of General Services.

Exceptions:

1. Buildings equipped with an automatic fire suppression system in accordance with Section 903.3.1.1 or the 1983 or later editions of NFPA 13.

2. Any dormitory at a state-supported military college or university which is patrolled 24 hours a day by military guards.

3. Application of the requirements of this section shall be modified in accordance with the following:

3.1. Building systems, equipment or components other than the fire suppression system shall not be required to be added or upgraded except as necessary for the installation of the fire suppression system and shall only be required to be added or upgraded where the installation of the fire suppression system creates an unsafe condition.

3.2. Residential sprinklers shall be used in all sleeping rooms. Other sprinklers shall be quick response or residential unless deemed unsuitable for a space. Standard response sprinklers shall be used in elevator hoist ways and machine rooms.

3.3. Sprinklers shall not be required in wardrobes in sleeping rooms that are considered part of the building construction or in closets in sleeping rooms, when such wardrobes or closets (i) do not exceed 24 square feet (2.23 m²) in area, (ii) have the smallest dimension less than 36 inches (914 mm), and (iii) comply with all of the following:

3.3.1. A single station smoke detector monitored by the building fire alarm system is installed in the room containing the wardrobe or closet that will activate the general alarm for the building if the single station smoke detector is not cleared within five minutes after activation.

3.3.2. The minimum number of sprinklers required for calculating the hydraulic demand of the system for the room shall be increased by two and the two additional sprinklers shall be corridor sprinklers where the wardrobe or closet is used to divide the room. Rooms divided by a wardrobe or closet shall be considered one room for the purpose of this requirement. 3.3.3. The ceiling of the wardrobe, closet or room shall have a fire resistance rating of not less than 1/2 hour.

3.4. Not more than one sprinkler shall be required in bathrooms within sleeping rooms or suites having a floor area between 55 square feet (5.12 m²) and 120 square feet (11.16 m²) provided the sprinkler is located to protect the lavatory area and the plumbing fixtures are of a noncombustible material.

3.5. Existing standpipe residual pressure shall be permitted to be reduced when the standpipe serves as the water supply for the fire suppression system provided the water supply requirements of NFPA 13-94 are met.

3.6. Limited service controllers shall be permitted for fire pumps when used in accordance with their listing.

3.7. Where a standby power system is required, a source of power in accordance with Section 701.11 (d) or 701.11 (e) of NFPA 70-96 shall be permitted.

Add Section 3413.13 to the IBC to read:

3413.13 Fire extinguishers and smoke detectors in SRCF's. SRCF's shall be provided with at least one approved type ABC portable fire extinguisher with a minimum rating of 2 A:10 B:C installed in each kitchen. In addition, SRCF's shall provide at least one approved and properly installed battery-operated smoke detector outside of each sleeping area in the vicinity of bedrooms and bedroom hallways and on each additional floor.

Add Section 3413.14 to the IBC to read:

3413.14 Smoke detectors in adult day care centers. Battery powered or AC powered smoke detector devices shall be installed in all adult day care centers licensed by the Virginia Department of Social Services, regardless of when the building was constructed. The location and installation of the smoke detectors shall be determined by the provisions of this code in effect on

October 1, 1990. The licensee shall obtain a certificate of compliance from the building official of the locality in which the center is located, or in the case of state-owned buildings, from the Director of the Virginia Department of General Services.

Add Section 3413.15 to the IBC to read:

3413.15 Posting of occupant load. Every room or space that is an assembly occupancy, and where the occupant load of that room or space is 50 or more, shall have the occupant load of the room or space as determined by the building official posted in a conspicuous place, near the main exit or exit access doorway from the room or space. Posted signs shall be of an approved legible permanent design and shall be maintained by the owner or authorized agent.

Add Section 3413.16 to the IBC to read:

3413.16 ALFSTs. Existing ALFSTs, regardless of when constructed, shall, by October 1, 2011, meet the applicable requirements of API 653 and TFI RMIP for suitability for service and inspections and shall provide a secondary containment system complying with Section 425.3.

117.2 Moved buildings and structures. Any building or structure moved into a locality or moved to a new location within a locality shall not be occupied or used until a certification of occupancy is issued for the new location. Such moved buildings or structures shall be required to comply with the requirements of this code for a newly constructed building or structure unless meeting all of the following requirements relative to the new location:

1. There is no change in the occupancy classification from its previous location.
2. The building or structure was in compliance with all state and local requirements applicable to it in its previous location and is in compliance with all state and local requirements applicable if originally constructed in the new location.
3. The building or structure did not become unsafe during the moving process due to structural damage or for other reasons.
4. Any alterations, reconstruction, renovations or repairs made pursuant to the move are in compliance with applicable requirements of this code of the VRC.

Changes to the VRC:

Chapter 1 ADMINISTRATION

SECTION 101 GENERAL

101.1 Short title. The Virginia Uniform Statewide Building Code, Part II, Rehabilitation, may be cited as the Virginia Rehabilitation Code.

101.2 Incorporation by reference. Chapters 2–15 of the 2009 International Existing Building Code, published by the International Code Council, Inc., are adopted and incorporated by reference to be an enforceable part of the Virginia Rehabilitation Code. The term “IEBC” means the 2009 International Existing Building Code, published by the International Code Council, Inc. Any codes and standards referenced in the IEBC are also considered to be part of the incorporation by reference, except that such codes and standards are used only to the prescribed extent of each such reference.

101.3 Numbering system. A dual numbering system is used in the Virginia Rehabilitation Code to correlate the numbering system of the Virginia Administrative Code with the numbering system of the IEBC. IEBC numbering system designations are provided in the catch-lines of the Virginia Administrative Code sections and cross references between sections or chapters of the Virginia Rehabilitation Code use only the IEBC numbering system designations. The term “chapter” is used in the context of the numbering system of the IEBC and may mean a chapter in the Virginia Rehabilitation Code, a chapter in the IEBC or a chapter in a referenced code or standard, depending on the context of the use of the term. The term “chapter” is not used to designate a chapter of the Virginia Administrative Code, unless clearly indicated.

101.4 Arrangement of code provisions. The Virginia Rehabilitation Code is comprised of the combination of (i) the provisions of Chapter 1, Administration, which are established herein, (ii) Chapters 2–15 of the IEBC, which are incorporated by reference in Section 101.2, and (iii) the changes to the text of the incorporated chapters of the IEBC that are specifically identified. The terminology “changes to the text of the incorporated chapters of the IEBC that are specifically identified” shall also be referred to as the “state amendments to the IEBC.” Such state amendments to the IEBC are set out using corresponding chapter and section

numbers of the IEBC numbering system. In addition, since Chapter 1 of the IEBC is not incorporated as part of the Virginia Rehabilitation Code, any reference to a provision of Chapter 1 of the IEBC in the provisions of Chapters 2–15 of the IEBC is generally invalid. However, where the purpose of such a reference would clearly correspond to a provision of Chapter 1 established herein, then the reference may be construed to be a valid reference to such corresponding Chapter 1 provision.

101.5 Use of terminology and notes. The term “this code,” or “the code,” where used in the provisions of Chapter 1, in Chapters 2–15 of the IEBC or in the state amendments to the IEBC means the Virginia Rehabilitation Code, unless the context clearly indicates otherwise. The term “this code,” or “the code,” where used in a code or standard referenced in the IEBC means that code or standard, unless the context clearly indicates otherwise. The term “USBC” where used in this code means Part I of the Virginia Uniform Statewide Building Code, also known as the “Virginia Construction Code,” unless the context clearly indicates otherwise. In addition, where the phrase “of the International Building Code under which the building was constructed” is used in the IEBC, it shall be construed to mean the USBC or other code that was in effect when the building was built. Further, the use of notes in Chapter 1 is to provide information only and shall not be construed as changing the meaning of any code provision. Notes in the IEBC, in the codes and standards referenced in the IEBC and in the state amendments to the IEBC may modify the content of a related provision and shall be considered to be a valid part of the provision, unless the context clearly indicates otherwise.

101.6 Order of precedence. The provisions of Chapter 1 of this code supersede any conflicting provisions of Chapters 2–15 of the IEBC and any conflicting provisions of the codes and standards referenced in the IEBC. In addition, the state amendments to the IEBC supersede any conflicting provisions of Chapters 2–15 of the IEBC and any conflicting provisions of the codes and standards referenced in the IEBC. Further, the provisions of Chapters 2–15 of the IEBC supersede any conflicting provisions of the codes and standards referenced in the IEBC.

101.7 Administrative provisions. The provisions of Chapter 1 establish administrative requirements, which include but are not limited to provisions relating to the scope and enforcement of the code. Any provisions of Chapters 2–15 of the IEBC or any provisions of the codes and standards referenced in the IEBC that address the same subject matter to a lesser or greater extent are deleted and replaced by the provisions of Chapter 1. Further, any administrative requirements contained in the state amendments to the IEBC shall be given the same precedence as the provisions of Chapter 1. Notwithstanding the above, where administrative requirements of Chapters 2–15 of the IEBC or of the codes and standards referenced in the IEBC are specifically identified as valid administrative requirements in Chapter 1 of this code or in the state amendments to the IEBC, then such requirements are not deleted and replaced.

Note: The purpose of this provision is to eliminate overlap, conflicts and duplication by providing a single standard for administrative, procedural and enforcement requirements of this code.

101.8 Definitions. The definitions of terms used in this code are contained in Chapter 2 along with specific provisions addressing the use of definitions. Terms may be defined in other chapters or provisions of the code and such definitions are also valid.

SECTION 102 PURPOSE AND SCOPE

102.1 Purpose. In accordance with Section 36-99.01 of the Code of Virginia, the General Assembly of Virginia has declared that (i) there is an urgent need to improve the housing conditions of low and moderate income individuals and families, many of whom live in substandard housing, particularly in the older cities of the Commonwealth; (ii) there are large numbers of older residential buildings in the Commonwealth, both occupied and vacant, which are in urgent need of rehabilitation and which must be rehabilitated if the State's citizens are to be housed in decent, sound, and sanitary conditions; and (iii) the application of those building code requirements currently in force to housing rehabilitation has sometimes led to the imposition of costly and time-consuming requirements that result in a significant reduction in the amount of rehabilitation activity taking place.

The General Assembly further declares that (i) there is an urgent need to improve the existing condition of many of the Commonwealth's stock of commercial properties, particularly in older cities; (ii) there are large numbers of older commercial buildings in the Commonwealth, both occupied and vacant, that are in urgent need of rehabilitation and that must be rehabilitated if the citizens of the Commonwealth are to be provided with decent, sound and sanitary work spaces; and (iii) the application of the existing building code to such rehabilitation has sometimes led to the imposition of costly and time-consuming requirements that result in a significant reduction in the amount of rehabilitation activity taking place.

102.2 Scope. Reconstruction, alteration, change of use, or repair of buildings or structures subject to the International Building Code shall comply with the Virginia Rehabilitation Code. For the purposes of this section, the term “rehabilitation” shall be as defined in the Virginia Rehabilitation Code

102.2.1 In accordance with Section 103-6 5of the USBC, this code shall be an acceptable alternative to compliance with the Virginia Construction Code for the rehabilitation of existing buildings and structures subject to the IRC code provisions.

SECTION 103 APPLICATION OF CODE

103.1 General. The provisions of this code shall control the rehabilitation, alteration, repair, addition and change of occupancy of existing buildings and structures when this code is chosen as an alternative to compliance with the Virginia Construction Code for buildings subject to the provisions of the International Residential Code (IRC). Buildings subject to the International Building Code (IBC) shall be subject to these requirements. All administrative provisions of the Virginia Construction Code, including but not limited to, requirements for permits, inspections and approvals by the local building department, provisions for appeals from decisions of the local building department and the issuance of modifications, are applicable to the use of this code, except where this code sets out differing requirements. Where there is a conflict between a general requirement and a specific requirement in the IBC, the specific requirement shall govern.

Exception: The use of this code shall not be permitted for change of occupancy involving Group I-2 or Group I-3.

103.1.1 Use of performance code. Compliance with the provisions of a nationally recognized performance code when approved as a modification shall be considered to constitute compliance with this code. All documents submitted as part of such consideration shall be retained in the permanent records of the local building department.

103.1.2 Preliminary meeting. When requested by a prospective permit applicant or when determined necessary by the code official, the code official shall meet with the prospective permit applicant prior to the application for a permit to discuss plans for the proposed work or change of occupancy in order to establish the specific applicability of the provisions of this code.

103.2 Requirements relating to maintenance. Any requirements of the IBC requiring the maintenance of existing buildings or structures are invalid.

Note: Requirements for the maintenance of existing buildings and structures and for unsafe conditions are contained in Part III of the Virginia Uniform Statewide Building Code, also known as the "Virginia Maintenance Code."

103.3 Use of Appendix A. Appendix A of the IBC provides guidelines for the seismic retrofit of existing buildings. The use of this appendix is not mandatory but shall be permitted to be utilized at the option of an owner, the owner's agent or the RDP involved in a rehabilitation project. However, in no case shall the use of Appendix A be construed to authorize the lowering of existing levels of health or safety in buildings or structures being rehabilitated.

103.4 Use of Appendix B. Appendix B of the IBC provides supplementary accessibility requirements for existing buildings and facilities. All applicable requirements of Appendix B shall be met in buildings and structures being rehabilitated.

103.5 Use of Resource A. Resource A of the IBC provides guidelines for the evaluation of fire resistance ratings of archaic materials and may be used in conjunction with rehabilitation projects.

103.6 Change of occupancy. No change of occupancy shall be made in any structure when the current USBC requires a greater degree of accessibility, structural strength, fire protection, means of egress, ventilation or sanitation. When such a greater degree is required, the owner or the owner's agent shall make written application to the local building department for a new certificate of occupancy and shall obtain the new certificate of occupancy prior to the new use of the structure.

When impractical to achieve compliance with this code for the new occupancy classification, the building official shall consider modifications upon application and as provided for in Section 106.3.

Exception: This section shall not be construed to permit noncompliance with any applicable flood load or floodresistant construction requirements of this code.

103.6 Retrofit requirements. The local building department shall enforce the provisions of Appendix D, which require certain existing buildings to be retrofitted with fire protection systems and other safety equipment. Retroactive fire protection system requirements contained in the International Fire Code shall not be applicable unless required for compliance with the provisions of Appendix D.

103.7 Nonrequired equipment. The following criteria for nonrequired equipment is in accordance with Section 36-103 of the Code of Virginia. Building owners may elect to install partial or full fire alarms or other safety equipment that was not required by the edition of the USBC in effect at the time a building was constructed without meeting current requirements of the code, provided the installation does not create a hazardous condition. Permits for installation shall be obtained in accordance with this code. In addition, as a requirement of this code, when such nonrequired equipment is to be installed, the building official shall notify the appropriate fire official or fire chief.

103.7.1 Reduction in function or discontinuance of nonrequired fire protection systems. When a nonrequired fire protection system is to be reduced in function or discontinued, it shall be done in such a manner so as not to create a false sense of protection. Generally, in such cases, any features visible from interior areas shall be removed, such as sprinkler heads, smoke detectors or alarm panels or devices, but any wiring or piping hidden within the construction of the building may remain. Approval of the proposed method of reduction or discontinuance shall be obtained from the building official.

103.8 Equipment changes. Upon the replacement or new installation of any fuel-burning appliances or equipment in existing buildings, an inspection or inspections shall be conducted to ensure that the connected vent or chimney systems comply with the following:

- 1. Vent or chimney systems are sized in accordance with either the International Residential Code, the International Mechanical Code or the International Fuel Gas Code, depending on which is applicable based on the fuel source and the occupancy classification of the structure.**
- 2. Vent or chimney systems are clean, free of any obstruction or blockages, defects or deterioration and are in operable condition. Where not inspected by the local building department, persons performing such changes or installations shall certify to the building official that the requirements of Items 1 and 2 of this section are met.**

CHAPTER 2 DEFINITIONS

Change Section 201.3 of the IEBC to read:

201.3 Terms defined in other codes. Where terms are not defined in this code and are defined in the other International Codes, such terms shall have the meanings ascribed to them in those codes, except that terms that are not defined in this code and that are defined in the Virginia Construction Code shall take precedence over other definitions.

Change the following definition in Section 202 of the IEBC to read:

Existing building. A building for which a legal certificate of occupancy has been issued under any edition of the USBC and that has been occupied for its intended use; or, a building built prior to the initial edition of the USBC.

CHAPTER 7 ALTERATIONS—LEVEL 2

Change Exception 2 of Section 705.2 to read:

- 2. Means of egress conforming to the requirements of the building code under which the building was constructed shall be considered compliant means of egress.**

Change Item 7 of Section 705.3.1.1 of the IEBC to read:

- 7. In Group R-2, H-4, H-5 and I occupancies and in rooming houses and childcare centers, a single exit is permitted in a one-story building with a maximum occupant load of 10 and the exit access travel distance does not exceed 75 feet (22 860 mm). In dwelling units within Group R-2 buildings, an occupant load of 12 shall be permitted to be substituted for the occupant load established above and, in addition, staff of such family day homes shall not be counted for the purposes of establishing occupant loads.**

CHAPTER 11 HISTORIC BUILDINGS

Change Section 1101.2 of the IEBC to read:

1101.2 Report. The code official shall be permitted to require that an historic building undergoing repair, alteration or change of occupancy be investigated and evaluated by an RDP or other qualified person or agency as a condition of determining compliance with this code.

CHAPTER 13 PERFORMANCE COMPLIANCE METHODS

Change Section 1301.2 of the IEBC to read:

1301.2 Applicability. Work involving rehabilitation, additions, alterations or changes of occupancy shall be made to conform to the requirements of this chapter or the provisions of Chapters 4 through 12. The provisions in Sections 1301.2.1 through 1301.2.5 shall apply to existing occupancies that will continue to be, or are proposed to be, in Groups A, B, E, F, M, R, S and U. These provisions shall not apply to buildings with occupancies in Group H or I.

Add an exception to Section 1301.2.1 of the IEBC to read:

Exception: Plumbing, mechanical and electrical systems in buildings undergoing a change of occupancy shall be subject to any applicable requirements of Section 103.3 of the Virginia Construction Code.

Change Section 1301.2.5 of the IEBC to read:

1301.2.5 Accessibility requirements. All portions of the buildings proposed for change of occupancy and all alterations to existing buildings shall conform to the applicable accessibility provisions of Section 310.

Chapter 17 **Retrofit Requirements**

1701 Scope. In accordance with Section 103.6 and as setout herein, the following buildings are required to be provided with certain fire protection equipment or systems or other retrofitted components.

1702 Smoke detectors in colleges and universities. In accordance with Section 36-99.3 of the Code of Virginia, college and university buildings containing dormitories for sleeping purposes shall be provided with battery-powered or AC-powered smoke detector devices installed therein in accordance with this code in effect on July 1, 1982. All public and private college and university dormitories shall have installed such detectors regardless of when the building was constructed. The chief administrative office of the college or university shall obtain a certificate of compliance with the provisions of this subsection from the building official of the locality in which the college or university is located or in the case of state-owned buildings, from the Director of the Virginia Department of General Services. The provisions of this section shall not apply to any dormitory at a state-supported military college or university which is patrolled 24 hours a day by military guards.

1703 Smoke detectors in certain juvenile care facilities. In accordance with Section 36-99.4 of the Code of Virginia, battery-powered or AC-powered smoke detectors shall be installed in all local and regional detention homes, group homes, and other residential care facilities for children and juveniles which are operated by or under the auspices of the Virginia Department of Juvenile Justice, regardless of when the building was constructed, by July 1, 1986, in accordance with the provisions of this code that were in effect on July 1, 1984. Administrators of such homes and facilities shall be responsible for the installation of the smoke detector devices.

1704 Smoke detectors for the deaf and hearing-impaired. In accordance with Section 36-99.5 of the Code of Virginia, smoke detectors providing an effective intensity of not less than 100 candela to warn a deaf or hearing impaired individual shall be provided, upon request by the occupant to the landlord or proprietor, to any deaf or hearing-impaired occupant of any of the following occupancies, regardless of when constructed:

- 1. All dormitory buildings arranged for the shelter and sleeping accommodations of more than 20 individuals;**
- 2. All multiple-family dwellings having more than two dwelling units, including all dormitories, boarding and lodging houses arranged for shelter and sleeping accommodations of more than five individuals; or**
- 3. All buildings arranged for use of one-family or two-family dwelling units.**

A tenant shall be responsible for the maintenance and operation of the smoke detector in the tenant's unit. A hotel or motel shall have available no fewer than one such smoke detector for each 70 units or portion thereof, except that this requirement shall not apply to any hotel or motel with fewer than 35 units. The proprietor of the hotel or motel shall post in a conspicuous place at the registration desk or counter a permanent sign stating the availability of smoke detectors for the hearing impaired. Visual detectors shall be provided for all meeting rooms for which an advance request has been made.

1705 Assisted living facilities (formerly known as adult care residences or homes for adults). Existing assisted living facilities licensed by the Virginia Department of Social Services shall comply with this section.

1706 Fire protective signaling system and fire detection system. A fire protective signaling system and an automatic fire detection system meeting the requirements of the USBC, Volume I, 1987 Edition, Third Amendment, shall be installed in assisted living facilities by August 1, 1994.

Exception: Assisted living facilities that are equipped throughout with a fire protective signaling system and an automatic fire detection system.

1707 Single and multiple station smoke detectors. Battery or AC-powered single and multiple station smoke detectors meeting the requirements of the USBC, Volume I, 1987 Edition, Third Amendment, shall be installed in assisted living facilities by August 1, 1994.

Exception: Assisted living facilities that are equipped throughout with single and multiple station smoke detectors. Add Section 3413.6 to the IBC to read:

1708 Smoke detectors in buildings containing dwelling units. AC-powered smoke detectors with battery backup or an equivalent device shall be required to be installed to replace a defective or inoperative battery-powered smoke detector located in buildings containing one or more dwelling units or rooming houses offering to rent overnight sleeping accommodations, when it is determined by the building official that the responsible party of such building or dwelling unit fails to maintain battery-powered smoke detectors in working condition.

1709 Fire suppression, fire alarm and fire detection systems in nursing homes and facilities. Fire suppression systems as required by the edition of this code in effect on October 1, 1990, shall be installed in all nursing facilities licensed by the Virginia Department of Health by January 1, 1993, regardless of when such facilities or institutions were constructed. Units consisting of certified long-term care beds located on the ground floor of general hospitals shall be exempt from the requirements of this section.

Fire alarm or fire detector systems, or both, as required by the edition of this code in effect on October 1, 1990, shall be installed in all nursing homes and nursing facilities licensed by the Virginia Department of Health by August 1, 1994.

1710 Fire suppression systems in hospitals. Fire suppression systems shall be installed in all hospitals licensed by the Virginia Department of Health as required by the edition of this code in effect on October 1, 1995, regardless of when such facilities were constructed.

1711 Identification of handicapped parking spaces by above grade signs. All parking spaces reserved for the use of handicapped persons shall be identified by above grade signs, regardless of whether identification of such spaces by above grade signs was required when any particular space was reserved for the use of handicapped persons. A sign or symbol painted or otherwise displayed on the pavement of a parking space shall not constitute an above grade sign.

Any parking space not identified by an above grade sign shall not be a parking space reserved for the handicapped within the meaning of this section. All above grade handicapped parking space signs shall have the bottom edge of the sign no lower than four feet (1219 mm) nor higher than seven feet (2133 mm) above the parking surface. Such signs shall be designed and constructed in accordance with the provisions of Chapter 11 of this code. All disabled parking signs shall include the following language: PENALTY, \$100-500 Fine, TOW-AWAY ZONE. Such language may be placed on a separate sign and attached below existing above grade disabled parking signs, provided that the bottom edge of the attached sign is no lower than four feet above the parking surface.

1712 Smoke detectors in hotels and motels. Smoke detectors shall be installed in hotels and motels as required by the edition of VR 394-01-22, USBC, Volume II, in effect on March 1, 1990, by the dates indicated, regardless of when constructed.

1713 Sprinkler systems in hotel and motels. By September 1, 1997, an automatic sprinkler system shall be installed in hotels and motels as required by the edition of VR 394-01-22, USBC, Volume II, in effect on March 1, 1990, regardless of when constructed.

1714 Fire suppression systems in dormitories. An automatic fire suppression system shall be provided throughout all buildings having a Group R-2 fire area which are more than 75 feet (22,860 mm) or six stories above the lowest level of exit discharge and which are used, in whole or in part, as a dormitory to house students by any public or private institution of higher education, regardless of when such buildings were constructed, in accordance with the edition of this code in effect on August 20, 1997, and the requirements for sprinkler systems under the edition of the NFPA 13 standard referenced by that code. The automatic fire suppression system shall be installed by September 1, 1999. The chief administrative office of the college or university shall obtain a certificate of compliance from the building official of the locality in which the college or university is located or in the case of state-owned buildings, from the Director of the Virginia Department of General Services.

Exceptions:

1. Buildings equipped with an automatic fire suppression system in accordance with Section 903.3.1.1 or the 1983 or later editions of NFPA 13.

2. Any dormitory at a state-supported military college or university which is patrolled 24 hours a day by military guards.

3. Application of the requirements of this section shall be modified in accordance with the following:

3.1. Building systems, equipment or components other than the fire suppression system shall not be required to be added or upgraded except as necessary for the installation of the fire suppression system and shall only be required to be added or upgraded where the installation of the fire suppression system creates an unsafe condition.

3.2. Residential sprinklers shall be used in all sleeping rooms. Other sprinklers shall be quick response or residential unless deemed unsuitable for a space. Standard response sprinklers shall be used in elevator hoist ways and machine rooms.

3.3. Sprinklers shall not be required in wardrobes in sleeping rooms that are considered part of the building construction or in closets in sleeping rooms, when such wardrobes or closets (i) do not exceed 24 square feet (2.23 m²) in area, (ii) have the smallest dimension less than 36 inches (914 mm), and (iii) comply with all of the following:

3.3.1. A single station smoke detector monitored by the building fire alarm system is installed in the room containing the wardrobe or closet that will activate the general alarm for the building if the single station smoke detector is not cleared within five minutes after activation.

3.3.2. The minimum number of sprinklers required for calculating the hydraulic demand of the system for the room shall be increased by two and the two additional sprinklers shall be corridor sprinklers where the wardrobe or closet is used to divide the room. Rooms divided by a wardrobe or closet shall be considered one room for the purpose of this requirement.

3.3.3. The ceiling of the wardrobe, closet or room shall have a fire resistance rating of not less than 1/2 hour.

3.4. Not more than one sprinkler shall be required in bathrooms within sleeping rooms or suites having a floor area between 55 square feet (5.12 m²) and 120 square feet (11.16 m²) provided the sprinkler is located to protect the lavatory area and the plumbing fixtures are of a noncombustible material.

3.5. Existing standpipe residual pressure shall be permitted to be reduced when the standpipe serves as the water supply for the fire suppression system provided the water supply requirements of NFPA 13-94 are met.

3.6. Limited service controllers shall be permitted for fire pumps when used in accordance with their listing.

3.7. Where a standby power system is required, a source of power in accordance with Section 701-11 (d) or 701-11 (e) of NFPA 70—96 shall be permitted.

1715 Fire extinguishers and smoke detectors in State Regulated Care Facilities (RCF). SRCF's shall be provided with at least one approved type ABC portable fire extinguisher with a minimum rating of 2-A:10-B:C installed in each kitchen. In addition, SRCF's shall provide at least one approved and properly installed battery operated smoke detector outside of each sleeping area in the vicinity of bedrooms and bedroom hallways and on each additional floor.

1716 Smoke detectors in adult day care centers. Battery-powered or AC-powered smoke detector devices shall be installed in all adult day care centers licensed by the Virginia Department of Social Services, regardless of when the building was constructed. The location and installation of the smoke detectors shall be determined by the provisions of this code in effect on October 1, 1990. The licensee shall obtain a certificate of compliance from the building official of the locality in which the center is located, or in the case of state-owned buildings from the Director of the Virginia Department of General Services.

1717 Posting of occupant load. Every room or space that is an assembly occupancy, and where the occupant load of that room or space is 50 or more, shall have the occupant load of the room or space as determined by the building official posted in a conspicuous place, near the main exit or exit access doorway from the room or space. Posted signs shall be of an approved legible permanent design and shall be maintained by the owner or authorized agent.

1718 Above ground Liquid Fertilizer Storage Tanks (ALFST) . Existing ALFSTs, regardless of when constructed, shall, by October 1, 2011, meet the applicable requirements of API 653 and TFI RMIP for suitability for service and inspections and shall provide a secondary containment system complying with Section 425.3.

1719 Standards for replacement glass. In accordance with Section 36-99.2 of the Code of Virginia, any replacement glass installed in buildings constructed prior to the first edition of the USBC shall meet the quality and installation standards for glass installed in new buildings as are in effect at the time of installation. In addition, as a requirement of this code, the installation or replacement of glass in buildings constructed under any edition of the USBC shall be as required for new installations.

Supporting Statement (including intent, need, and impact of the proposal):

The 2015 International Code Council series of codes will delete chapter 34 of the IBC and require all change of use, alteration, repair, and renovations to be covered under the International Existing Building Code. This proposed change will make this occur for the 2012 Virginia Uniform Statewide Building Code for all buildings subject to the IBC as identified by use group. Those buildings that are constructed under the IRC will continue to address alterations, repairs, and renovations as they currently are addressed in the VCC.

Since the 2006 version of the IEBC, it has contained a new chapter (Chapter 3) that provide a prescriptive requirements for compliance when a change of use, alteration, reconstruction or repair is undertaken. The current IEBC provides approaches for a prescriptive method, repair, performance, level of alteration, change of use component approach, and a scoring method. Every possible approach to existing building construction activity that was previously addressed in the VCC is now provided for in the IEBC in some form. Having all of the requirements in one document will remove confusion and encourage the use and acceptance of alternative approaches that may encourage creative uses and cost savings. The proposed text, with some additional Virginia modifications, will send all users to one document for these activities without requiring a change to the intended outcome.

An example of where cost savings occurs can be found when meeting the structural loading requirements for a change of use. Currently, the 2009 IBC Chapter 34 requires that the provisions of chapter 16 (structural requirements) be met for a new use. However, the prescriptive method found in Chapter 3 of the IEBC allows an existing condition to remain as long as it does not require greater than a 5% increase over the table values. This could benefit house to office conversions and similar changes where exiting structural capacities are close to the structural live load table values.

There is general consensus within the VBCOA Administration Committee on this code change. However, work is continuing to make sure that all previous IBC Chapter 34 provisions are covered in this proposed change.

Submittal Information

Date Submitted: November 27, 2012

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
600 East Main Street
Suite 300
Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: DRAFT

Proponent Information

(Check one): ☒ Individual ☐ Government Entity ☐ Company

Name: John Catlett

Representing: VBCOA Administration Committee

Mailing Address: 301 King Street, Alexandria, Virginia 22314

Email Address: john.catlett@alexandriava.gov

Telephone Number: 703.746.4182

Proposal Information

Code(s) and Section(s): VMC602.2 and VMC 602.4 Dates for heating and cooling.

Proposed Change (including all relevant section numbers, if multiple sections):

~~602.2 Heat supply. Every owner and operator of any building~~ Every owner and operator of a Group R-2 apartment building or other residential dwelling who rents, leases or lets one or more dwelling unit, rooming unit, dormitory or guestroom on terms, either expressed or implied, to furnish heat to the occupants thereof shall supply heat during the period from October 15 to May 1 to maintain a temperature of not less than 65°F (18°C) in all habitable rooms, bathrooms, and toilet rooms. The code official may also consider modifications as provided in Section 104.5.2 when requested for unusual circumstances or may issue notice approving building owners to convert shared heating and cooling piping HVAC systems 14 calendar days before or after the established dates when extended periods of unusual temperatures merit modifying these dates.

(Remainder unchanged)

~~602.4 Cooling supply. Every owner and operator of a Group R-2 apartment building who rents, leases or lets one or more dwelling units, rooming units or guestrooms on terms, either expressed or implied, to furnish cooling to the occupants thereof shall supply cooling during the period from May 15 to October 1 to maintain a temperature of not more than 80°F (27°C) in all habitable rooms. The code official may also consider modifications as provided in Section 104.5.2 when requested for unusual circumstances or may issue notice approving building owners to convert shared heating and cooling piping HVAC systems 14 calendar days before or after the established dates when extended periods of unusual temperatures merit modifying these dates.~~

Supporting Statement (including intent, need, and impact of the proposal):

The temperature differences throughout the state should be considered when establishing switch over dates between heating and cooling seasons. To assume that the Tidewater area and Northern Shenandoah Valley have the same climatic experiences each year would be incorrect. The provision allows for local official to have latitude based on local experience. The revised language also serves to remind the code official that modifications can be considered and granted during periods of extreme temperature changes from the normal.

The problem arises in older apartment buildings when a physical switch between heating and cooling must occur. The process can take several days and also serves as down time for maintenance. Making the switch back to the previous condition is time consuming. The unusual conditions such as they occurred in the late winter and spring of 2012 served as verification that firm dates may sometimes prove impracticable.

The addition of Group R2 apartment buildings to VMC 602.2 will take away the long term confusion of if these provisions should apply to R2 condominium buildings where renting is not the primary purpose.

TAB 4

Virginia Manufactured Home Safety Regulations

Staff Recommendation for Proposed Regulations for the 2012 Code Change Cycle

13VAC5-95-10. Definitions.

A. The following words and terms when used in this chapter shall have the following meanings unless the context clearly indicates otherwise:

~~"Act" or "the Act"~~ "Federal Act" means the National Manufactured Housing Construction and Safety Standards Act of 1974, Title VI of the Housing and Community Development Act of 1974 as amended (42 USC § 5401 et seq.).

"Administrator" means the Director of DHCD or his designee.

"DHCD" means the Virginia Department of Housing and Community Development.

"Dealer" means any person engaged in the sale, lease, or distribution of manufactured homes primarily to persons who in good faith purchase or lease a manufactured home for purposes other than resale.

"Defect" means a failure to comply with an applicable federal manufactured home construction and safety standard that renders the manufactured home or any part of the home unfit for the ordinary use of which it was intended, but does not result in an imminent risk of death or severe personal injury to occupants of the affected home.

"Distributor" means any person engaged in the sale and distribution of manufactured homes for resale.

"Federal installation standards" means the federal Model Manufactured Home Installation Standards (24 CFR Part 3285).

~~"Federal regulation"~~ "Federal regulations" means the federal Manufactured Home Procedural and Enforcement Regulations, enacted May 13, 1976, under authority granted by § 625 of the Act, and designated as Part 3282, Chapter XX, Title 24 of HUD's regulations (24 CFR Part 3282). ~~(Part 3282 consists of subparts A through L, with sections numbered 3282.1 through 3282.554, and has an effective date of June 15, 1976.)~~

"HUD" means the United States Department of Housing and Urban Development.

"Imminent safety hazard" means a hazard that presents an imminent and unreasonable risk of death or severe personal injury that may or may not be related to failure to comply with an applicable federal manufactured home construction or safety standard.

"Installation" means completion of work to include, but not be limited to, stabilizing, supporting, anchoring and closing-up a manufactured home and joining sections of a multi-section manufactured home, when any such work is governed by the federal installation standards.

"Installer" means the person or entity who is retained to engage in, or who engages in, the business of directing, supervising, controlling or correcting the initial installation of a manufactured home.

"Label," or "certification label" or "HUD label" means the approved form of certification label prescribed by the manufacturer that, under 24 CFR 3282.362(e)(2)(i) of the Manufactured Home Procedural and Enforcement Regulations, is permanently affixed to each transportable section of each manufactured home manufactured for sale to a purchaser in the United States federal standards.

"Local code building official" means the officer or other designated authority charged with the administration and enforcement of USBC, or duly authorized representative.

"Manufactured home" means a structure subject to federal regulation, which is transportable in one or more sections; is eight body feet or more in width and 40 body feet or more in length in the traveling mode, or is 320 or more square feet when erected on site; is built on a permanent chassis; is designed to be used as a single-family dwelling, with or without a permanent foundation, when connected to the required utilities; and includes the plumbing, heating, air conditioning, and electrical systems contained in the structure.

"Manufacturer" means any person engaged in manufacturing or assembling manufactured homes, including any person engaged in importing manufactured homes.

"Noncompliance" means a failure of a manufactured home to comply with a federal manufactured home construction or safety standard that does not constitute a defect, serious defect, or imminent safety hazard.

"Purchaser" means the first person purchasing a manufactured home in good faith for purposes other than resale.

"Secretary" means the Secretary of HUD.

"Serious defect" means any failure to comply with an applicable federal manufactured home construction and safety standard that renders the manufactured home or any part thereof not fit for the ordinary use for which it was intended and which results in an unreasonable risk of injury or death to occupants of the affected manufactured home.

"Standards" or "federal standards" means the federal Manufactured Home Construction and Safety Standards (24 CFR Part 3280) adopted by HUD, in accordance with authority in the Act. The standards were enacted December 18, 1975, and amended May 11, 1976, to become effective June 15, 1976.

"State administrative agency" or "SAA" means DHCD which is responsible for the administration and enforcement of Chapter 4.1 (§ 36-85.2 et seq.) of Title 36 of the Code of Virginia throughout Virginia and of the plan authorized by § 36-85.5 of the Code of Virginia.

"USBC" means the Virginia Uniform Statewide Building Code (13VAC5-63).

B. Terms defined within the federal regulations and standards shall have the same meanings in this chapter.

13VAC5-95-20. Application and enforcement.

A. This chapter shall apply to manufactured homes as defined in 13VAC5-95-10 and 13VAC5-95-20 as set out in this section.

B. Enforcement of this chapter shall be in accordance with the federal regulation regulations.

C. Manufactured homes produced on or after June 15, 1976, shall conform to all the requirements of the federal standards, as amended.

D. DHCD is delegated all lawful authority for the enforcement of the federal standards pertaining to manufactured homes by the administrator according to § 36-85.5 of the Code of Virginia. The Division of Building and Fire Regulation of DHCD is designated as a state administrative agency in the HUD enforcement program, and shall act as an agent of HUD. The administrator is authorized to perform the activities required of an SAA by the HUD enforcement plan including, but not limited to, investigation, citation of violations, handling of complaints, conducting hearings, supervising remedial actions, monitoring, and making such reports as may be required and seeking enforcement of the civil and criminal penalties established by §36-85.12 of the Code of Virginia.

E. All In accordance with § 36-85.11 of the Code of Virginia, all local code building officials are authorized by § 36-85.11 of the Code of Virginia to and shall enforce the provisions of this chapter within the limits of their jurisdiction. Such local code officials shall enforce this chapter, subject to the general oversight of the Division of Building and Fire Regulation and shall not permit the use of any manufactured home containing a serious defect or imminent safety hazard within their jurisdiction, and shall be responsible for the following:

1. Verify through inspection that a manufactured home displays the required HUD label and data plate;

2. Determine whether the manufactured home has been damaged during transit. If the manufactured home has been damaged, then the local code officials are authorized to require tests, in accordance with the federal standards, for tightness of plumbing systems, gas piping and an operational test to insure that all luminaries and receptacles are operable. If a manufactured home has sustained damage to the structural components, the local building official shall require the appropriate design approval primary inspection agency approval on any repairs or designs;

3. Prevent the use of a manufactured home that in the opinion of a local building official contains a serious defect or imminent safety hazard and notify the administrator immediately.

4. Notify the administrator of any apparent violations of this chapter, to include defects and noncompliance that occurred during the manufacturing process and any alterations that occurred during installation; and

5. Verify through inspection that the installation is in accordance with the federal installation standards. Where the local building official finds that the installation of the manufactured home is not in accordance with the federal installation standards, the local building official shall order the home to be brought into compliance within a reasonable time. If the order is not complied with then the local building official shall notify the administrator.

F. Mounting and anchoring In accordance with § 36-85.11 of the Code of Virginia, site preparation, utility connection and skirting installation of manufactured homes shall be in accordance with meet the applicable requirements of the USBC. In addition, as a requirement of this chapter and the USBC, administrative provisions of the USBC, such as requirements for permits, inspections and certificates of occupancy, shall also be applicable.

13VAC5-95-30. Effect of label.

~~A. In accordance with § 36-85.11 of the Code of Virginia, manufactured homes displaying the certification label as prescribed in the federal standards shall be accepted in all localities as meeting the requirements of the Manufactured Housing Construction and Safety Standards Law (Chapter 4.1 (§ 36-85.2 et seq.) of Title 36 of the Code of Virginia), which shall supersede the building codes of the counties, municipalities and state agencies. In addition, as a requirement of this chapter, local code officials shall carry out the following functions with respect to manufactured homes displaying the HUD label, provided such functions do not involve disassembly of the homes or parts of the homes, change of design, or result in the imposition of more stringent conditions than those required by the federal regulations.~~

~~1. Verify through inspection that the manufactured home has not been damaged in transit to a degree that would render it unsafe. If the manufactured home has been damaged, then the local code official is authorized to require tests for tightness of plumbing systems and gas piping, and electrical short circuits at meter connections.~~

~~2. Verify through inspection that (i) supplemental components required by the manufacturer's installation instructions or this chapter are properly provided, (ii) manufacturer's installation or erection instructions are followed, and (iii) any special conditions or limitations of use stipulated by the manufacturer's installation instructions or the label in accordance with the standards or this chapter are followed.~~

~~B. Local code officials are required by the USBC to enforce applicable requirements of the USBC for utility connections, site preparation, foundations, stoops, decks, porches, alterations and additions to existing manufactured homes, building permits, skirting, certificates of use and~~

~~occupancy, and all other applicable requirements, except those governing the design and construction of the labeled units. In addition, local code officials shall verify that a manufactured home displays the required HUD label.~~

13VAC5-95-40. Report to DHCD. (Repealed.)

~~Whenever any manufactured home is moved from a local jurisdiction before a noted violation has been corrected, the local code official shall make a prompt report of the circumstances to the administrator. The report shall include a list of uncorrected violations, all information pertinent to identification and manufacture of the home contained on the label and the data plate, the destination of the home if known, and the name of the party responsible for moving it.~~

13VAC5-95-50. Alterations.

A. No distributor, installer or dealer shall perform or cause to be performed any alteration affecting one or more requirements set forth in the federal standards, ~~except those alterations approved by the administrator~~ unless the alteration is included in the manufacturer's design approval primary inspection agency's approved design and installation instructions.

B. ~~In handling and approving dealer requests for alterations, the administrator may be assisted by local code officials. The local code official shall report violations of subsection A of this section and failures to conform to the terms of their approval to the administrator.~~ In accordance with § 36-99 of the Code of Virginia and the USBC, alterations, additions and repairs associated with existing manufactured homes are subject to Section 424 of the USBC and not this chapter.

13VAC5-95-60. Installations.

Distributors, installers or dealers ~~installing or setting up a manufactured home shall perform such installation in accordance with the manufacturer's installation instructions or other support and anchoring system approved by the local code official in accordance with the USBC.~~

13VAC5-95-70. Prohibited resale. (Repealed.)

~~No distributor or dealer shall offer for resale any manufactured home possessing a serious defect or imminent safety hazard.~~

13VAC5-95-80. Lot inspections.

At any time during regular business hours when a manufactured home is located on a dealer's or distributor's lot and offered for sale, the administrator shall have authority to inspect such home for transit damages, seal tampering, violations of the federal regulations and standards and the dealer's or distributor's compliance with applicable state and federal laws and regulations. The administrator shall give written notice to the dealer or distributor when any home inspected does not comply with the federal regulations and standards or this chapter.

13VAC5-95-90. Consumer complaints; ~~on-site inspections.~~

A. The administrator shall receive all consumer complaints on manufactured homes reported to DHCD by owners, dealers, distributors, ~~code~~ local building officials, and other state or federal agencies. The administrator may request ~~such reports~~ all consumer complaints to be submitted by letter or on a report form supplied by DHCD or in another format acceptable by the administrator.

B. The administrator may conduct, or cause to be conducted, an on-site inspection of a manufactured home at the request of the owner reporting a complaint with the home or under the following conditions with the permission of the owner of the home:

1. The dealer, distributor or manufacturer requests an on-site inspection;
2. The reported complaint indicates extensive and serious noncompliances;
3. Consumer complaints lead the administrator to suspect that a class of homes may be similarly affected; or
4. Review of manufacturer's records, corrective action, and consumer complaint records leads the administrator to suspect secondary or associated noncompliances may also exist in a class of homes.

C. When conducting an on-site inspection of a home involving a consumer complaint, the administrator may request the dealer, distributor, installer and manufacturer of the home to have a representative present to coordinate the inspection and investigation of the consumer complaint.

D. After reviewing the complaint report or the on-site inspection of the home involved, the administrator shall, where possible, indicate the cause of any nonconformance and, where possible, indicate the responsibility of the manufacturer, dealer, distributor, or owner for the noncompliance and any corrective action necessary.

E. The administrator shall ~~refer to~~ notify the manufacturer of the home, in writing, of any consumer complaint concerning that home reported to the administrator. The administrator may shall refer any such reported complaint to HUD, to the SAA in the state where the manufacturer is located and, as necessary, to the inspection agency involved with certifying the home.

F. The administrator shall assist the owner, dealer, distributor, installer and manufacturer in resolving consumer complaints. ~~The administrator shall monitor the manufacturer's performance to assure compliance with Subpart I of the federal regulations for consumer complaint handling and shall take such actions as are necessary to assure compliance of all involved parties with applicable state and federal regulations.~~

G. The administrator shall monitor the manufacturer's performance to assure compliance with Subpart I of the federal regulations for consumer complaint handling and shall take such actions

as are necessary to assure compliance of all involved parties with applicable state and federal regulations.

13VAC5-95-100. Violation; appeal; penalty.

A. ~~Where the administrator finds any violation of the provisions of this chapter, a notice of violation shall be issued. This notice of violation shall order the party responsible to bring the unit into compliance, within a reasonable time.~~

B. ~~Parties aggrieved by the findings of the notice of violation may appeal to the State Building Code Technical Review Board, which shall act on the appeal in accordance with the provisions of the USBC. The aggrieved party shall file the appeal within 10 days of the receipt of the notice of violation. Unless the notice of violation is revoked by the review board, the aggrieved party must comply with the stipulations of the notice of violation.~~

C. ~~Any person, firm or corporation violating any provisions of this chapter shall, upon conviction, be considered guilty of a misdemeanor in accordance with § 36-85.12 of the Code of Virginia. In accordance with § 36-85.12 of the Code of Virginia, it shall be unlawful for any person, firm, or corporation, to violate any provisions of this law, the rules and regulations enacted under authority of this law, or the federal law and regulations. Any person, firm, or corporation violating any provision of said laws, rules, and regulations, or any final order issued there under, shall be liable for civil penalty not to exceed \$1,000 for each violation. Each violation shall constitute a separate violation with respect to each manufactured home or with respect to each failure or refusal to allow or to perform an act required by the legislation or regulations. The maximum civil penalty may not exceed one million dollars for any related series of violations occurring within one year from the date of the first violation.~~

An individual or a director, officer, or agent of a corporation who knowingly and willfully violates Section 610 of the National Manufactured Housing Construction and Safety Standards Act in a manner that threatens the health or safety of any purchaser shall be deemed guilty of a Class 1 misdemeanor and upon conviction fined not more than \$1,000 or imprisoned not more than one year, or both.

TAB 5

Virginia Industrialized Building Safety Regulations

Staff Recommendation for Proposed Regulations for the 2012 Code Change Cycle

13VAC5-91-10. Definitions.

The following words and terms when used in this chapter shall have the following meanings unless the context clearly indicates otherwise.

“Administrator” means the Director of DHCD or his designee.

“Approved” as applied to a material, device, method of construction, registered building, or as otherwise used in this chapter means approved by the administrator.

“Building official” means the officer or other designated authority charged with the administration and enforcement of the USBC, or duly authorized representative.

“Compliance assurance agency” means an architect or professional engineer registered in Virginia, or an organization, determined by DHCD to be specially qualified by reason of facilities, personnel, experience, and demonstrated reliability, to investigate, test and evaluate industrialized buildings; to list such buildings complying with standards at least equal to this chapter; to provide adequate follow-up services at the point of manufacture to ensure that production units are in full compliance; and to provide a label as evidence of compliance on each manufactured section or module.

“DHCD” means the Virginia Department of Housing and Community Development.

“ICC” means the International Code Council, Inc.

“Industrialized building” means a combination of one or more sections or modules, subject to state regulations and including the necessary electrical, plumbing, heating, ventilating, and other service systems, manufactured off-site and transported to the point of use for installation or erection, with or without other specified components, to comprise a finished building. Manufactured homes defined in § 36-85.3 of the Code of Virginia and certified under the provisions of the National Manufactured Housing Construction and Safety Standards Act (42 USC § 5401 et seq.) shall not be considered industrialized buildings for the purpose of this law.

“Label,” “certification label” or “compliance assurance agency certification label” means the label required by 13VAC5-91-210.

“Model” means a specific design of an industrialized building designated by the producer of the building including production buildings with variations and options that do not affect compliance with the standards governing structural, plumbing, mechanical, or electrical systems or any other items governed by this chapter.

“Registered” means an industrialized building which displays a registration seal issued by DHCD in accordance with this chapter.

“Seal,” “registration seal” or “Virginia registration seal” means the seal required by 13VAC5-91-260.

"SBCAO" "SBCO" means the State Building Code Administrative Codes Office within DHCD.

"State Review Board" means the Virginia State Building Code Technical Review Board as established by § 36-108 of the Code of Virginia.

"This law" means the Virginia Industrialized Building Safety Law as embraced in Chapter 4 (§ 36-70 et seq.) of Title 36 of the Code of Virginia.

"USBC" means the Virginia Uniform Statewide Building Code (13VAC5-63).

13VAC5-91-20. Application and compliance.

A. In accordance with § 36-81 of the Code of Virginia, registered industrialized buildings shall be acceptable in all localities as meeting the requirements of the Industrialized Building Safety Law (Chapter 4 (§ 36-70 et seq.) of Title 36 of the Code of Virginia), which shall supersede the building codes and regulations of the counties, municipalities and state agencies. Local requirements affecting industrialized buildings, including zoning, utility connections, preparation of the site and maintenance of the unit shall remain in full force and effect. All building officials are authorized to and shall enforce the provisions of the Industrialized Building Safety Law (Chapter 4 (§ 36-70 et seq.) of Title 36 of the Code of Virginia) and this chapter.

B. In accordance with § 36-78 of the Code of Virginia, no person, firm or corporation shall offer for sale or rental, or sell or rent, any industrialized building subject to any provisions of this chapter unless it conforms with the applicable provisions of this chapter.

Further, any industrialized building constructed before January 1, 1972, shall remain subject to the ordinances, laws or regulations in effect at the time such industrialized building was constructed. Additionally, as a requirement of this chapter, any industrialized building bearing the label of a compliance assurance agency shall remain subject to the provisions of this chapter that were effective when such building was constructed, regardless of whether the building has been relocated.

C. In accordance with § 36-99 of the Code of Virginia and in accordance with the USBC, the installation or erection of industrialized buildings and alterations, additions, or repairs to industrialized buildings are regulated by the USBC and not this chapter. The USBC provides for administrative requirements for permits, inspections, and certificates of occupancy for such work.

D. Shipping containers and portable on-demand storage (PODS) containers are not subject to this chapter.

13VAC5-91-30. Purpose.

The purpose of this chapter is to ensure safety to life, health, and property through compliance with uniform statewide construction standards for industrialized buildings.

13VAC5-91-40. Inspection and enforcement by administrator.

A. The SBCAO SBCO is designated as the administrator's representative for the enforcement of this chapter and shall act as the building official for registered industrialized buildings. It shall have authority to make inspections during reasonable hours at the manufacturing facilities and at building

sites where industrialized buildings are being installed. The SBCAO SBCO shall have authority to issue inspection reports for correction of violations caused by the manufacturer and to take such other actions as are required to enforce this chapter.

B. The SBCAO SBCO will maintain a list of approved compliance assurance agencies. Each manufacturer producing registered industrialized buildings will contract with one or more compliance assurance agencies for required evaluation, monitoring and inspection services. The contract will delineate the services to be provided by the compliance assurance agency. The compliance assurance agency will notify the SBCAO SBCO within 30 days of signing a new contract or terminating an existing contract with any manufacturer.

13VAC5-91-50. Right of entry and examination by administrator.

In accordance with § 36-82 of the Code of Virginia, the administrator shall have the right, at all reasonable hours, to enter into any industrialized building upon permission of any person who has authority or shares the use, access, or control over the building, or upon request from local officials having jurisdiction, for examination as to compliance with this chapter.

13VAC5-91-60. Notice of violation from administrator.

In accordance with § 36-82 of the Code of Virginia, whenever the administrator shall find any violation of this chapter, he shall order the person responsible therefor to bring the building into compliance within a reasonable time, to be fixed in the order. In addition, as a requirement of this chapter, the administrator may request assistance from the building official for enforcement of this section. Any order issued by the administrator pursuant to this section shall contain a statement explaining the right of appeal of the order.

13VAC5-91-70. Appeals.

Any person aggrieved by DHCD's application of this chapter shall be heard by the State Review Board established by § 36-108 of the Code of Virginia. Such appeal shall be submitted within 21 calendar days of receipt of DHCD's decision. A copy of the decision of DHCD to be appealed shall be submitted with the application for appeal. Failure to submit an application for appeal within the time limit established by this section shall constitute acceptance of DHCD's decision.

13VAC5-91-80. Limitation of manufacturer's liability.

The manufacturer of a registered industrialized building shall not be required to remedy violations caused by on-site work by others not under his control or violations involving components and materials furnished by others and not included with the registered industrialized building.

13VAC5-91-90. Penalty for violation.

In accordance with § 36-83 of the Code of Virginia, any person, firm or corporation violating any provisions of this chapter shall be considered guilty of a Class 1 misdemeanor and, upon conviction, shall be fined not more than \$1,000.

13VAC5-91-100. Duties and responsibilities of building officials in the installation or erection of a registered industrialized building.

A. All building officials are authorized by § 36-81 of the Code of Virginia to enforce the provisions of this chapter and shall be responsible for and authorized to do the following:

1. Verify through inspection that the registered industrialized building displays the required state registration seal and the proper label of the compliance assurance agency.
2. Verify through inspection that the registered industrialized building has not been damaged in transit to a degree that would render it unsafe. If the building has been damaged, then the building official is authorized to require tests for tightness of plumbing systems and gas piping and an operational test to ensure that all luminaries and receptacles are operable.
3. ~~Prevent the use or occupancy of a registered industrialized building that in the opinion of the building official contains a serious defect or imminent safety hazard and notify the SBCAO immediately. If warranted due to the nature of any violations discovered, the building official shall be permitted to require the correction of any violations of this chapter before occupancy of the registered industrialized building is permitted.~~
4. Notify the ~~SBCAO~~ SBCO of any apparent violations of this chapter ~~to include defects and noncompliance.~~

B. In accordance with § 36-99 of the Code of Virginia and the USBC, all site work associated with the installation or erection of an industrialized building is subject to the USBC. In addition, under the USBC, all administrative requirements for permits, inspections, and certificates of occupancy are also applicable.

13VAC5-91-115. Change of occupancy classification.

When the occupancy classification of a registered industrialized building is proposed to be changed, a compliance assurance agency shall inspect the building, including any disassembly necessary, to determine whether compliance may be achieved for a change of occupancy classification in accordance with ~~the USBC this chapter~~. If factory plans are available, then disassembly is not required to the extent that the factory plans can be reasonably verified to reflect the actual construction. Once any necessary work is completed, the compliance assurance agency shall prepare a report documenting the method utilized for the change of occupancy and any alterations to the building to achieve compliance. When the report is complete, the compliance assurance agency shall (i) mark the building with a new compliance assurance agency label in accordance with 13VAC5-91-210, which replaces the existing label; (ii) place a new manufacturer's data plate on the building in accordance with 13VAC5-91-245, which replaces the existing manufacturer's data plate and reflects the new occupancy classification; and (iii) forward a copy of the report and new data plate to the ~~SBCAO~~ SBCO.

13VAC5-91-120. Unregistered industrialized buildings.

A. The building official shall determine whether any unregistered industrialized building complies with this chapter and shall require any noncomplying unregistered building to be brought into compliance with this chapter. The building official shall enforce all applicable requirements of this chapter including those relating to the sale, rental and disposition of noncomplying buildings. The building official may require submission of full plans and specifications for each building. Concealed parts of the building may be exposed to the extent necessary to permit inspection to determine

compliance with the applicable requirements. The building official may also accept reports of inspections and tests from individuals or agencies deemed acceptable to the building official.

~~B. Unregistered industrialized buildings offered for sale in this Commonwealth shall be marked by a warning sign to prospective purchasers that the building is not registered in accordance with this chapter and must be inspected and approved by the building official. The sign shall be of a size and form approved by the administrator and shall be conspicuously posted on the exterior of the unit near the main entrance door. This requirement shall not apply to residential accessory buildings.~~

~~C. An existing unregistered industrialized building may be registered in accordance with one of the following:~~

1. Where an unregistered building was constructed under an industrialized building program of another state and approved under such program, a compliance assurance agency shall prepare a report based on review of the plans and specifications and inspection of the building to determine whether there is compliance with the construction requirements of this chapter that were in effect on the date of manufacture of the building. If compliance is determined, the compliance assurance agency shall (i) mark the building with a compliance assurance agency label in accordance with 13VAC5-91-210, (ii) place a new manufacturer's data plate on the building in accordance with 13VAC5-91-245, (iii) mark the building with a registration seal in accordance with 13VAC5-91-260, and (iv) forward a copy of the report and new data plate to the ~~SBCAO~~ SBCO.

2. Where an unregistered building was not approved under an industrialized building program of another state and the date of manufacture can be verified, the compliance assurance agency shall inspect the building, including any disassembly necessary, to determine whether there is compliance with the construction requirements of this chapter that were in effect on the date of manufacture of the building. When factory plans are available, then disassembly is not required to the extent that the factory plans can be verified to reflect the actual construction of the building. When compliance with the construction requirements of this chapter that were in effect on the date of manufacture of the building is achieved, the compliance assurance agency shall prepare a report documenting compliance, outlining any changes made to the building, and certifying the building in accordance with clauses (i) through (iv) of subdivision 1 of this subsection.

3. When the date of manufacture of the existing unregistered building cannot be verified, the building shall be evaluated for compliance with the codes and standards specified in 13VAC5-91-160. The compliance assurance agency shall inspect the building, including any disassembly necessary, to determine whether there is compliance with these construction requirements. If compliance is achieved, the compliance assurance agency shall prepare a report documenting compliance, outlining any changes made to the building, and certifying the building in accordance with clauses (i) through (iv) of subdivision 1 of this subsection.

13VAC5-91-130. ~~Disposition of noncomplying building. (Repealed.)~~

~~When a building is found to be in violation of this chapter, the building official may require the violations to be corrected before occupancy of the building is permitted.~~

13VAC5-91-140. Report to the ~~SBCAO~~ SBCO.

If the building is moved from the jurisdiction before the violations have been corrected, the building official shall make a prompt report of the circumstances to the ~~SBCAO~~ SBCO. The report shall include all of the following:

1. A list of the uncorrected violations.
2. All information contained on the label pertinent to the identification of the building, the manufacturer and the compliance assurance agency.
3. The number of the Virginia registration seal.
4. The new destination of the building, if known.
5. The party responsible for moving the building.

13VAC5-91-150. When modification may be granted.

~~A. The administrator shall have the power upon request in specific cases to authorize modification of this chapter so as to permit certain specified alternatives where the objectives of this law can still be fulfilled. Such request shall be in writing and shall be accompanied by the plans, specifications and other information necessary for an adequate evaluation of the modification requested.~~

~~B. Before a modification is authorized, the building official may be afforded an opportunity to present his views and recommendations.~~

13VAC5-91-160. Use of model codes and standards.

A. Industrialized buildings produced after the effective date of the ~~2009~~ 2012 edition of this chapter shall comply with all applicable requirements of the codes and standards listed in subsection B of this section except that the following codes and standards may be used for ~~90 days~~ one year after the effective date of the ~~2009~~ 2012 edition of this chapter:

1. ICC International Building Code – ~~2006~~ 2009 Edition
2. ICC International Plumbing Code – ~~2006~~ 2009 Edition
3. ICC International Mechanical Code – ~~2006~~ 2009 Edition
4. National Fire Protection Association Standard Number 70 (National Electrical Code) – ~~2005~~ 2008 Edition
5. ICC International Fuel Gas Code – 2009 Edition
6. ICC International Energy Conservation Code – 2009 Edition
7. ICC International Residential Code – ~~2006~~ 2009 Edition

B. The following documents are adopted and incorporated by reference to be an enforceable part of this chapter:

1. ICC International Building Code – 2009 2012 Edition
2. ICC International Plumbing Code – 2009 2012 Edition
3. ICC International Mechanical Code – 2009 2012 Edition
4. National Electrical Code – 2008 2011 Edition
5. ICC International Fuel Gas Code – 2012 Edition
6. ICC International Energy Conservation Code – 2012 Edition
7. ICC International Residential Code – 2009 2012 Edition

Note: As the 2009 2012 editions of the International Codes are incorporated by reference as the construction standards for use with these regulations, this chapter is also referred to as the 2009 2012 edition of the Virginia Industrialized Building Safety Regulations or the 2009 2012 edition of this chapter.

The codes and standards referenced above may be procured from:

International Code Council, Inc.
500 New Jersey Avenue, NW, 6th Floor
Washington, DC 20001-2070

13VAC5-91-170. Amendments to codes and standards.

A. All requirements of the referenced model codes and standards that relate to fees, permits, certificates of use and occupancy, approval of plans and specifications, and other procedural, administrative and enforcement matters are deleted and replaced by the procedural, administrative and enforcement provisions of this chapter and the applicable provisions of Chapter 4 of the USBC.

B. The referenced codes and standards are amended as set forth in the USBC.

13VAC5-91-180. Compliance assurance agencies.

A. Application may shall be made to the SBCAO SBCO for acceptance as a compliance assurance agency. Application shall be made under oath and shall be accompanied by information and evidence that is adequate for the SBCAO SBCO to determine whether the applicant is specially qualified by reason of facilities, personnel, experience and demonstrated reliability to investigate, test and evaluate industrialized buildings for compliance with this chapter, and to provide adequate follow-up and compliance assurance services at the point of manufacture.

B. Following a determination by the SBCO that an application is complete, the information contained in the application and any other information deemed necessary by the SBCO will be reviewed for approval or disapproval. If the application is approved, the applicant will be notified with an approval letter for a two-year period from the date of the approval letter. If the application is disapproved, the applicant will be notified in writing of the reasons for the disapproval. The applicant may then

resubmit the application within 30 days of the receipt of the notification of disapproval for reconsideration of approval.

C. Compliance assurance agencies which are already approved by the SBCO at the time of the effective date of this provision shall have 90 days from the effective date of this provision to apply for re-approval in accordance with subsections A and B of this section. Such agencies shall continue to be approved while the SBCO evaluates the reapplication. Compliance assurance agencies receiving an approval letter from the SBCO after the effective date of this provision shall apply for re-approval within 90 days prior to the expiration of the two-year approval period if continued approval as a compliance assurance agency is desired.

D. The SBCO may suspend or revoke the approval of a compliance assurance agency upon a determination that (i) approval or re-approval was based upon fraudulent or inaccurate information, (ii) a change in facts or circumstances renders the agency incapable of meeting its duties and responsibilities as a compliance assurance agency in a satisfactory manner, or (iii) the agency failed to discharge its duties and responsibilities as a compliance assurance agency in a satisfactory manner. In such cases, the SBCO will issue a suspension or revocation notice to the agency outlining the reasons for the actions and the terms, if any, for reinstatement.

13VAC5-91-190. Freedom from conflict of interest.

A compliance assurance agency shall not be affiliated with, nor influenced or controlled by, producers, suppliers or vendors of products in any manner which might affect its capacity to render reports of findings objectively and without bias. A compliance assurance agency is judged to be free of such affiliation, influence and control if it complies with all of the following conditions:

1. The agency has no managerial affiliation with producers, suppliers or vendors and is not engaged in the sale or promotion of any product or material.
2. The results of the agency's work accrue no financial benefits to the agency through stock ownership of, or other similar affiliation to, any producer, supplier or vendor of the product involved.
3. The agency's directors and other management personnel in their job capacities receive no stock option or other financial benefit from any producer, supplier or vendor of the product involved.
4. The agency has sufficient interest or activity that the loss or award of a specific contract to determine compliance of a producer's, supplier's or vendor's product with this chapter would not be a determining factor in its financial well-being.
5. The employment security status of the agency's personnel is free of influence or control by producers, suppliers or vendors.

13VAC5-91-200. Information required by the administrator.

All of the following information and criteria will be considered by the administrator in designating compliance assurance agencies:

1. Names of officers and location of offices.

2. Specification and description of services proposed to be furnished under this chapter.
3. Description of qualifications of personnel and their responsibilities, including an assurance that personnel involved in system analysis, design and plans review, compliance assurance inspections, and their supervisors comply with the requirements of the American Society for Testing and Material (ASTM) Standard Number E541-08 - Standard Specification for Agencies Engaged in System Analysis and Compliance Assurance for Manufactured Building or shall obtain ICC or DHCD certifications in the appropriate subject area within 18 months of employment and maintain such certifications in an active status.
4. Summary of experience within the organization.
5. General description of procedures and facilities to be used in proposed services, including evaluation of the model, factory follow-up, quality assurance, labeling of production buildings, and specific information to be furnished on or with labels.
6. Procedures to deal with any defective buildings resulting from oversight.
7. Acceptance of these services by independent accrediting organizations and by other jurisdictions.
8. Proof of independence and absence of conflict of interest.

The ASTM Standard Number E541-08 may be procured from:

American Society for Testing and Materials
100 Barr Harbor Drive
West Conshohocken, PA 19428-2959

13VAC5-91-210. Compliance assurance agency certification label.

~~Every manufactured section or module of a registered~~ A. Registered industrialized building buildings shall be marked with a label certification labels supplied by the compliance assurance agency that includes the name and address of the compliance assurance agency and the certification label number. The labels shall be applied to registered industrialized buildings intended for sale or use in Virginia and shall be applied prior to the shipment of the building from the place of manufacture. The labels shall be applied by the compliance assurance agency or by the manufacturer when so authorized by the compliance assurance agency.

B. Registered industrialized buildings shall bear one certification label on each manufactured section or module, or as an alternative, the certification label for each manufactured section or module may be placed in one location in the completed building.

13VAC5-91-220. Mounting of compliance assurance agency certification label.

To the extent practicable, the certification label shall be installed so that it cannot be removed without destroying it. The label shall be applied in the vicinity of the electrical distribution panel or in another location that is readily accessible for inspection and shall be installed near the registration seal. When a

~~building is comprised of more than one section or module, the required label may be furnished as a single label for the entire building provided each section or module is marked by the compliance assurance agency in a clearly identifiable manner provided with or on the label.~~

13VAC5-91-240. ~~Label control~~ Control of compliance assurance agency certification label.

The labels shall be under direct control of the compliance assurance agency until applied by the manufacturer to buildings that comply fully with this chapter. The manufacturer shall place its order for labels with the compliance assurance agency. The manufacturer is not permitted to acquire labels from any other source. Each compliance assurance agency shall keep a list of the serial numbers of labels issued to each manufacturer's plant in such manner that a copy of the record can be submitted to the administrator upon request.

13VAC5-91-245. Manufacturer's data plate.

A. All of the following information shall be placed on a permanent manufacturer's data plate in the vicinity of the electrical distribution panel or in some other location that is readily accessible for inspection. The compliance assurance agency shall approve the form and location of the data plate and shall ensure that the data plate is complete:

1. Manufacturer's name and address.
2. Compliance assurance agency certification number.
3. Serial number of each module of the building.
4. Serial number of the Virginia registration seal.
5. Date of manufacture of the building.
6. List of codes and standards under which the building was evaluated and constructed and the type of construction and occupancy classification under those codes and standards.
7. Design live roof load, design floor live load, design wind speed, and design ground snow load.
8. Thermal resistance ("R") values.
9. Special conditions or limitations concerning the use of the building under the codes and standards applicable to the building; however, a list of such conditions or limitations that are furnished separately with the building shall satisfy this requirement.
10. Special instructions for handling, installation and erection of the building; however, a list of such instructions that are furnished separately with the building shall satisfy this requirement.
11. Designation of electrical service ratings, directions for water and drain connections and, where applicable, identification of permissible type of gas for appliances.
12. Name of manufacturer and model designation of major factory installed appliances.

B. The manufacturer shall maintain copies of the data plate and reports of inspection, tests and any corrective action taken for a minimum period of 10 years from the date of manufacture of the building.

13VAC5-91-250. Industrialized buildings eligible for registration.

Any industrialized building must meet all of the following requirements to be registered and eligible for a Virginia registration seal:

1. The design of the building has been found by a compliance assurance agency to be in full compliance with this chapter. Approved designs shall be evidenced by the stamp and date of approval on each design sheet by the compliance assurance agency.
2. The compliance assurance agency has conducted any necessary testing and evaluation of the building and its component parts.
3. The compliance assurance agency has provided the required inspections and other quality assurance follow-up services at the point of manufacture to assure the building complies with this chapter.
4. The building contains the appropriate evidence of such compliance through a label permanently affixed by the compliance assurance agency.

13VAC5-91-260. Registration seal for industrialized buildings.

A. Registered industrialized buildings shall be marked with approved registration seals issued by the SBCAO SBCO. The seals shall be applied by the manufacturer to a registered industrialized building intended for sale or use in Virginia prior to the shipment of the building from the place of manufacture. The seals shall be applied by the compliance assurance agency or by the manufacturer when authorized to do so by the compliance assurance agency.

B. Registered industrialized buildings shall bear one registration seal on each manufactured section or module, or, as an alternative, the registration seal for each manufactured section or module may be placed in one location in the completed building.

C. Approved registration seals may shall be purchased from the SBCAO SBCO in advance of use. The fee for each registration seal shall be \$75, except that the fee for each registration seal for buildings constructed as Group R-5 under Part I of the USBC shall be \$50. Fees shall be submitted by checks made payable to "Treasurer of Virginia" or shall be submitted by electronic means. Payment for the seals must be received by the SBCAO SBCO before the seals can be sent to the user.

D. To the extent practicable, the registration seal shall be installed so that it cannot be removed without destroying it. The seal shall be applied in the vicinity of the electrical distribution panel or in another location that is readily accessible for inspection and shall be installed near the certification label applied by the compliance assurance agency.

E. The compliance assurance agency or the manufacturer under the supervision of the compliance assurance agency shall maintain permanent records of the disposition of all Virginia registration seals obtained by the compliance assurance agency or manufacturer.

F. Refunds of seals shall be in accordance with § 36-85.1 of the Code of Virginia. An administrative and processing fee of 25% of the amount of the refund due shall be deducted from the refund; however, such deduction shall not exceed \$250.00.

13VAC5-91-270. Manufacturer's installation instructions and responsibilities of installers.

A. The manufacturer of each industrialized building shall provide specifications or instructions, or both, with each building for handling, installing or erecting the building. Such instructions may be included as part of the label from the compliance assurance agency or may be furnished separately by the manufacturer of the building. The manufacturer shall not be required to provide the foundation and anchoring equipment for the industrialized building.

B. Persons or firms installing or erecting registered industrialized buildings shall install or erect the building in accordance with the manufacturer's instructions.

C. Where the installation or erection of an industrialized building utilizes components that are to be concealed, the installer shall notify and obtain approval from the building official prior to concealment of such components unless the building official has agreed to an alternative method of verification.

Note: The Virginia Department of Professional and Occupational Regulation's Board for Contractors requires licenses for certain activities related to the industrialized building industry. For more information, contact the Board for Contractors.

TAB 6

Virginia Amusement Device Regulations (VADR)

Base Document for 2012 Code (Starts with Virginia Code Commission database and adds amendments to use the newest ASTM standards, plus has editorial corrections)

Part I - General Provisions

13VAC5-31-10. Purpose.

A. The purpose of this chapter is to establish standards for the regulation, design, construction, maintenance, operation, and inspection of amusement devices.

B. The provisions of the USBC, including but not limited to all administrative procedures shall apply in the administration and enforcement of this chapter and to amusement devices to the extent such provisions are not superseded by the provisions of this chapter.

13VAC5-31-20. Definitions.

A. The following words and terms when used in this chapter shall have the following meanings unless the context clearly indicates otherwise:

“Amusement device” means (i) a device or structure open to the public by which persons are conveyed or moved in an unusual manner for diversion, but excluding snow tubing parks and rides, ski terrain parks, ski slopes, and ski trails, and (ii) passenger tramways.

“Bungee cord” means the elastic rope to which the jumper is attached which lengthens and shortens to produce a bouncing action.

“Carabineer” means a shaped metal device with a gate used to connect sections of a bungee cord, jump rigging, equipment, or safety gear.

“DHCD” means the Virginia Department of Housing and Community Development.

“Gravity ride” means a ride that is installed on an inclined surface, which depends on gravity for its operation to convey a passenger from the top of the incline to the bottom, and which conveys a passenger in or on a carrier tube, bag, bathing suit, or clothes.

“Ground operator” means a person who assists the jump master to prepare a jumper for jumping.

“Harness” means an assembly to be worn by a bungee jumper to be attached to a bungee cord. It is designed to prevent the wearer from becoming detached from the bungee system.

“Jump master” means a person who has responsibility for the bungee jumper and who takes the jumper through the final stages to the actual jump.

“Jump zone” means the space bounded by the maximum designed movements of the bungee jumper.

“Jumper” means the person who departs from a height attached to a bungee system.

“Kiddie ride” means an amusement device where the passenger or patron height is limited to 54 inches or less, the design capacity of passengers or patrons is 12 or less, and the assembly time for the device is two hours or less.

“Landing area” means the surface area of ground or water directly under the jump zone, the area where the lowering device moves the bungee jumper to be landed away from the jump space and the area covered by the movement of the lowering device.

“Local building department” means the agency or agencies of the governing body of any city, county or town in this Commonwealth charged with the enforcement of the USBC.

“Operating manual” means the document that contains the procedures and forms for the operation of bungee jumping equipment and activity at a site.

“Passenger tramway” means a device used to transport passengers uphill, and suspended in the air by the use of steel cables, chains or belts, or ropes, and usually supported by trestles or towers with one or more spans.

“Platform” means the equipment attached to the structure from which the bungee jumper departs.

“Private inspector” means a person performing inspections who is independent of the company, individual or organization owning, operating or having any vested interest in an amusement device being inspected.

“Ultimate tensile strength” means the greatest amount of load applied to a bungee cord prior to failure.

“USBC” means the Virginia Uniform Statewide Building Code (13VAC5-63).

B. Words and terms used in this chapter which are defined in the USBC shall have the meaning ascribed to them in that regulation unless the context clearly indicates otherwise.

C. Words and terms used in this chapter which are defined in the standards incorporated by reference in this chapter shall have the meaning ascribed to them in those standards unless the context clearly indicates otherwise.

13VAC5-31-30. Exemptions.

The following equipment or devices shall not be considered amusement devices subject to this chapter:

1. Nonmechanized playground or recreational equipment such as swing sets, sliding boards, climbing bars, jungle gyms, skateboard ramps and similar equipment where no

admission fee is charged for its use or for admittance to areas where the equipment is located;

2. Coin-operated rides designed to accommodate three or less passengers; and

3. Water slides or similar equipment used in community association, community club or community organization swimming pools.

13VAC5-31-40. Incorporated standards.

A. The following standards are hereby incorporated by reference for use as part of this chapter:

1. American National Standards Institute (ANSI) Standard No. ~~B77.1-2006~~ B77.1-2011 for the regulation of passenger tramways; and

2. American Society for Testing and Materials (ASTM) Standard Nos. ~~F698-94 (Reapproved 2000)~~, ~~F747-06~~, ~~F770-06a~~ F770-11, ~~F846-92 (Reapproved 2003 2009)~~, ~~F853-05~~, ~~F893-05a~~ F893-10, ~~F1159-03a~~, ~~F1193-06~~, ~~F1305-94 (Reapproved 2002)~~, ~~F1950-99~~, ~~F1957-99 (Reapproved 2004 2011)~~, ~~F2007-06~~ F2007-11, ~~F2137-09~~ F2137-11, ~~F2291-09b~~ F2291-11, ~~F2374-07a~~ F2374-10, ~~F2375-09~~, ~~F2376-06~~ F2376-08 and ~~F2460-06~~ F2460-11 for the regulation of amusement devices.

The standards referenced above may be procured from:

ANSI
25 W 43rd Street
New York, NY 10036

ASTM
100 Barr Harbor Dr.
West Conshohocken, PA 19428-2959

B. The provisions of this chapter govern where they are in conflict with any provisions of the standards incorporated by reference in this chapter.

C. The following requirements supplement the provisions of the ASTM standards incorporated by reference in this chapter:

1. The operator of an amusement device shall be at least 16 years of age, except when the person is under the supervision of a parent or guardian and engaged in activities determined not to be hazardous by the Commissioner of the Virginia Department of Labor and Industry;

2. The amusement device shall be attended by an operator at all times during operation except that (i) one operator is permitted to operate two or more amusement devices provided they are within the sight of the operator and operated by a common control panel or station and (ii) one operator is permitted to operate two kiddie rides with separate controls provided the distance between controls is no more than 35 feet and the controls are equipped with a positive pressure switch; and

3. The operator of an amusement device shall not be (i) under the influence of any drugs which may affect the operator's judgment or ability to assure the safety of the public or (ii) under the influence of alcohol.

D. Where an amusement device was manufactured under previous editions of the standards incorporated by reference in this chapter, the previous editions shall apply to the extent that they are different from the current standards.

13VAC5-31-50. Certification of amusement device inspectors.

A. Any person, including local building department personnel, inspecting an amusement device relative to a certificate of inspection shall possess certification as an amusement device inspector in accordance with the Virginia Certification Standards (13VAC5-21).

B. Local building department personnel enforcing this chapter and private inspectors shall attend periodic maintenance training as designated by DHCD. In addition to the periodic maintenance training required above, local building department personnel and private inspectors shall attend 16 hours of continuing education every two years as approved by DHCD. If local building department personnel or private inspectors possess more than one BHCD certificate, the 16 hours shall satisfy the continuing education requirement for all BHCD certificates.

13VAC5-31-60. Appeals.

Appeals from the local building department concerning the application of this chapter shall be made to the local board of building code appeals established by the USBC. Application for appeal shall be filed with the local building department within 14 calendar days after receipt of the decision of the local building department. The board of appeals shall hear the appeal within seven calendar days after the application for appeal is filed. After final determination by the board, any person who was a party to the appeal may appeal to the Technical Review Board within 14 calendar days of receipt of the decision to be appealed. Such appeal shall be in accordance with the procedures established in the USBC, under the authority granted by § 36-98.3 of the Code of Virginia where the provisions of Chapter 6 of Title 36 of the Code of Virginia and the USBC apply to amusement devices.

NOTE: Because of the short time frames normally associated with amusement device operations, DHCD staff will be available to assist in finding a timely resolution to disagreements between owners or operators and the local building department upon request by either party.

Part II - Enforcement, Permits and Certificates of Inspection

13VAC5-31-75. Local building department.

A. In accordance with §§ 36-98.3 and 36-105 of the Code of Virginia, the local building department shall be responsible for the enforcement of this chapter and may charge fees for such enforcement activity. The total amount charged for any one permit to operate an

amusement device or devices or the renewal of such permit shall not exceed the following, except that when a private inspector is used, the fees shall be reduced by 50%:

1. \$25 for each kiddie ride covered by the permit;
2. \$35 for each circular ride or flat-ride less than 20 feet in height covered by the permit;
3. \$55 for each spectacular ride covered by the permit that cannot be inspected as a circular ride or flat-ride in subdivision 2 of this subsection due to complexity or height; and
4. \$150 for each coaster covered by the permit that exceeds 30 feet in height.

B. Notwithstanding the provisions of subsection A of this section, when an amusement device is constructed in whole or in part at a site for permanent operation at that site and is not intended to be disassembled and moved to another site, then the local building department may utilize permit and inspection fees established pursuant to the USBC to defray the cost of enforcement. This authorization does not apply to an amusement device that is only being reassembled, undergoing a major modification at a site or being moved to a site for operation.

C. A permit application shall be made to the local building department at least five days before the date in which the applicant intends to operate an amusement device. The application shall include the name of the owner, operator or other person assuming responsibility for the device or devices, a general description of the device or devices including any serial or identification numbers available, the location of the property on which the device or devices will be operated and the length of time of operation. The permit application shall indicate whether a private inspector will be utilized. If a private inspector is not utilized, the applicant shall give reasonable notice when an inspection is sought and may stipulate the day such inspection is requested provided it is during the normal operating hours of the local building department. In addition to the information required on the permit application, the applicant shall provide proof of liability insurance of an amount not less than \$1,000,000 per occurrence or proof of equivalent financial responsibility. The local building department shall be notified of any change in the liability insurance or financial responsibility during the period covered by the permit.

D. Notwithstanding the provisions of subsection C of this section, a permit application is not required for a kiddie ride that has an unexpired certificate of inspection issued by any local building department in this Commonwealth. In such cases, the local building department shall be notified prior to the operation of the kiddie ride and the information required on a permit application as listed in subsection C of this section shall be provided to the local building department.

E. Local building department personnel shall examine the permit application within five days and issue the permit if all requirements are met. A certificate of inspection for each amusement device shall be issued when the device has been found to comply with this chapter by a private inspector or by an inspector from the local building department. It shall be the responsibility of the local building department to verify that the private inspector possesses a valid certificate of competence as an amusement device inspector from the Virginia Board of

Housing and Community Development. In addition, local building department personnel shall be responsible for assuring that the certificate of inspection is posted or affixed on or in the vicinity of the device in a location visible to the public. Permits shall indicate the length of time the device or devices will be operated at the site, clearly identify the device or devices to which it applies and the date of expiration of the permit. Permits shall not be valid for longer than one year.

F. In addition to obtaining a certificate of inspection in conjunction with a permit application for amusement devices permanently fixed to a site, a new certificate of inspection shall also be obtained prior to the operation of an amusement device following a major modification, prior to each seasonal operation of a device, at least once during the operating season and prior to resuming the operation of a device following an order from a local building department to cease operation. This requirement shall not apply to kiddie rides meeting the conditions outlined in subsection D of this section.

G. For amusement devices manufactured prior to 1978, the owner or operator shall have the information required by §§ 2.1 through 2.6 of ASTM F698 available at the time of inspection. In addition, the operator of any amusement device shall be responsible for obtaining all manufacturer's notifications, service bulletins and safety alerts issued pursuant to ASTM F853 and the operator shall comply with all recommendations and requirements set out in those documents. A copy of all such documents shall be made available during an inspection.

H. In the enforcement of this chapter, local building department personnel shall have authority to conduct inspections at any time an amusement device would normally be open for operation or at any other time if permission is granted by the owner or operator, to issue an order to temporarily cease operation of an amusement device upon the determination that the device may be unsafe or may otherwise endanger the public and to accept and approve or deny requests for modifications of the rules of this chapter in accordance with the modification provisions of the USBC.

I. In accordance with subdivision 7 of § 36-137 of the Code of Virginia, the local building department shall collect a 2.0% levy of fees charged for permits under this chapter and transmit it quarterly to DHCD to support training programs of the Virginia Building Code Academy. Localities that maintain individual or regional training academies accredited by DHCD shall retain such levy.

13VAC5-31-85. Accidents involving serious injury or death.

A. If an accident involving the serious injury or death of a patron occurs, the operation of an amusement device shall cease and the local building department and DHCD shall be notified as soon as practicable, but in no case later than during the next working day. The operation of the device shall not resume until inspected by a private inspector or an inspector from the local building department, except where the owner or operator determines the cause was not related to malfunction or improper operation of the amusement device.

B. The owner or operator shall conduct an investigation of the accident including, at a minimum, an examination of the accident scene and interviews of any witnesses or persons involved in the accident. An accident investigation report shall be compiled which, at a

minimum, shall contain a summary of the investigation and a description of the device involved, including its serial number and date of manufacture, if available. The report shall be submitted to the local building department within 24 hours of the accident except that if the local building department is closed during that period, then the report shall be submitted with four hours of the reopening of the department.

C. Local building department personnel are authorized to investigate the accident and to issue an order to cease operation when warranted and to specify the conditions under which the device may resume operation. The amusement device shall be inspected prior to resuming operation either by an inspector from the local building department or by a private inspector and found to comply with this chapter.

Part III - Gravity Rides

13VAC5-31-180. General requirements.

A. The provisions of this part are specific to gravity rides and are in addition to other applicable provisions of this chapter.

B. A ride using carriers shall be designed and constructed to retain the passengers in or on a carrier during the operation of the ride and retain the carrier on or within the track, slide, or chute system during the operation of the ride.

C. A ride that conveys passengers not in or on a carrier shall be designed and constructed to retain the passengers within the chute or slide during the ride.

D. At each loading or unloading area, a hard surface which is other than earth and which is reasonably level shall be provided. The surface shall be large enough to accommodate the intended quantity of passengers.

E. Where loading or unloading platforms are elevated more than 30 inches from the adjacent areas, guard rails conforming to the USBC shall be provided.

F. Passengers shall not have to step up or down more than 12 inches from the loading or unloading surface to enter or exit the ride.

G. The frequency of departure of carriers or riders from the loading areas shall be controlled by a ride operator. The minimum distance between departures shall be determined by the designer of the specific ride.

H. When a passenger has control of the speed or course of the carrier, the passenger shall have a clear sight distance along the course of the ride long enough to allow the passenger to avoid a collision with another person or carrier.

I. The unloading area of the ride shall be designed and constructed to bring riders and carriers to a safe stop without any action by the rider.

J. There shall be attendants at the loading and unloading area when the ride is in use. However, where the physical structure of the ride is such that it is not capable of accommodating an attendant at both the loading and unloading area and the entire ride is visible and under the supervision of a single attendant, attendants at both the loading and unloading areas shall not be required.

K. If the entire course of the ride is not visible to the operator, additional persons with communications equipment shall be provided or approved visual surveillance equipment shall be installed along the course of the ride which is not visible to the operator.

L. Any moving or hot parts that may be injurious to the ride operator or the public shall be effectively guarded to prevent contact.

M. Fencing or adequate clearance shall be provided that will prevent the riders from contact with persons or nearby objects.

Part IV - Concession Go-Karts

13VAC5-31-190. General requirements.

In addition to other applicable requirements of this chapter, concession go-karts shall be operated, maintained and inspected in accordance with ASTM F2007.

Part V - Inflatable Amusement Devices

13VAC5-31-200. General requirements.

In addition to other applicable requirements of this chapter, inflatable amusement devices shall be operated, maintained and inspected in accordance with ASTM F2374.

Notwithstanding any requirements of this chapter to the contrary, a permit to operate an inflatable amusement device that is less than 150 square feet and in which the height of the patron containment area is less than 10 feet need not be obtained if the device has an unexpired certificate of inspection issued by a local building department in this Commonwealth, regardless of whether the device has been disassembled or moved to a new site.

Part VI - Artificial Climbing Walls

13VAC5-31-210. General requirements.

In addition to other applicable requirements of this chapter, artificial climbing walls shall be operated, maintained and inspected in accordance with ASTM F1159.

Notwithstanding any requirements of this chapter to the contrary, an artificial climbing wall may be moved, setup and operated without obtaining a permit provided the wall has a valid certificate of inspection issued by a local building department within the prior 90 days and the

expiration date of the wire ropes used with the device does not expire within that 90-day period.

Part VII - Bumper Boats

13VAC5-31-215. General requirements.

In addition to other applicable requirements of this chapter, bumper boats shall be operated, maintained and inspected in accordance with ASTM F2460.

Part VIII - Bungee Jumping

13VAC5-31-220. General requirements.

A. The provisions of this part are specific to bungee jumping and are in addition to other applicable provisions of this chapter.

B. Bungee jumping operations that are open to the public shall be permitted from structures designed for use as part of the bungee jumping operation. Bungee jumping from other types of structures, cranes or derricks is not permitted for public participation.

C. Bungee jumping activities that involve double jumping, sandbagging, catapulting or stunt jumping shall not be permitted to be open for public participation.

13VAC5-31-230. Bungee cords.

A. Bungee cords shall be tested by an approved testing agency or by an engineer licensed in Virginia. The following criteria shall be met:

1. Each lot of bungee cords shall have a minimum of 10%, but not less than one of the cords tested to determine the lowest ultimate tensile strength of the cords tested. A load versus elongation curve based on the test result shall be provided with each lot of bungee cords; and

2. The manufacturer shall specify the maximum number of jumps for which each cord or cord type is designed and the criteria for use of the cord.

B. Bungee cords shall be retired when the cords (i) exhibit deterioration or damage; (ii) do not react according to specifications; or (iii) have reached the maximum usage expressed in number of jumps as specified by the manufacturer. Bungee cords retired from use shall be destroyed immediately by cutting the cord into five-foot lengths.

13VAC5-31-240. Jump hardware.

Jump harnesses shall be either full body-designed, which includes a waist harness worn in conjunction with a chest harness, or ankle-designed with a link to a waist harness. All jump harnesses, carabineers, cables and other hardware shall be designed and manufactured for the purpose or designed or analyzed by an engineer licensed in Virginia and shall be used and maintained in accordance with the manufacturer's or engineer's instructions.

13VAC5-31-250. Structure requirements.

Structures constructed on site for bungee jumping activities shall be designed by an engineer licensed in Virginia. Structures manufactured for bungee jumping activities shall be analyzed by an engineer licensed in Virginia and assembled and supported in accordance with the manufacturer's instructions.

13VAC5-31-260. Operational and site requirements.

- A. Operators shall follow the criteria provided by the manufacturer for the use of bungee cords. A record of the number of jumps with each cord shall be maintained. All cords shall be inspected daily for wear, slippage, or other abnormalities unless the manufacturer specifies more frequent inspections.
- B. The jump master or site manager shall be responsible for determining the appropriate use of all bungee cords in relation to the weight of the jumper and height of the platform. Bungee cords shall be attached to the structure at all times when in the connection area.
- C. All harnesses shall be inspected prior to harnessing a jumper and shall be removed from service when they exhibit signs of excessive wear or damage. All carabineers shall be inspected daily and shall be removed from service when they exhibit signs of excessive wear or damage or fail to function as designed. The anchors shall be inspected daily and shall be replaced if showing signs of excessive wear.
- D. A secondary retrieval system shall be provided in all operations. A locking mechanism on the line shall be used to stop and hold the jumper in place after being pulled back to the jump platform in a retrieval system. A dead man's switch or locking mechanism that will stop the lowering action shall be used in a friction lowering system.
- E. The jump zone, preparation area and landing/recovery area shall be identified and maintained during bungee jumping activities. The landing/recovery area shall be accessible to emergency vehicles. Communication shall be maintained between all personnel involved with the jump.
- F. An air bag, a minimum of 10 feet by 10 feet, shall be used. The air bag shall be rated for the maximum free fall height possible from the platform during operation. The air bag shall be located immediately below the jump space. The landing area shall be free of spectators and debris at all times and shall be free of any equipment or personnel when a jumper is being prepared on the jump platform and until the bungee cord is at its static extended state. A place to sit and recover shall be provided adjacent to, but outside, the landing area where the jumper shall be allowed to recover.
- G. Where the jump space or landing area, or both, is over sea, lake, river, or harbor waters, the following shall apply:
 - 1. The landing water area shall be at least nine feet deep and a minimum of 10 feet by 10 feet or have a minimum of 15 feet in diameter if circular;

2. The jump space and landing area shall be free of other vessels, floating and submerged objects and buoys. A sign of approved size that reads "Bungee Jumping! Keep Clear" shall be fixed to buoys on four sides of the landing area;

3. The landing vessel shall be readily available for the duration of the landing procedures;

4. The landing vessel shall have a landing pad size of at least five feet by five feet within and lower than the sides of the vessel;

5. A landing vessel shall be available that can be maneuvered in the range of water conditions expected and will enable staff to pick up a jumper; and

6. One person may operate the landing vessel where the vessel is positioned without the use of power. A separate person shall operate the vessel where power is required to maneuver into or hold the landing position.

H. Where the landing area is part of a swimming pool or the landing area is specifically constructed for bungee jumping, the following shall apply:

1. Rescue equipment shall be available, such as a life ring or safety pole;

2. The jump space and landing area shall be fenced to exclude the public; and

3. Only the operators of the bungee jump and jumper shall be within the jump zone and landing areas.

I. Storage shall be provided to protect equipment from physical, chemical and ultra-violet radiation damage. The storage shall be provided for any current, replacement and emergency equipment and organized for ready access and shall be secure against unauthorized entry.

13VAC5-31-270. Management and personnel responsibilities.

A. All bungee jumping activities shall have a minimum of one site manager, one jump master and one ground operator to be present at all times during operation of the bungee jump.

B. The site manager is responsible for the following:

1. Controlling the entire operation;

2. Site equipment and procedures;

3. Determining whether it is safe to jump;

4. Selection of, and any training of personnel;

5. Emergency procedures; and

6. Maintaining records.

C. A jump master shall be located at each jump platform and shall have thorough knowledge of, and is responsible for, the following:

1. Overseeing the processing of jumpers, selection of the bungee cord, adjustment of the rigging, final check of jumper's preparation, and countdown for and observation of the jump;
2. Verifying that the cord is attached to the structure at all times when the jumper is in the jump area;
3. Rescue and emergency procedures; and
4. Ensuring that the number of jumps undertaken in a given period of time will allow all personnel to safely carry out their responsibilities.

D. The ground operator shall have knowledge of all equipment used and of jump procedures and shall have the following responsibilities:

1. Ensuring that the jumper is qualified to jump;
2. Assisting the jump master to prepare the jumper and attach the jumper to the harness and rigging;
3. Assisting the jumper to the recovery area; and
4. Maintaining a clear view of the landing area.

E. Each site shall have an operating manual that shall include the following:

1. Site plan, job descriptions (including procedures), inspections and maintenance requirements of equipment including rigging, hardware, bungee cords, harnesses, and lifelines; and
2. An emergency rescue plan.

F. The daily operating procedures shall be conducted in accordance with ASTM F770.

G. The qualification and preparation of jumpers shall include obtaining any pertinent medical information, jumper weight and a briefing of jumping procedures and safety instructions.

Part IX - Accessibility Requirements for Amusement Devices

13VAC5-31-280. Scope.

This part shall apply to newly designed and constructed amusement devices for permanent installation and does not apply to amusement devices regularly assembled or disassembled.

This part also does not apply to mobile, portable, or temporary amusement devices set up for short periods of time such as at traveling carnivals, state and county fairs, and festivals. For the purposes of this part, newly designed and constructed amusement devices are those that are new upon first use by patrons and the first permanent installation of the ride and would not include a ride that was moved within a park or to another park after several seasons of use.

13VAC5-31-290. Requirements.

Amusement devices subject to this part shall comply with applicable requirements of 36 CFR Part 1191 – Americans With Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities and ; Architectural Barriers Act (ABA) Accessibility Guidelines, 69 FR 44151-44455 (July 23, 2004).

TAB 7

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: Amusement Device Technical Advisory Comm. Representing: _____

Proposal Information

Code(s) and Section(s): VADR, Sections 20 and 75

Proposed Change (including all relevant section numbers, if multiple sections):

Change Section 13 VAC 5-31-20 by adding the following definition and Section 13 VAC 5-31-75 to read as follows:

13 VAC 5-31-20. Definitions.

A. The following words and terms when used in this chapter shall have the following meanings unless the context clearly indicates otherwise:

"Certificate of inspection" means the certificate or sticker for amusement devices distributed by DHCD.

(Remainder of section unchanged)

13 VAC 5-31-75. Local building department.

(no change to subsections A – D)

E. Local building department personnel shall examine the permit application within five days and issue the permit if all requirements are met. A certificate of inspection for each amusement device shall be issued when the device has been found to comply with this chapter by a private inspector or by an inspector from the local building department. It shall be the responsibility of the local building department to verify that the private inspector possesses a valid certificate of competence as an amusement device inspector from the Virginia Board of Housing and Community Development. In addition, local building department personnel shall be responsible for assuring that the certificate of inspection is posted or affixed on or in the vicinity of the device in a location visible to the public. Local building department personnel shall post or affix such certificates or permit the certificates to be posted or affixed by the private inspector. Permits shall indicate the length of time the device or devices will be operated at the site, clearly identify the device or devices to which it applies and the date of expiration of the permit. Permits shall not be valid for longer than one year.

(Remainder of section unchanged)

Supporting Statement (including intent, need, and impact of the proposal):

This proposal would require the use of the state sticker for amusement devices. In the existing regulation, the state sticker may be used or a locality may have their own sticker. In addition, the proposal clarifies that the local building department may allow the private inspector to post the sticker on the approved amusement device. The existing regulation permitted this practice, but only stated that the local department were to assure the certificate was posted on or near the device and didn't specifically address permitting the private inspectors to post the certificates, although it is common practice in many jurisdictions.

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: Amusement Device Technical Advisory Comm. Representing: _____

Mailing Address: _____

Email Address: _____ Telephone Number: _____

Proposal Information

Code(s) and Section(s): VADR, Section 30 _____

Proposed Change (including all relevant section numbers, if multiple sections):

Change Section 13 VAC 5-31-30 to read as follows:

13 VAC 5-31-30. Exemptions Devices covered and exempt.

A. The following devices, identified by name or description, when open to the public, shall be considered amusement devices subject to this chapter. The list is intended only to clarify questionable devices, while the definition of an "amusement device" in 13 VAC 5-31-20 is generally used to determine the applicability of this chapter.

1. Devices known as water walking balls, euro bubbles or similar devices;
2. Inflatable amusement devices;
3. Mechanical bulls;
4. Devices known as mall trains, shopping mall trains or electric trackless trains for malls; and
5. Zip lines.

B. The following equipment or devices shall not be considered amusement devices subject to this chapter:

1. Non-mechanized playground or recreational equipment such as swing sets, sliding boards, climbing bars, jungle gyms, skateboard ramps and similar equipment where no admission fee is charged for its use or for admittance to areas where the equipment is located;
2. Coin-operated rides designed to accommodate three or less passengers; and
3. Water slides or similar equipment used in community association, community club or community organization swimming pools.

Supporting Statement (including intent, need, and impact of the proposal):

This proposal is to assist local building departments in the determination of whether certain devices are amusement devices and to achieve more uniformity in the application of the regulation.

Submittal Information

Date Submitted: _____

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)

600 East Main Street

Suite 300

Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov

Fax Number: (804) 371-7092

Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: Amusement Device Technical Advisory Comm. Representing: _____

Mailing Address: _____

Email Address: _____ Telephone Number: _____

Proposal Information

Code(s) and Section(s): VADR, Section 75

Proposed Change (including all relevant section numbers, if multiple sections):

Change Section 13 VAC 5-31-75 to read as follows:

13 VAC 5-31-75. Local Building Department.

A. In accordance with §§ 36-98.3 and 36-105 of the Code of Virginia, the local building department shall be responsible for the enforcement of this chapter and may charge fees for such enforcement activity. The total amount charged for any one permit to operate an amusement device or devices or the renewal of such permit shall not exceed the following, except that when a private inspector is used, the fees shall be reduced by 50%:

1. \$25 for each kiddie ride covered by the permit;
2. \$35 for each circular ride or flat-ride less than 20 feet in height covered by the permit;
3. \$55 for each spectacular ride covered by the permit which cannot be inspected as a circular ride or flat-ride in subdivision 2 of this subsection due to complexity or height; and
4. \$150 for each coaster covered by the permit which exceeds 30 feet in height.

Notwithstanding the above, the local building department shall be permitted to increase the fees up to 50% when requested to perform weekend or after-hour inspections.

Remainder of section unchanged)

Supporting Statement (including intent, need, and impact of the proposal):

Private inspectors are not always available to perform inspections on weekends and after hours, so if the owner or operator of an amusement device requests the local building department to do an after-hour or weekend inspection and the building department is willing to do so, they should be able to charge up to 50% more to offset the cost of paying the local inspector overtime wages.

Submittal Information

VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: Amusement Device Technical Advisory Comm. Representing: _____

Mailing Address: _____

Email Address: _____ Telephone Number: _____

Proposal Information

Code(s) and Section(s): VADR, Sections 75D, 200 and 210

Proposed Change (including all relevant section numbers, if multiple sections):

Change Sections 13 VAC 5-31-75D, 200 and 210 as shown below:

13 VAC 5-31-75. Local Building Department.

(Subsections A – C unchanged)

D. Notwithstanding the provisions of subsection C of this section, a permit application is not required for a kiddie ride that has an unexpired a certificate of inspection issued by any local building department in this Commonwealth within a one year prior to the dates the kiddie ride is to be used. In such cases, the local building department shall be notified prior to the operation of the kiddie ride and the information required on a permit application as listed in subsection C of this section shall be provided to the local building department.

(Remainder of section unchanged)

13 VAC 5-31-200. General requirements.

In addition to other applicable requirements of this chapter, inflatable amusement devices shall be operated, maintained and inspected in accordance with ASTM F2374.

Notwithstanding any requirements of this chapter to the contrary, a permit to operate an inflatable amusement device that is less than 150 square feet and in which the height of the patron containment area is less than 10 feet need not be obtained if the device has an unexpired a certificate of inspection issued by a local building department in this Commonwealth within a one year period prior to the dates the inflatable amusement device is to be used, regardless of whether the device has been disassembled or moved to a new site.

13 VAC 5-31-210. General requirements.

In addition to other applicable requirements of this chapter, artificial climbing walls shall be operated, maintained and inspected in accordance with ASTM F1159.

Notwithstanding any requirements of this chapter to the contrary, an artificial climbing wall may be moved, setup and operated without obtaining a permit provided the wall has a valid certificate of inspection issued by a local building department in this Commonwealth within the prior 90 days and the expiration date of the wire ropes used with the device does not expire within that 90-day period.

Supporting Statement (including intent, need, and impact of the proposal):

The changes are to clarify that amusement devices using the kiddie ride, inflatable or rock-climbing wall permit exception must already have a certificate of inspection. The use of the words "unexpired" and "valid" in the existing regulation could be misleading since a certificate of inspection for a permitted amusement device does not automatically last for one year, but rather is only for the period of time the permit is issued (see 13 VAC 5-31-75E). The exceptions for kiddie rides, inflatables and rock-climbing walls are to allow a certificate to be extended for up to a year (or 90 days in the case of rock-climbing walls). The new language is just to clarify what the terms "unexpired" and "valid" really mean.

Submittal Information

Date Submitted: _____

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
300 East Main Street
Suite 300
Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: Amusement Device Technical Advisory Comm. Representing: _____

Proposal Information

Code(s) and Section(s): VADR, Section 75

Proposed Change (including all relevant section numbers, if multiple sections):

Add Subsection J to Section 13 VAC 5-75 to read as follows:

13 VAC 5-31-75. Local building department.

(no change to subsections A – I)

J. In accordance with Section 36-98.1 of the Code of Virginia, the Virginia Department of General Services (DGS) shall function as the local building department for the application of this chapter to amusement devices located on state-owned property. In accordance with Sections 36-98.2 and 36-114 of the Code of Virginia, appeals of the application of this chapter by the DGS shall be made directly to the State Building Code Technical Review Board (Technical Review Board), established under Section 36-108 of the Code of Virginia. Further, as a condition of this chapter, such appeals shall be filed within 14 calendar days after receipt of the decision of DGS.

Supporting Statement (including intent, need, and impact of the proposal):

This proposal is to clarify the application of the chapter to amusement devices operated on state-owned property.

Submittal Information

Date Submitted: _____

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
300 East Main Street
Suite 300
Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7140 or (804) 371-7150



VIRGINIA DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
DIVISION OF BUILDING AND FIRE REGULATION

Code Change Form for the 2012 Code Change Cycle

Code Change Number: _____

Proponent Information

(Check one): ☐ Individual ☐ Government Entity ☐ Company

Name: Amusement Device Technical Advisory Comm. Representing: _____

Mailing Address: _____

Email Address: _____ Telephone Number: _____

Proposal Information

Code(s) and Section(s): VADR, Section 75

Proposed Change (including all relevant section numbers, if multiple sections):

Add Subsection J to Section 13 VAC 5-75 to read as follows:

13 VAC 5-31-75. Local building department.

no change to subsections A – I)

I. In accordance with Section 36-98.3 of the Code of Virginia and 13 VAC 5-31-10 B, the procedures for violations of this chapter shall be as prescribed in the USBC.

Supporting Statement (including intent, need, and impact of the proposal):

This proposal is to clarify the procedural requirements for handling violations of the VADR as state law provides that the USBC is applicable to the extent that the VADR does not set out differing requirements.

Submission Information

Date Submitted: _____

The proposal may be submitted by email as an attachment, by fax, by mail, or by hand delivery.

Please submit the proposal to:

DHCD DBFR TASO (Technical Assistance and Services Office)
100 East Main Street
Suite 300
Richmond, VA 23219

Email Address: taso@dhcd.virginia.gov
Fax Number: (804) 371-7092
Phone Numbers: (804) 371-7140 or (804) 371-7150



TAB 8

Ok err
MEMORANDUM OF AGREEMENT
between the
Board of Housing and Community Development
and the
Virginia Department of Health

In accordance with § 36-97 *et seq.* and § 32.1-167 *et. seq.* of the *Code of Virginia*, the Virginia Department of Health (hereafter referred to as the "Department") and the Board of Housing and Community Development (hereafter referred to as the "BHCD") on this November 19, 2012, agrees to coordinate the Uniform Statewide Building Code (hereafter referred to as the "USBC") and the *Virginia Waterworks Regulations* (hereafter referred to as the "*Regulations*"). The USBC shall not supersede the *Regulations* as stated in § 36-98 of the *Code of Virginia*. The parties agree to the following.

1. That adoption and promulgation of the USBC is the responsibility of the BHCD; that enforcement of the USBC is the responsibility of the local building department; and that adoption, promulgation and enforcement of the *Regulations* is the responsibility of the Department.
2. That the jurisdiction of the USBC includes all buildings, structures, and equipment (as defined in § 36-97 of the *Code of Virginia*) up to the point of connection to the water meter; and that the jurisdiction of the *Regulations* includes the meter, all public water supply mains, treatment facilities, and raw water collection and transmission facilities. Where no meter is installed, the point of demarcation between the jurisdiction of the USBC and of the *Regulations* is the point of connection to the public water supply main; or, in the case of an owner of both public water supply system and the building served, the point of demarcation is the point of entry into the building.

Exception: Whenever a building or structure is utilized to house portions of a waterworks, as determined by the Department, the *Regulations* shall apply to all such water treatment, storage, and pumping facilities and the USBC shall apply to the building, structure, and equipment as defined in § 36-97 of the *Code of Virginia*.

3. That both the USBC and the *Regulations* will include a clear reference to jurisdiction of the other document.
4. That the *Regulations* require each waterworks owner to have a cross-connection control and backflow prevention program consistent with the *Regulations*, and that this program requires as a minimum, an approved containment device at each service connection consistent with any existing or potential health, pollution, or system hazard to the waterworks. Point-of-use isolation protection devices may be installed in place of service containment devices when in accordance with the waterworks' approved backflow prevention program. Point-of-use isolation devices shall comply with applicable standards of the USBC.

5. That the building official is required by the USBC to be assured that the water supply to a building is safe and of adequate capacity before issuing a building permit. Building permits involving a new water connection or extension of an existing connection to a public water supply main shall not be issued when the Department has notified the building official in writing that the water supply system is at or above its permitted capacity.
6. That appropriate amendments, additions, or deletions will be made to the Regulations and to the USBC to insure that there is no jurisdictional conflict between the two documents.
7. That it is the intention of both the BHCD and the Department to cooperate with each other in resolving any technical conflicts between the Regulations and the USBC, and in developing and implementing operational procedures to insure and promote a constructive working relationship between building and health officials.
8. That, except in matters of imminent danger to public health or safety, whenever conflicts or disagreements arise between the two agencies or their staffs, all appropriate regulatory procedures will be exhausted prior to any judicial action.
9. This Agreement may be amended or terminated by mutual consent of the parties.

The undersigned agree to the conditions of this Agreement.

William C. Shelton
Director,
Department of Housing and Community Development
for the Board of Housing and Community Development

Maureen E. Dempsey, MD, FAAP
Acting Commissioner,
Virginia Department of Health
for the Board of Health

MEMORANDUM OF AGREEMENT

<INSERT DATE>

Between the Virginia Department of Housing and Community Development (VDHCD)
and the Virginia Department of Health (VDH)

In accordance with Va. Code §§ 36-98 et seq., 32.1-12, and 32.1-163 et seq., the VDH and the VDHCD agree to coordinate jurisdictional responsibilities through the Virginia Uniform Statewide Building Code (13 VAC 5-62, the "building code") and applicable VDH regulations ("VDH regulations")¹ as follows:

Codes and Regulations: Adoption and Enforcement

1. VBHCD adopts and promulgates the building code. The local building department enforces the building code.
2. The Board of Health adopts and promulgates VDH regulations. The Board of Health and VDH jointly enforce VDH regulations.

Definitions:

"Alternative Discharging System" means a treatment works that requires a permit from VDH pursuant to 12 VAC5-640.

"Onsite Sewage System" means a conventional or alternative onsite sewage system as defined in Va. Code 32.1-163, which requires a permit from VDH pursuant to 12 VAC5-610 or 12 VAC5-613.

"Treatment works" means any device or system used in the storage, treatment, disposal or reclamation of sewage or combinations of sewage and industrial wastes, including but not limited to pumping, power and other equipment and appurtenances, septic tanks, and any works, including land, that are or will be (i) an integral part of the treatment process or (ii) used for ultimate disposal of residues or effluents resulting from such treatment.

"Graywater system" means treatment works that disperses untreated wastewater from bathtubs, showers, lavatory fixtures, wash basins, washing machines, and laundry tubs. A graywater system does not include wastewater from toilets, urinals, kitchen sinks, dishwashers, or laundry water from soiled diapers.

¹ VDH implements the Sewage Handling and Disposal Regulations (12 VAC 5-610); Alternative Discharging Sewage Treatment Regulations for Individual Single Family Dwellings (12 VAC 5-640); Regulations for Alternative Onsite Sewage systems (12 VAC5-613); Private Well Regulations (12 VAC5-630)

Treatment works applicability

1. The building code will apply to all internal service plumbing components of a treatment works up to the point of connection of the building drain to the building sewer.
2. The building code will apply to electrical and structural components of a treatment works, except as provided below.
 - a. The VDH regulations will apply to control panels for the treatment works and its functional treatment components, including electrical devices for pump stations, master disconnect switches, manual override switches, motor control panels, and separate motor control centers when specified by the designer or required by VDH.
 - b. VDH regulations and policies do not consider cord and plug connections associated with a treatment works. If allowed by the building code, cord and plug connections for the treatment works must be located in a weather proof box when outside of the wet well to prevent exposure to weather conditions.
3. The VDH regulations will apply to the treatment and functional components of a treatment works regardless of location (inside or outside of the building or structure), except as provided below.
 - a. The building code will apply to graywater systems not regulated by VDH, such as building or structures connected to a public sewer system.
4. The VDH regulations will apply to components of a treatment works that are external to the building or structure. External components include the septic tank, pump station, distribution box or mechanism, piping, or additional treatment devices such as blowers and associated electrical devices.

Reviews pursuant to Va. Code § 32.1-165

No county, city, town or employee thereof shall issue a building permit for the construction of a new building designed for human occupancy without the prior written notification of the State Health Commissioner or agent that safe, adequate, and proper sewage treatment is or will be made available to such building.

1. VDH approves a treatment works three ways: (1) a certification letter that recognizes a treatment works can be designed sometime in the future, which does not expire; (2) a subdivision letter that describes future treatment works for each subdivision lot, which also does not expire; and (3) a construction permit, which describes the actual construction of the treatment works and is valid for 18 months with one 18 month renewal under certain conditions.

2. The local building official may use the certification letter, subdivision letter, or construction permit to issue a building permit. The local building official understands that a treatment works cannot be constructed until the local health department issues a construction permit. The footprint of the building or structure cannot interfere with the setbacks required by the VDH regulations.
3. The local building official will contact the local health department as provided by local and routine processes, which might differ in various jurisdictions, upon finding that issuance of the building permit might have an impact on the function of an existing treatment works already installed. If VDH requests an application for review of the installed treatment works, then the application must be completed before VDH can determine whether the treatment works is acceptable.
 - a. If the wastewater flow, capacity, or effluent strength increases for the existing treatment works, then the building official must rely on a valid construction permit from VDH before issuing the building permit. A certification letter or subdivision approval will not be sufficient.
4. VDH will only approve a treatment works if it complies with VDH regulations and associated policies. VDH will notify the local building official as soon as practical whether a treatment works was installed correctly by issuance of an operation permit. The local building official will not issue a certificate of occupancy until after VDH has issued the operation permit.

Conflict Resolution

Both VDH and VDHCD will cooperate in resolving any technical conflicts between VDH regulations and the building code. The agencies will develop and implement procedures as needed to ensure collaboration between local building officials and local health departments. Appropriate amendments, edits, additions, or deletions will be made to the VDH regulations and the building code when necessary. When conflicts or disagreements arise between the two agencies or their staff, all appropriate regulatory procedures will be exhausted prior to any judicial action, except in cases of imminent danger.

This Agreement may be amended or terminated by mutual consent of the parties. The undersigned agree to the Conditions of this Agreement.

William, C. Shelton, Director
Department of Housing and
Community Development

Maureen Dempsey
Acting State Health Commissioner
Department of Health